

CURVE	LENGTH	RADIUS	DELTA
C1	63.04'	392.00'	09°12'49"
C2	184.73'	303.00'	34°55'50"
C3	39.24'	50.00'	44°57'39"
C4	37.12'	50.00'	42°32'01"
C5	14.91'	13.00'	65°41'51"
C6	12.05'	22.00'	57°25'28"
C7	11.84'	39.50'	17°10'38"
C8	23.56'	15.00'	90°00'00"
C9	7.98'	13.00'	35°10'48"
C10	29.52'	32.00'	52°51'02"
C11	31.13'	33.00'	54°02'40"

NOTE:
THE DEVELOPER/ENGINEER ACKNOWLEDGE THAT THE SIZE OF THE WATER QUALITY AND/OR FLOOD CONTROL BASIN WILL BE REVIEWED AT THE IMPROVEMENT PLAN STAGE. SIGNIFICANT CHANGE OF THE SIZE OF THE BASIN FROM WHAT IS SHOWN ON THE TENTATIVE MAP MAY RESULT IN REVISIONS TO THE TENTATIVE MAP BY THE DEPARTMENT OF REGIONAL PLANNING.

NOTE:
ALL EXISTING STRUCTURES TO BE REMOVED

NOTE:
ALL DRAINAGE DEVICES WILL BE MAINTAINED BY PROPERTY OWNER

NOTE:
THE STRUCTURAL SECTION FOR FIRE LANES WILL BE CAPABLE TO SUBJECT LIVE LOAD OF 75,000 LBS

LOT 1:
GROSS AREA = 1.21 Acres
NET AREA = 1.19 Acres

LINE	LENGTH	BEARING
L1	15.97'	N64°34'09"E
L2	4.04'	S49°44'00"E
L3	21.93'	S40°16'00"W

TENTATIVE TRACT NO. 072684

(FOR CONDOMINIUM PURPOSES)


EXHIBIT "A"

LOCATED IN THE UNINCORPORATE TERRITORY OF THE COUNTY OF LOS ANGELES, STATE OF CALIFORNIA

PARKING SUMMARY

PARKING SUMMARY PER LOT				
LOT NUMBER	NO. OF UNITS	GARAGE SPACES	SURFACE PARKING SPACES	HANDICAP SPACES
1	20	40	3	1
2	33	66	13	1
TOTAL	53	106	16	2
RATIO	2/UNIT	0.33/UNIT	2% OF TOTAL	

PARKING REQUIRED (TOTAL)		PARKING PROVIDED	
UNIT TYPE	SPACES PER UNIT	PARKING TYPE	SPACES
2+BR	2/UNIT	GARAGE	106
QUEST	1 PER 4	QUEST(INCL. 2 HC)	18
TOTAL	119	TOTAL	124



VICINITY MAP
NTS

PROJECT DESCRIPTION

- NO. OF LOTS: 2
- NO. DWELLING UNITS: 53
- NO. OF BUILDING PROPOSED: 12
- APN: 8030-008-011 & 8030-023-024

ADA UNITS	REQUIRED	PROVIDED
ADA UNITS	5.3	6
LOT 1	2	4
LOT 2	4	2

ZONING: (EXISTING)
EXISTING PLAN CATEGORIES
OPEN SPACE (OS), AREA= 2.46 Acres AND
LOW DENSITY RESIDENTIAL (1), AREA= 1.21 Acres

EXISTING ZONING DESIGNATIONS
A-1 (AREA=2.46 Acres) AND
C-3-BE (AREA=1.21 Acres)

ZONING: (PROPOSED)
PROPOSED LAND USE CATEGORY
CATEGORY 3 (MEDIUM DENSITY RESIDENTIAL-12-22 DWELLING UNITS/PER GROSS ACRE)

PROPOSED ZONING
R3-DP (LIMITED MULTIPLE RESIDENCE DEVELOPMENT PROGRAM)

UTILITIES:
SEWER: CONSOLIDATED SEWER MAINTENANCE DISTRICT OF LOS ANGELES COUNTY
COUNTY OF LOS ANGELES DEPARTMENT OF PUBLIC WORKS
SEWER MAINTENANCE DIVISION
P.O. BOX 1475
ALAMOGA, CA 91802-1475
(626) 300-3399


WATER: ORCHARD DALE WATER DISTRICT
13819 EAST TELEGRAPH ROAD,
WHITTIER, CA 90604
(562) 941-0114

BASIS OF BEARING
THE BEARING SHOWN HEREON ARE BASED ON THE BEARING OF TELEGRAPH ROAD BEING NORTH 49°44'00" WEST AS SHOWN ON THE RECORD OF SURVEY RECORDED IN BOOK 55 PAGE 48 OF MAPS, RECORDS OF LOS ANGELES COUNTY, STATE OF CALIFORNIA.

FLOOD ZONE DESIGNATION
FLOOD ZONE: X
FLOOD MAP NO.: 06037C1841F
COMMUNITY PANEL NO.: 1841
COMMUNITY NO.: 065043
DATE OF MAP: SEPTEMBER 26, 2008

BENCHMARK
BM# Y 8224
ELEV.: 139.832
(SANTA FE QUAD 2005)

L&T IN NLY CB 300M(FT) ELY/O BCR @ NE COR VICTORIA AVE & TELEGRAPH RD



EARTHWORK QUANTITIES

DESCRIPTION	CUT	FILL
EARTHWORK	9,000 CY	3,500 CY
OVEREXCAVATION	10,400 CY	11,100 CY
SUBSIDENCE	570 CY	
SHRINKAGE	560 CY	
EXPORT		3,670 CY
TOTAL	19,400 CY	10,400 CY

DIRT DUMP LOCATION : SAVAGE CANYON LAND FILL

LEGAL DESCRIPTION



THE LAND REFERRED TO HEREIN BELOW IS SITUATED IN THE UNINCORPORATED AREA, COUNTY OF LOS ANGELES, STATE OF CALIFORNIA, AND IS DESCRIBED AS FOLLOWS:

LOT 1:
A PORTION OF PARCEL 1 IN THE COUNTY OF LOS ANGELES, STATE OF CALIFORNIA, AS SHOWN ON THE RECORD OF SURVEY FILED IN BOOK 55, PAGES 48 AND 49 OF RECORDS OF SURVEY, IN THE OFFICE OF THE COUNTY RECORDER OF SAID COUNTY DESCRIBED AS FOLLOWS:
BEGINNING AT THE NORTHEAST CORNER OF SAID PARCEL AS SHOWN ON SAID RECORD OF SURVEY; THENCE NORTH 49°44'00" WEST 20.00 FEET ALONG THE NORTHEASTERN LINE OF SAID PARCEL TO THE TRUE POINT OF BEGINNING, SAID NORTHEASTERN LINE ALSO BEING PARALLEL TO THE TRUE POINT OF BEGINNING, SAID NORTHEASTERN LINE ALSO BEING PARALLEL TO THE CENTERLINE OF TELEGRAPH ROAD (FORMERLY ANAHEIM-TELEGRAPH ROAD) AS SHOWN ON THE SAID RECORD OF SURVEY; THENCE NORTH 49°44'00" WEST 150.00 FEET ALONG THE SAID NORTHEASTERN LINE OF PARCEL 1 TO THE BEGINNING OF A CURVE CONCAVE TO THE SOUTH HAVING A RADIUS OF 25.00 FEET; THENCE NORTHWESTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 90°00'00", AN ARC DISTANCE OF 39.27 FEET; THENCE SOUTH 40°16'00" WEST 250.00 FEET ALONG THE EASTERN LINE OF PRIVATE STREET PER SAID RECORD OF SURVEY TO THE BEGINNING OF A CURVE CONCAVE TO THE EAST HAVING A RADIUS OF 15.00 FEET; THENCE SOUTHWESTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 90°00'00", AN ARC DISTANCE OF 23.56 FEET TO THE NORTHERLY LINE OF PRIVATE STREET SHOWN ON SAID RECORD OF SURVEY; THENCE SOUTH 49°44'00" EAST 168.00 FEET ALONG THE NORTHERLY LINE OF SAID PRIVATE STREET; THENCE NORTH 40°16'00" EAST 290.00 FEET TO THE TRUE POINT OF BEGINNING.

ALSO EXCEPTING THEREFROM ALL OIL, GAS AND OTHER HYDROCARBONS AND MINERALS IN AND UNDER AND PRODUCE THEREFROM FROM THE SAID LAND NOT SHOWN AS "MINERAL RIGHTS" AS RESERVED BY HUGES BROS. TILE AND MANTEL COMPANY, IN DEED RECORDED MAY 26, 1952 IN BOOK 39017 PAGE 240, OFFICIAL RECORDS.

LOT 2:
A PORTION OF LOT 4 OF TRACT 3014 IN THE COUNTY OF LOS ANGELES, STATE OF CALIFORNIA AS PER MAP RECORDED IN BOOK 36, PAGE 52, IN THE OFFICE OF THE COUNTY RECORDER OF SAID COUNTY DESCRIBED AS FOLLOWS:
BEGINNING AT A POINT ON THE NORTHEASTERN LINE OF SAID LOT 4, A DISTANT NORTH 49°44'00" WEST 2562.90 FEET FROM THE NORTHEAST CORNER OF SAID LOT, SAID POINT BEING ON THE SOUTHWESTERN LINE OF ANAHEIM-TELEGRAPH ROAD (50 FEET WIDE), SAID POINT ALSO BEING THE POINT OF BEGINNING OF PARCEL 3 AND NORTHEAST CORNER OF PARCEL 2 AS DESCRIBED IN DEED RECORDED DECEMBER 28, 1960 IN BOOK 4052, PAGES 56 TO 66 OF OFFICIAL RECORDS; THENCE CONTINUING ALONG THE NORTHEASTERN LINE OF SAID LOT 4 NORTH 49°44'00" WEST 78.43 FEET; THENCE LEAVING SAID NORTHEASTERN LINE OF SAID LOT 4 SOUTH 40°16'00" WEST 63.06 FEET; THENCE SOUTH 33°37'15" EAST 109.19 FEET TO THE BEGINNING OF A CURVE CONCAVE TO THE NORTHEAST HAVING A RADIUS OF 392.00 FEET; THENCE SOUTHEASTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 09°06'33" AN ARC DISTANCE OF 62.32 FEET TO THE EASTERLY LINE OF PARCEL 2 AS DESCRIBED IN DEED RECORDED DECEMBER 28, 1960 IN BOOK 4052, PAGES 56 TO 66 OF OFFICIAL RECORDS; SAID EASTERLY LINE ALSO BEING THE WESTERN LINE OF PARCEL 3 AS DESCRIBED IN DEED RECORDED DECEMBER 28, 1960 IN BOOK 4052, PAGES 56 TO 66 OF OFFICIAL RECORDS; THENCE CONTINUING SOUTHEASTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 00°06'15" AN ARC DISTANCE OF 0.71 FEET TO THE BEGINNING OF A COMPOUND CURVE CONCAVE TO THE SOUTHWEST HAVING A RADIUS OF 303.00 FEET; THENCE SOUTHEASTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 34°55'50" AN ARC DISTANCE OF 184.73 FEET TO THE BEGINNING OF A COMPOUND CURVE CONCAVE TO THE NORTHWEST HAVING A RADIUS OF 50.00 FEET; THENCE SOUTHWESTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 44°57'39" AN ARC DISTANCE OF 39.24 FEET TO THE BEGINNING OF A CURVE CONCAVE TO THE SOUTHWEST HAVING A RADIUS OF 50.00 FEET; THENCE SOUTHWESTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 42°32'01" AN ARC DISTANCE OF 37.12 FEET; THENCE SOUTH 05°08'26" EAST 23.81 FEET; THENCE SOUTH 40°16'00" WEST 96.17 FEET; THENCE SOUTH 49°44'00" EAST 125.52 FEET TO THE EASTERLY LINE OF SAID PARCEL 3 AS DESCRIBED IN DEED RECORDED DECEMBER 28, 1960 IN BOOK 4052, PAGES 56 TO 66 OF OFFICIAL RECORDS; SAID LINE ALSO BEING THE WESTERN LINE OF PARCEL 9 AS SHOWN ON RECORD OF SURVEY FILED IN BOOK 55, PAGES 48 AND 49 OF RECORD OF SURVEYS OF SAID COUNTY; THENCE CONTINUING SOUTH 49°44'00" EAST 44.25 FEET; THENCE NORTH 64°34'09" EAST 15.97 FEET TO THE BEGINNING OF A CURVE CONCAVE TO THE SOUTH HAVING A RADIUS OF 13.00 FEET; THENCE EASTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 65°41'51" AN ARC DISTANCE OF 14.91 FEET; THENCE SOUTH 49°44'00" EAST 4.04 FEET TO THE BEGINNING OF A NON-TANGENT CURVE CONCAVE TO THE SOUTH EAST HAVING A RADIUS OF 22.00 FEET; RADIAL THROUGH THE POINT BEING NORTH 55°19'46" WEST; THENCE NORTHEASTERLY ALONG SAID CURVE AN ARC DISTANCE OF 22.05 FEET TO THE BEGINNING OF A REVERSE TO CURVE CONCAVE TO THE NORTH HAVING A RADIUS OF 30.50 FEET; THENCE EASTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 17°10'38" AN ARC DISTANCE OF 11.84 FEET TO THE WESTERN LINE OF PRIVATE DRIVE AS SHOWN ON SAID RECORD OF SURVEY FILED IN BOOK 55, PAGES 48 AND 49 OF RECORDS OF SURVEY; THENCE NORTH 40°16'00" EAST 281.07 FEET ALONG THE SAID WESTERN LINE OF PRIVATE DRIVE TO THE BEGINNING OF A CURVE CONCAVE TO THE WEST HAVING A RADIUS OF 25.00 FEET; THENCE NORTHWESTERLY ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 90°00'00" AN ARC DISTANCE OF 39.27 FEET TO THE NORTHEASTERN LINE OF SAID PARCEL 9; THENCE NORTH 49°44'00" WEST 57.90 FEET ALONG THE NORTHEASTERN LINE OF SAID PARCEL 9; THENCE NORTH 40°16'00" EAST 25.00 FEET ALONG THE PROLONGATION OF THE WESTERN LINE OF SAID PARCEL 9 TO A POINT ON THE NORTHEASTERN LINE OF SAID LOT 1; THENCE NORTH 49°44'00" WEST 428.62 FEET ALONG THE NORTHEASTERN LINE OF SAID LOT 1 TO THE POINT OF BEGINNING.

EXCEPTING THEREFROM THAT PORTION DESCRIBED AS PARCEL 32-42 ACQUIRED BY THE COUNTY OF LOS ANGELES IN FINAL ORDER OF CONDEMNATION RECORDED SEPTEMBER 16, 1969 AS INSTRUMENT NO. 2186, IN OFFICIAL RECORDS OF LOS ANGELES COUNTY.



ENGINEER
DMS CONSULTANTS, INC.
CIVIL ENGINEERS
12371 Leavitt St., 2025 Golden Grove CA 92840 P: 714-740-8840 F: 714-740-8842
SURENDER DEWAN RCE 34559 EXP. 09/30/15

OWNER
CANDLEWOOD COUNTRY CLUB
A CALIFORNIA NON-PROFIT CORPORATION
14000 Telegraph Rd
Whittier, CA.

DEVELOPER:
BRANDYWINE HOMES
16580 Aston-Irvine, CA 92606
Tel: (949) 296-2400 Fax: (949) 296-2420

EXHIBIT "A" 14000 TELEGRAPH ROAD, WHITTIER, CA-90604
MAJOR LAND DIVISION
TENTATIVE TRACT NO. 072684
(FOR CONDOMINIUM PURPOSES)
LOCATED IN THE UNINCORPORATE TERRITORY OF THE COUNTY OF LOS ANGELES, STATE OF CALIFORNIA
DATE: 11/19/14 SHEET 1 OF 1