CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD SAN DIEGO REGION

2375 Northside Drive, Suite.100, San Diego, CA 92108 Phone (619) 516-1990 • Fax (619) 516-1994 http://www.waterboards.ca.gov/sandiego/

Clean Water Act Section 401 Water Quality Certification and Waste Discharge Requirements for Discharge of Dredged and/or Fill Materials

Reg. Meas. ID: 421790

Place ID: 847816

Person ID: 554133

Party ID: 39658

PROJECT: FY 19 Montezuma Creek Channel Maintenance

MMP Map 66 Project

Certification Number R9-2018-0107

WDID: 9000003313

APPLICANT: City of San Diego

2781 Caminito Chollas MS #46

San Diego, CA 92105

ACTION:

☑ Order for Low Impact Certification	☐ Order for Denial of Certification
☐ Order for Technically-conditioned Certification	☐ Waiver of Waste Discharge Requirements
☑ Enrollment in SWRCB GWDR Order No. 2003-017-DWQ	☐ Enrollment in Isolated Waters Order No. 2004-004-DWQ

PROJECT DESCRIPTION

An application dated May 23, 2018 was submitted by the City of San Diego (hereinafter Applicant), for Water Quality Certification pursuant to section 401 of the Clean Water Act (33 U.S.C. § 1341) for the proposed FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Project (Project). The Applicant has also applied for Clean Water Act section 404 Nationwide Permit Nos. 18 and 33 from the United States Army Corps of Engineers for the Project (USACE File SPL-2018-00362-SRR.).

The Project consists of the installation of a check dam, the installation of a row of fence posts to serve as a debris catcher, the removal of palm trees with stumps left in place, and the repair of broken and missing concrete in the Montezuma Channel within the City of San Diego, San Diego County, California between 4891 and 4896 54th Street. The Project is needed to decrease tailwater conditions caused by an undersized culvert that currently decreases channel capacity to less than a 2-year storm event. The Project's center readings are at latitude 32.767527 and longitude -117.080787. The Applicant has paid all required fees for this Certification in the amount of \$1500.00. On August 23, 2018, the San Diego Water Board provided public notice of the Project application pursuant to California Code of Regulations, title 23, section 3858 by posting information describing the Project on the San Diego Water Board's web site and providing a period of twenty-one days for public review and comment. No comments were received.

- 2 -

The Applicant proposes to install a check dam to slow velocity and prevent erosion, install a row of fence posts to act as a debris catcher, remove palm trees, and repair broken and missing concrete within an earthen and concrete lined channel.

The check dam is proposed to be 2.75 feet in height and installed in the upstream earthen portion of the channel. It would be constructed by imbedding six steel posts and two steel bollards in concrete foots and placing chain link fencing with solar resistant geotextile fabric on the upstream side of the fencing. Sediment is expected to settle in on the upstream side of the check dam, which would slow the velocity of the water and allow for additional infiltration. Over time, sediment would continue to accumulate and level out in front of the check dam, providing an environment for vegetation to grow. It is expected that vegetation would grow in the settled sediment and eventually surround and cover the check dam, obscuring it from view and allowing it to blend naturally into the channel.

Downstream of the check dam the applicant proposes to install six steel fence posts (but no fence fencing) to collect and prevent large sized debris such as palm tree stumps from entering and clogging the undersized culvert.

The applicant proposes to cut down the down the existing palm trees within the earthen channel, but leave 2-foot-tall stumps intact to decrease channel velocities. Within the concrete portion of the channel, one existing palm will be completely removed and the crack in the concrete would be repaired.

Diversion pumps will be placed at the upstream and downstream ends of the project area. Water will be pumped around the project area in a pipe and discharged downstream of the project area. Heavy equipment will be used within the channel reach for installation of the check dam, posts, and removal of cut palm trees.

The project will permanently impact 0.075 acre (194 linear feet) of Wetland Waters of the United States and/or State. Of the 0.075 acre of permeant impact, 0.001 acre is from the placement of fill for the check dam and the debris catcher. The additional 0.074 acre of impact is from the removal of palm trees. The project will temporarily impact 0.017 acre (44 linear feet) of wetland waters of the Unites States and/or State and 0.004 acre of non-wetland waters of the United States and/or State. No compensatory mitigation will be required for the impacts to the 0.074 acre of wetland waters from the removal of palm trees.

Receiving waters potentially affected by the Project are protected in accordance with water quality standards in the *Water Quality Control Plan for the San Diego Basin (9)* (Basin Plan). This Certification authorizes permanent and temporary impacts to waters of the United States and /or State affected by the Project and requires compensatory mitigation to offset adverse impacts as described in section VI of the Certification. The temporary impacts will be restored by the Applicant to pre-Project conditions and do not include physical loss of aquatic resource area or degradation of ecological conditions. Compensatory mitigation to offset the permanent loss of 0.001 acre of jurisdictional waters will be achieved through the rehabilitation credits form the Applicant's Advanced Permittee Mitigation Site located at the Stadium Wetland Mitigation Project along the San Diego River. Mitigation will occur at a 2:1 ratio for the loss of

FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Project Certification No. R9-2018-0107

0.001 acre of wetlands through 0.002 acre of rehabilitation. Based on all of these considerations, the Applicant's compliance with the terms and conditions of this Certification will ensure that the water quality standards for all waters of the United States and/or State impacted by the Project are met.

TABLE OF CONTENTS

I.	STANDARD CONDITIONS	5
II.	GENERAL CONDITIONS	
III.	PROJECT IMPACTS AND COMPENSATORY MITIGATION	8
IV.	MONITORING AND REPORTING REQUIREMENTS	g
٧.	NOTIFICATION REQUIREMENTS	12
VI.	CALIFORNIA ENVIRONMENTAL QUALITY ACT COMPLIANCE	13
VII.	SAN DIEGO WATER BOARD CONTACT PERSON	14
VIII.	WATER QUALITY CERTIFICATION	14

Attachments:

- 1. Definitions
- 2. Project Figures and Plans
- 3. CEQA Mitigation Monitoring and Reporting Program

Certification No. R9-2018-0107

The San Diego Water Board has independently reviewed the record of the Project to analyze the extent and nature of proposed Project impacts to the water quality and beneficial uses of waters of the United States and/or State and associated compensatory mitigation required to offset impacts attributed to the Project. In accordance with this Certification, the Applicant may proceed with the Project under the following terms and conditions:

I. STANDARD CONDITIONS

Pursuant to section 3860 of title 23 of the California Code of Regulations, the following three standard conditions apply to <u>all</u> water quality certification actions:

- A. This Certification action is subject to modification or revocation upon administrative or judicial review, including review and amendment pursuant to section 13330 of the Water Code and chapter 28, article 6 (commencing with title 23, section 3867), of the California Code of Regulations.
- B. This Certification action is not intended and shall not be construed to apply to any discharge from any activity involving a hydroelectric facility and requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent Certification application was filed pursuant to California Code of Regulations title 23, section 3855 subdivision (b), and that application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
- C. This Certification action is conditioned upon total payment of any fee required under title 23, chapter 28 (commencing with section 3830) of California Code of Regulations and owed by the applicant.

II. GENERAL CONDITIONS

- A. **Term of Certification**. Water Quality Certification No. R9-2018-0107 (Certification) shall expire upon a) the expiration or retraction of the Clean Water Act section 404 (33 U.S.C. §1344) permit issued by the U.S. Army Corps of Engineers for this Project, or b) five (5) years from the date of issuance of this Certification, whichever occurs first.
- B. **Duty to Comply.** The Applicant must comply with all conditions and requirements of this Certification. Any Certification noncompliance constitutes a violation of the Water Code and is grounds for enforcement action or Certification termination, revocation and reissuance, or modification.
- C. **General Waste Discharge Requirements**. The requirements of this Certification are enforceable through Water Quality Order No. 2003-0017-DWQ, *Statewide General Waste Discharge Requirements for Discharges of Dredged or Fill Material that have Received State Water Quality Certification* (Water Quality Order No. 2003-0017-

FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Project Certification No. R9-2018-0107

DWQ). This provision shall apply irrespective of whether a) the federal permit for which the Certification was obtained is subsequently retracted or is expired, or b) the Certification is expired. Water Quality Order No. 2003-0017-DWQ is accessible at:

http://www.waterboards.ca.gov/water_issues/programs/cwa401/docs/generalorders/gowdr401regulated_projects.pdf.

- D. Project Conformance with Application. All water quality protection measures and BMPs described in the application and supplemental information for water quality certification are incorporated by reference into this Certification as if fully stated herein. Notwithstanding any more specific conditions in this Certification, the Applicant shall construct, implement and comply with all water quality protection measures and BMPs described in the application and supplemental information. The conditions within this Certification shall supersede conflicting provisions within the application and supplemental information submitted as part of this Certification action.
- E. Project Conformance with Water Quality Control Plans or Policies. Notwithstanding any more specific conditions in this Certification, the Project shall be constructed in a manner consistent with the Basin Plan and any other applicable water quality control plans or policies adopted or approved pursuant to the Porter Cologne Water Quality Act (Division 7, commencing with Water Code Section 13000) or section 303 of the Clean Water Act (33 U.S.C §1313.). The Basin Plan is accessible on-line at:

http://www.waterboards.ca.gov/sandiego/water_issues/programs/basin_plan/index.shtm

- F. **Project Modification**. The Applicant must submit any changes to the Project, including Project operation, which would have a significant or material effect on the findings, conclusions, or conditions of this Certification, to the San Diego Water for prior review and written approval. If the San Diego Water Board is not notified of a significant change to the Project, it will be considered a violation of this Certification
- G. **Certification Distribution Posting.** During Project construction, the Applicant must maintain a copy of this Certification at the Project site. This Certification must be available at all times to site personnel and agencies. A copy of this Certification shall also be provided to any contractor or subcontractor performing construction work, and the copy shall remain in their possession at the Project site.
- H. **Inspection and Entry**. The Applicant must allow the San Diego Water Board or the State Water Resources Control Board, and/or their authorized representative(s) (including an authorized contractor acting as their representative), upon the presentation of credentials and other documents as may be required under law, to:

- Channel
- 1. Enter upon the Project or Compensatory Mitigation site(s) premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of this Certification;
- 2. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this Certification;
- Inspect, at reasonable times, any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this Certification; and
- 4. Sample or monitor, at reasonable times, for the purposes of assuring Certification compliance, or as otherwise authorized by the Clean Water Act or Water Code, any substances or parameters at any location.
- I. Enforcement Notification. In the event of any violation or threatened violation of the conditions of this Certification, the violation or threatened violation shall be subject to any remedies, penalties, process or sanctions as provided for under State law. For purposes of section 401(d) of the Clean Water Act, the applicability of any State law authorizing remedies, penalties, process or sanctions for the violation or threatened violation constitutes a limitation necessary to assure compliance with the water quality standards and other pertinent requirements incorporated into this Certification.
- J. **Certification Actions**. This Certification may be modified, revoked and reissued, or terminated for cause including but not limited to the following:
 - 1. Violation of any term or condition of this Certification;
 - Monitoring results indicate that continued Project activities could violate water quality objectives or impair the beneficial uses of the Montezuma Creek Channel or its tributaries;
 - Obtaining this Certification by misrepresentation or failure to disclose fully all relevant facts;
 - 4. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge; and
 - 5. Incorporation of any new or revised water quality standards and implementation plans adopted or approved pursuant to the Porter-Cologne Water Quality Control Act or section 303 of the Clean Water Act.

The filing of a request by the Applicant for modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any Certification condition.

City of San Diego FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Project Certification No. R9-2018-0107

- K. **Duty to Provide Information**. The Applicant shall furnish to the San Diego Water Board, within a reasonable time, any information which the San Diego Water Board may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this Certification or to determine compliance with this Certification.
- L. **Property Rights**. This Certification does not convey any property rights of any sort, or any exclusive privilege.
- M. Petitions. Any person aggrieved by this action of the San Diego Water Board may petition the State Water Resources Control Board (State Water Board) to review the action in accordance with the California Code of Regulations, title 23, sections 3867 and following. The State Water Board must receive the petition by 5:00 p.m., 30 days after the date of this Certification. Copies of the law and regulations applicable to filing petitions may be found on the Internet at: http://www.waterboards.ca.gov/public notices/petitions/water quality or will be provided upon request.

III. CONSTRUCTON AND POST CONSTRUCTON BEST MANAGEMENT PRACTICES

- A. Construction Requirements. Prior to start of Project construction, the Applicant must, as applicable, obtain coverage under, and comply with, the requirements of State Water Resources Control Board Water Quality Order No. 2009-0009-DWQ, the General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activity (General Construction Storm Water Permit) and any reissuance. If Project construction activities do not require coverage under the General Construction Storm Water Permit, the Applicant must develop and implement a pollution control plan, construction BMP plan, and/or erosion and sediment control plan to prevent the discharge of sediment and other pollutants during construction activities.
- B. **Post Construction Requirements**. The Project must meet all the Post-Construction requirements of the San Diego Water Board Order No. R9-2013-0001, National Pollutant Discharge Elimination Systems Permit and Waste Discharge Requirements for Discharges from the Municipal Separate Storm Sewer Systems (MS4) Draining the Watersheds within the San Diego Region (Regional MS4 Permit).

IV. PROJECT IMPACTS AND COMPENSATORY MITIGATION

A. **Project Impacts and Compensatory Mitigation.** Unavoidable Project impacts to an Montezuma Creek Channel its unnamed tributaries within the San Diego Watershed must not exceed the type and magnitude of impacts described in the table below. At a minimum, compensatory mitigation required to offset unavoidable temporary and permanent Project impacts to waters of the United States and/or State must be achieved as described in the table below:

	Impacts (acres)	Impacts (linear ft.)	Mitigation for Impacts (acres)	Mitigation Ratio (area mitigated :area impacted)	Mitigation for Impacts (linear ft.)	Mitigation Ratio (linear feet mitigated :linear feet impacted)
Permanent Impac	cts					
Wetland	0.075 (0.001) ¹	194 (36) ¹	0.002 Rehabilitation ²	2:1	NA ³	NA ³
Temporary Impac	cts ⁴					
Streambed	0.0044	374	N/A ⁵	N/A ⁵	N/A ⁵	N/A ⁵
Wetland	0.0174	445 ⁴	N/A ⁵	N/A ⁵	N/A ⁵	

NA - Not applicable

- 1. Permanent impacts total 0.075 acre (194 linear feet) from the placement of check dam, fence posts, and removal of palm trees. The 0.074 acre (158 linear feet) of the 0.075 acre (194 linear feet) that occurs from the removal of palm trees does not require compensatory mitigation. The total amount of wetland waters impact that require mitigation is 0.001 acre (36 linear feet).
- 2. Project compensatory mitigation rehabilitation credits will be subtracted from the Wetland Stadium Mitigation Project ledger.
- 3. Compensatory mitigation is being provided in a contiguous area at the advanced permittee mitigation site (approximately 65 acres); therefore, compensatory mitigation for linear feet is not being calculated on a project by project basis.
- 4. Temporary impacts associated with impacts from equipment.
- 5. All areas of temporary impacts must be restored to pre-project contours and re-vegetated with native species.
 - B. **Mitigation Credit.** Prior to the start of construction, the Applicant must provide documentation to the San Diego Water Board verifying the deduction of 0.002 acre of rehabilitation of wetland waters from the ledger for the Stadium Wetland Mitigation Bank.
 - C. Temporary Project Impact Areas. The Applicant must restore all areas of temporary impacts and all other areas of temporary disturbance which could result in a discharge or a threatened discharge of pollutants to waters of the United States and/or State. Restoration must include grading of disturbed areas to pre-project contours and revegetation with native species. The Applicant must implement all necessary BMPs to control erosion and runoff from areas associated with the Project.

V. MONITORING AND REPORTING REQUIREMENTS

A. **Annual Project Progress Reports.** The Applicant must submit annual Project progress reports describing compliance with all requirements of this Certification to the San Diego Water Board prior to **March 1** of each year following the issuance of this

- 10 -

Certification, until the Project has reached completion. The report must include the following information:

- 1. The names, qualifications, and affiliations of the persons contributing to the report;
- 2. The status, progress, and anticipated schedule for completion of Project construction activities;
- 3. A description of Project construction delays encountered or anticipated that may affect the schedule for construction completion; and
- 4. A description of each incident of noncompliance during the annual monitoring period and its cause, the period of the noncompliance including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and the steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.
- H. A description of the Applicant's progress towards meeting the objectives and ecological success performance standards contained in the Mitigation Plan. Final Project Completion Report. The Applicant must submit a Final Project Completion Report to the San Diego Water Board within 30 days of completion of the Project. The final report must include the following information:
 - 1. Date of construction initiation;
 - 2. Date of construction completion;
 - 3. As-built drawings of the Project, no bigger than 11"X17"; and
 - 4. Photo documentation of implemented post-construction BMPs and all areas of permanent and temporary impacts, prior to and after project construction. Photo documentation must be conducted in accordance with guidelines posted at http://www.waterboards.ca.gov/sandiego/water_issues/programs/401_certification/d ocs/401c/401PhotoDocRB9V713.pdf. In addition, photo documentation must include Global Positioning System (GPS) coordinates for each of the photo points referenced.
- I. Reporting Authority. The submittal of information required under this Certification, or in response to a suspected violation of any condition of this Certification, is required pursuant to Water Code section 13267 and 13383. Civil liability may be administratively imposed by the San Diego Water Board for failure to submit information pursuant to Water Code sections 13268 or 13385.
- J. Electronic Document Submittal. The Applicant must submit all reports and information required under this Certification in electronic format via e-mail to SanDiego@waterboards.ca.gov. Documents over 50 megabytes will not be accepted via e-mail and must be placed on a disc and delivered to:

California Regional Water Quality Control Board San Diego Region Attn: 401 Certification No. R9-2018-0107:847816:ngergans 2375 Northside Drive, Suite 100 San Diego, California 92108

Each electronic document must be submitted as a single file, in Portable Document Format (PDF), and converted to text searchable format using Optical Character Recognition (OCR). All electronic documents must include scanned copies of all signature pages; electronic signatures will not be accepted. Electronic documents submitted to the San Diego Water Board must include the following identification numbers in the header or subject line: Certification No. R9-2018-0107: 847816:ngergans.

- K. **Document Signatory Requirements**. All applications, reports, or information submitted to the San Diego Water Board must be signed as follows:
 - 1. For a corporation, by a responsible corporate officer of at least the level of vice president.
 - 2. For a partnership or sole proprietorship, by a general partner or proprietor, respectively.
 - 3. For a municipality, or a state, federal, or other public agency, by either a principal executive officer or ranking elected official.
 - 4. A duly authorized representative may sign applications, reports, or information if:
 - a. The authorization is made in writing by a person described above.
 - b. The authorization specifies either an individual or position having responsibility for the overall operation of the regulated activity.
 - c. The written authorization is submitted to the San Diego Water Board Executive Officer.

If such authorization is no longer accurate because a different individual or position has responsibility for the overall operation of the Project, a new authorization satisfying the above requirements must be submitted to the San Diego Water Board prior to or together with any reports, information, or applications, to be signed by an authorized representative.

L. **Document Certification Requirements**. All applications, reports, or information submitted to the San Diego Water Board must be certified as follows:

City of San Diego FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Project Certification No. R9-2018-0107

"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment."

VI. NOTIFICATION REQUIREMENTS

- A. Twenty Four Hour Non-Compliance Reporting. The Applicant shall report any noncompliance which may endanger health or the environment. Any such information shall be provided orally to the San Diego Water Board within 24 hours from the time the Applicant becomes aware of the circumstances. A written submission shall also be provided within five days of the time the Applicant becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected; the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance. The San Diego Water Board, or an authorized representative, may waive the written report on a case-by-case basis if the oral report has been received within 24 hours.
- B. **Anticipated Noncompliance**. The Applicant shall give advance notice to the San Diego Water Board of any planned changes in the Project or the Compensatory Mitigation project which may result in noncompliance with Certification conditions or requirements.
- C. Transfers. This Certification is not transferable in its entirety or in part to any person or organization except after notice to the San Diego Water Board in accordance with the following terms:
 - 1. **Transfer of Property Ownership:** The Applicant must notify the San Diego Water Board of any change in ownership of the Project area. Notification of change in ownership must include, but not be limited to, a statement that the Applicant has provided the purchaser with a copy of the Section 401 Water Quality Certification and that the purchaser understands and accepts the certification requirements and the obligation to implement them or be subject to liability for failure to do so; the seller and purchaser must sign and date the notification and provide such notification to the San Diego Water Board within 10 days of the transfer of ownership.
 - 2. Transfer of Mitigation Responsibility: Any notification of transfer of responsibilities to satisfy the mitigation requirements set forth in this Certification must include a signed statement from an authorized representative of the new party (transferee) demonstrating acceptance and understanding of the responsibility to comply with and fully satisfy the mitigation conditions and agreement that failure to comply with the mitigation conditions and associated requirements may subject the transferee to enforcement by the San Diego Water Board under Water Code section

FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Project Certification No. R9-2018-0107

13385, subdivision (a). Notification of transfer of responsibilities meeting the above conditions must be provided to the San Diego Water Board within 10 days of the transfer date.

3. Transfer of Post-Construction BMP Maintenance Responsibility: The Applicant assumes responsibility for the inspection and maintenance of all post-construction structural BMPs until such responsibility is legally transferred to another entity. At the time maintenance responsibility for post-construction BMPs is legally transferred the Applicant must submit to the San Diego Water Board a copy of such documentation and must provide the transferee with a copy of a long-term BMP maintenance plan that complies with manufacturer specifications. The Applicant must provide such notification to the San Diego Water Board within 10 days of the transfer of BMP maintenance responsibility.

Upon properly noticed transfers of responsibility, the transferee assumes responsibility for compliance with this Certification and references in this Certification to the Applicant will be interpreted to refer to the transferee as appropriate. Transfer of responsibility does not necessarily relieve the Applicant of this Certification in the event that a transferee fails to comply.

D. **Discharge Commencement**. The Applicant must notify the San Diego Water Board in writing **at least 5 days prior to** the start of Project construction.

VII. CALIFORNIA ENVIRONMENTAL QUALITY ACT COMPLIANCE

- A. The City of San Diego is the Lead Agency under the California Environmental Quality Act (CEQA) (Public Resources Code section 21000, et seq.) section 21067, and CEQA Guidelines (California Code of Regulations, title 14, section 15000 et seq.) section 15367, and has filed a Notice of Determination dated October 24, 2011 for the Final Environmental Impact (FEIR) titled Final Recirculated Program Environmental Impact Report for the Master Storm Water System Maintenance Program (State Clearing House Number 2004101032). The Lead Agency has determined the Project will have a significant effect on the environment and mitigation measures were made a condition of the Project.
- B. The San Diego Water Board is a Responsible Agency under CEQA (Public Resources Code section 21069; CEQA Guidelines section 15381). The San Diego Water Board has considered the Lead Agency's FEIR and finds that the Project as proposed will have a significant effect on resources within the San Diego Water Board's purview.
- C. The San Diego Water Board has required mitigation measures as a condition of this Certification to avoid or reduce the environmental effects of the Project to resources within the Board's purview to a less than significant level.
- D. As a Responsible Agency under CEQA, the San Diego Water Board will file a Notice of Determination in accordance with CEQA Guidelines section 15096 subdivision(i).

FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Project Certification No. R9-2018-0107

VIII. SAN DIEGO WATER BOARD CONTACT PERSON

Nicole Gergans, Environmental Scientist California Regional Water Quality Control Board, San Diego Region 2375 Northside Drive, Suite 100 San Diego, California 92108

Telephone: 619-521-3969

Email: nicole.gergans@waterboards.ca.gov

WATER QUALITY CERTIFICATION IX.

I hereby certify that the proposed discharge from the FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Project (Certification No. R9-2018-0107) will comply with the applicable provisions of sections 301 ("Effluent Limitations"), 302 ("Water Quality Related Effluent Limitations"), 303 ("Water Quality Standards and Implementation Plans"), 306 ("National Standards of Performance"), and 307 ("Toxic and Pretreatment Effluent Standards") of the Clean Water Act. This discharge is also regulated under State Water Board Order No. 2003-0017-DWQ, "Statewide General Waste Discharge Requirements for Dredged or Fill Discharges that have Received State Water Quality Certification (General WDRs)." which requires compliance with all conditions of this Water Quality Certification. Please note that enrollment under Order No. 2003-017-DWQ is conditional and, should new information come to our attention that indicates a water quality problem, the San Diego Water Board may issue individual waste discharge requirements at that time.

Except insofar as may be modified by any preceding conditions, all Certification actions are contingent on (a) the discharge being limited to, and all proposed mitigation being completed in strict compliance with, the applicants' Project description and/or the description in this Certification, and (b) compliance with all applicable requirements of the Basin Plan.

I, David W. Gibson, Executive Officer, do hereby certify the forgoing is a full, true, and correct copy of Certification No. R9-2018-0107 issued on September 20, 2018.

Executive Officer

San Diego Water Board

20 September 2018

ATTACHMENT 1

DEFINITIONS

Activity - when used in reference to a permit means any action, undertaking, or project including, but not limited to, construction, operation, maintenance, repair, modification, and restoration which may result in any discharge to waters of the state.

Buffer - means an upland, wetland, and/or riparian area that protects and/or enhances aquatic resource functions associated with wetlands, rivers, streams, lakes, marine, and estuarine systems from disturbances associated with adjacent land uses.

California Rapid Assessment Method (CRAM) - is a wetland assessment method intended to provide a rapid, scientifically-defensible and repeatable assessment methodology to monitor status and trends in the conditions of wetlands for applications throughout the state. It can also be used to assess the performance of compensatory mitigation projects and restoration projects. CRAM provides an assessment of overall ecological condition in terms of four attributes: landscape context and buffer, hydrology, physical structure and biotic structure. CRAM also includes an assessment of key stressors that may be affecting wetland condition and a "field to PC" data management tool (eCRAM) to ensure consistency and quality of data produced with the method.

Compensatory Mitigation Project - means compensatory mitigation implemented by the Applicant as a requirement of this Certification (i.e., applicant -responsible mitigation), or by a mitigation bank or an in-lieu fee program.

Discharge of dredged material – means any addition of dredged material into, including redeposit of dredged material other than incidental fallback within, the waters of the United States and/or State.

Discharge of fill material – means the addition of fill material into waters of the United States and/or State.

Dredged material – means material that is excavated or dredged from waters of the United States and/or State.

Ecological Success Performance Standards – means observable or measurable physical (including hydrological), chemical, and/or biological attributes that are used to determine if a compensatory mitigation project meets its objectives.

Enhancement – means the manipulation of the physical, chemical, or biological characteristics of an aquatic resource to improve a specific aquatic resource function(s). Enhancement results in the gain of selected aquatic resource function(s), but may also lead to a decline in other aquatic resource function(s). Enhancement does not result in a gain in aquatic resource area.

Establishment – means the manipulation of the physical, chemical, or biological characteristics present to develop an aquatic resource that did not previously exist. Creation results in a gain in aquatic resource area.

Fill material – means any material used for the primary purpose of replacing an aquatic area with dry land or of changing the bottom elevation of a water body.

Isolated wetland – means a wetland with no surface water connection to other aquatic resources.

Mitigation Bank – means a site, or suite of sites, where resources (e.g., wetlands, streams, riparian areas) are restored, established, enhanced, and/or preserved for the purpose of providing mitigation for impacts authorized by this Certification.

Preservation - means the removal of a threat to, or preventing the decline of, aquatic resources by an action in or near those aquatic resources. This term includes activities commonly associated with the protection and maintenance of aquatic resources through the implementation of appropriate legal and physical mechanisms. Preservation does not result in a gain of aquatic resource area or functions.

Re-establishment - means the manipulation of the physical, chemical, or biological characteristics of a site with the goal of returning natural/ historic functions to a former aquatic resource. Re-establishment results in rebuilding a former aquatic resource and results in a gain in aquatic resource area and functions.

Rehabilitation - means the manipulation of the physical, chemical, or biological characteristics of a site with the goal of repairing natural/ historic functions to a degraded aquatic resource. Rehabilitation results in a gain in aquatic resource function, but does not result in a gain in aquatic resource area.

Restoration - means the manipulation of the physical, chemical, or biological characteristics of a site with the goal of returning natural/historic functions to a former or degraded aquatic resource. For the purpose of tracking net gains in aquatic resource area, restoration is divided into two categories: re-establishment and rehabilitation.

Start of Project Construction - For the purpose of this Certification, "start of Project construction" means to engage in a program of on-site construction, including site clearing, grading, dredging, landfilling, changing equipment, substituting equipment, or even moving the location of equipment specifically designed for a stationary source in preparation for the fabrication, erection or installation of the building components of the stationary source within waters of the United States and/or State.


Uplands - means non-wetland areas that lack any field-based indicators of wetlands or other aquatic conditions. Uplands are generally well-drained and occur above (i.e., up-slope) from nearby aquatic areas. Wetlands can, however, be entirely surrounded by uplands. For example, some natural seeps and constructed stock ponds lack aboveground hydrological connection to other aquatic areas. In the watershed context, uplands comprise the landscape matrix in which aquatic areas form. They are the primary sources of sediment, surface runoff, and associated chemicals that are deposited in aquatic areas or transported through them.

Water quality objectives and other appropriate requirements of state law – means the water quality objectives and beneficial uses as specified in the appropriate water quality control plan(s); the applicable provisions of sections 301, 302, 303, 306, and 307 of the Clean Water Act; and any other appropriate requirement of state law.

City of San Diego FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Certification No. R9-2018-0107

ATTACHMENT 2 PROJECT FIGURES AND PLANS

- 1) Figure 1 Project Vicinity
- Figure 2 Vegetation/Land Cover
 Figure 3 Jurisdictional Delineation Results for the FY 18
 Maintenance Plans for Montezuma Channel MMP Map #66




SOURCE: ESRI; SanGIS; USGS Topo 7.5' Quad La Mesa 1975, 1978

Montezuma Creek Channel Maintanance

Figure 1
Project Vicinity



Attachment A




SOURCE: ESRI; City of San Diego; SanGIS; ESA

Montezuma Creek Channel Maintanance

Figure 2
Vegetation Communities/Land Cover





SOURCE: Rick Engineering; ESA; SanGIS; Digital Globe aerial imagery, 1/26/2016

Montezuma Creek Channel Maintenance

GENERAL NOTES

1. APPROVAL OF THESE PLANS BY THE CITY ENGINEER DOES NOT AUTHORIZE ANY WORK TO BE PERFORMED UNTIL A PERMIT HAS BEEN ISSUED.

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SURVEY MONUMENTS AND/OR VERTICAL CONTROL BENCHMARKS WHICH ARE DISTURBED OR DESTROYED BY CONSTRUCTION. A LAND SURVEYOR MUST FIELD LOCATE, REFERENCE, AND/OR PRESERVE ALL HISTORICAL OR CONTROLLING MONUMENTS. IF DESTROYED, SUCH MONUMENTS SHALL BE REPLACED WITH APPROPRIATE MONUMENTS BY A LAND SURVEYOR. A CORNER RECORD OR RECORD OF SURVEY, AS APPROPRIATE SHALL BE FILED AS REQUIRED BY THE PROFESSIONAL LAND SURVEYORS ACT. IF ANY VERTICAL CONTROL IS TO BE DISTURBED OR DESTROYED, THE CITY OF SAN DIEGO FIELD SURVEY SECTION MUST BE NOTIFIED, IN WITING, AT LEAST TAKES OF THE CONTROL THE CONTROL OF T 3 DAYS PRIOR TO THE CONSTRUCTION. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE COST OF REPLACING ANY VERTICAL CONTROL BENCHMARKS DESTROYED BY THE CONSTRUCTION.

3. IMPORTANT NOTICE: SECTION 4216 OF THE GOVERNMENT CODE REQUIRES A DIG ALERT IDENTIFICATION NUMBER BE ISSUED BEFORE A "PERMIT TO EXCAVATE" WILL BE VALID. FOR YOUR DIG ALERT I.D. NUMBER, CALL UNDERGROUND SERVICE ALERT, TOLL FREE 1-800-422-4133, TWO DAYS BEFORE YOU DIG.

4. CONTRACTOR SHALL IMPLEMENT AN EROSION AND SEDIMENT CONTROL PROGRAM DURING THE PROJECT GRADING AND/OR CONSTRUCTION ACTIVITIES. THE PROGRAM SHALL MEET ALL APPLICABLE REQUIREMENTS OF THE STATE WATER RESOURCE CONTROL BOARD AND THE CITY OF SAN DIEGO MUNICIPAL CODE AND STORM WATER STANDARDS MANUAL.

5. "PUBLIC IMPROVEMENT SUBJECT TO DESUETUDE OR DAMAGE." IF REPAIR OR REPLACEMENT OF SUCH PUBLIC IMPROVEMENTS IS REQUIRED, THE OWNER SHALL OBTAIN THE REQUIRED PERMITS FOR WORK IN THE PUBLIC RIGHT-OF-WAY, SATISFACTORY TO THE PERMIT- ISSUING AUTHORITY.

6. PRIOR TO ANY DISTURBANCE TO THE SITE, EXCLUDING UTILITY MARK-OUTS AND SURVEYING, THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR A PRE-CONSTRUCTION MEETING WITH THE CITY OF SAN DIEGO FIELD ENGINEERING DIVISION

7. DEVIATIONS FROM THESE SIGNED PLANS WILL NOT BE ALLOWED UNLESS A CONSTRUCTION CHANGE IS APPROVED BY THE CITY ENGINEER OR THE CHANGE IS REQUIRED BY THE CITY INSPECTOR. 8. AS-BUILT DRAWINGS MUST BE SUBMITTED TO THE RESIDENT ENGINEER PRIOR TO ACCEPTANCE OF THIS PROJECT BY

THE CITY OF SAN DIEGO. 9. THE AREA WHICH IS DEFINED AS A NON GRADING AREA AND WHICH IS NOT TO BE DISTURBED SHALL BE STAKED PRIOR TO START OF THE WORK, THE PERMIT APPLICANT AND ALL OF THEIR REPRESENTATIVES OR CONTRACTORS SHALI COMPLY WITH THE REQUIREMENTS FOR PROTECTION OF THIS AREA AS REQUIRED BY ANY APPLICABLE AGENCY. ISSUANCE OF THE CITY'S GRADING PERMIT SHALL NOT RELIEVE THE APPLICANT OR ANY OF THEIR REPRESENTATIVES OR CONTRACTORS FROM COMPLYING WITH ANY STATE OR FEDERAL REQUIREMENTS BY AGENCIES INCLUDING BUT NOT LIMITED TO CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD, CALIFORNIA DEPARTMENT OF FISH AND GAME. COMPLIANCE MAY INCLUDE OBTAINING PERMITS, OTHER AUTHORIZATIONS, OR COMPLIANCE WITH MANDATES BY ANY APPLICABLE STATE OR FEDERAL AGENCY.

GROUND WATER DISCHARGE

1. ALL GROUND WATER EXTRACTION AND SIMILAR WASTE DISCHARGES TO SURFACE WATER NOT TRIBUTARY TO THE SAN DIEGO BAY ARE PROHIBITED UNTIL IT CAN BE DEMONSTRATED THAT THE OWNER HAS APPLIED AND OBTAINED AUTHORIZATION FROM THE STATE OF CALIFORNIA VIA AN OFFICIAL "ENROLLMENT LETTER" FROM THE REGIONAL WATER QUALITY CONTROL BOARD IN ACCORDANCE WITH THE TERMS, PROVISIONS AND CONDITIONS OF SATE ORDER NO R9-2009-0002 NPDES CAG919002.

2. THE ESTIMATED MAXIMUM DISCHARGE RATES MUST NOT EXCEED THE LIMITS SET IN THE OFFICIAL "ENROLLMENT LETTER" FROM THE REGIONAL BOARD UNLESS PRIOR NOTIFICATION AND SUBSEQUENT AUTHORIZATION HAS BEEN OBTAINED, AND DISCHARGE OPERATIONS MODIFIED TO ACCOMMODATE THE INCREASED RATES.

3. ALL GROUND WATER EXTRACTIONS AND SIMILAR WASTE DISCHARGES TO SURFACE WATERS NOT TRIBUTARY TO THE SAN DIEGO BAY ARE PROHIBITED UNTIL IT CAN BE DEMONSTRATED THAT THE OWNER HAS APPLIED AND OBTAINED AUTHORIZATION FROM THE STATE OF CALIFORNIA VIA OFFICIAL "ENROLLMENT LETTER" FROM THE REGIONAL WATER QUALITY CONTROL BOARD IN ACCORDANCE WITH THE TERMS, PROVISIONS AND CONDITIONS OF STATE ORDER NO R9-2007-0034 NPDES NO. CAG919001.

SHEET INDEX

TITLE SHEET	SHEET	1
MAINTENANCE PLAN	SHEET	2
MAINTENANCE METHODOLOGIES AND BMP NOTES	SHEET	3
MASTER MAINTENANCE PROGRAM (MMP) PROTOCOL REQUIREMENTS AND PEIR ENVIRONMENTAL MITIGATION MEASURES	SHEET	4

REFERENCE DRAWINGS


PLANS FOR THE IMPROVEMENT OF COLLEGE VALLEY CITY OF SAN DIEGO DRAWING NO. 16057-D

COLLEGE GLEN UNIT NO. 2 DRAINAGE CHANNEL CITY OF SAN DIEGO DRAWING NO. 7199A-D

PLANS FOR THE IMPROVEMENT OF DEFIANCE WAY, PROSPERITY LANE AND UNNAMED EASEMENTS IN AND ADJOINING PICARD ESTATES UNIT NO. 1 CITY OF SAN DIEGO DRAWING NO. 13391-L

MAINTENANCE PLANS FOR:

MONTEZUMA CREEK CHANNEL MMP MAP#66



TOPOGRAPHY SOURCE

CITY OF SAN DIEGO SANGIS 2014 2 FOOT CONTOURS, NAVD88

BENCHMARK

BRASS PLUG N.E. RETURN 54TH AND ADAMS. FB. 1720-55

CHISELED SQUARE ON WATER M.H. S.W. CORNER LOTS 36&37 COLLEGE HTS MAP NO. 2906 ELEV. 417.95

BRASS PLUG AT N.E. CORNER 55TH & MONTEZUMA ROAD IN CURB AT EASTERLY RETURN ELEV. 459.89 M.S.L.

STORM WATER PROTECTION NOTES

1. THIS PROJECT IS SUBJECT TO MUNICIPAL STORM WATER PERMIT ORDER R920070001; AND RISK LEVEL/TYPE: CHECK ONE BELOW ☐ CGP RISK LEVEL 1 ☐ CGP LUP TYPE 1 ☐ CGP RISK LEVEL 2 ☐ CGP LUP TYPE 2 ☐ CGP RISK LEVEL 3 □ CGP LUP TYPE 3

2. WDID NO: NOT APPLICABLE

☑ NOT APPLICABLE

3. CHECK ONE ☐ THIS PROJECT WILL EXCEED THE MAXIMUM DISTURBED AREA LIMIT, THEREFORE A WEATHER TRIGGERED ACTION PLAN (WTAP) IS REQUIRED. ☐ THIS PROJECT WILL FOLLOW PHASED GRADING NOT TO EXCEED FIVE (5) ACRES PER PHASE.

4. THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE WPCP OR SWPPP AS APPLICABLE.

5. WATERSHED: LOWER SAN DIEGO

6. HYDROLOGIC SUB AREA NAME: MISSION SAN DIEGO

7. HYDROLOGIC SUB AREA NUMBER: ____907.11

WATER POLLUTION CONTROL PLAN FOR MONTEZUMA CREEK CHANNEL MAINTENANCE PROJECT PREPARED BY: McGRATH CONSULTING

PO BOX 2488 EL CAJON, CA. 92021 (619) 443-3811

DECLARATION OF RESPONSIBLE CHARGE

I HEREBY DECLARE THAT I AM THE ENGINEER OF WORK FOR THIS PROJECT, THAT I HAVE EXERCISED RESPONSIBLE CHARGE OVER THE DESIGN OF THE PROJECT AS DEFINED IN SECTION 6703 OF THE BUSINESS AND PROFESSIONS CODE, AND THAT THE DESIGN IS CONSISTENT WITH CURRENT STANDARDS.

I UNDERSTAND THAT THE CHECK OF PROJECT DRAWINGS AND SPECIFICATIONS BY THE CITY OF SAN DIEGO IS CONFINED TO A REVIEW ONLY AND DOES NOT RELIEVE ME, AS ENGINEER OF WORK, OF MY RESPONSIBILITIES FOR PROJECT DESIGN.

CARSON P. EDGINGTON R.C.E. NO. 76519 DATE

STREET NAME



SPEED

STREET DATA TABLE

CLASSIFICATION

5620 FRIARS ROAD SAN DIEGO, CA 92110 619-291-0707 (FAX) 619-291-4165

ADT

(MPH) (VEHICLES) (FT)

WORK TO BE DONE

THE IMPROVEMENTS CONSIST OF THE FOLLOWING WORK TO BE DONE ACCORDING TO THESE PLANS AND THE SPECIFICATIONS AND STANDARD DRAWINGS OF THE CITY OF SAN DIEGO. MAINTENANCE OF CONCRETE & EARTHENED CHANNELS TO REMOVE ACCUMULATED SEDIMENT AND OTHER DEBRIS

STANDARD SPECIFICATIONS:

LEGEND

DOCUMENT NO. PITS070112-01

STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION (GREENBOOK), 2012 EDITION

CITY OF SAN DIEGO STANDARD SPECIFICATIONS FOR PITS070112-02 PUBLIC WORKS CONSTRUCTION (WHITEBOOK), 2012 EDITION CALIFORNIA DEPARTMENT OF TRANSPORTATION MANUAL PITS070112-04 OF UNIFORM TRAFFIC CONTROL DEVICES, 2012 EDITION

CALIFORNIA DEPARTMENT OF TRANSPORTATION U.S. PITS070112-06 CUSTOMARY STANDARD SPECIFICATIONS, 2010 EDITION STANDARD DRAWINGS

DESCRIPTION DOCUMENT NO.

CITY OF SAN DIEGO STANDARD DRAWINGS FOR PUBLIC PITS070112-03 WORKS CONSTRUCTION, 2012 EDITION

PITS070112-05 CALIFORNIA DEPARTMENT OF TRANSPORTION U.S. CUSTOMARY STANDARD PLANS, 2010 EDITION CALIFORNIA STORMWATER QUALITY ASSOCIATION. CASQA MANUAL

STORMWATER BEST MANAGEMENT PRACTICE HANDBOOK PORTAL: CONSTRUCTION, JANUARY 2015

EXISTING IMPROVEMENTS	SYMBOL
EXIST. CONTOURS	
EXIST. CURB INLET	
EXIST. STORM DRAIN MAIN	
EXIST. SEWER MAIN	s
EXIST. WATER MAIN	— W ——
CHANNEL MAINTENANCE AREA	\
ACCESS & LOADING AREA	
STAGING AREA	/////////
STEEL PLATE PLACEMENT	

STORM WATER MANAGEMENT BMPs

<u>ITEM</u>	<u>SYMBOL</u>	
STREET SWEEPING AND VACUUMING DAILY	SEE CASQA MANUAL SE-7	
SANDBAG BARRIER	SEE CASQA MANUAL SE-8	
STORM DRAIN INLET PROTECTION	SEE CASQA MANUAL SE-10	
SCHEDULING	SEE CASQA MANUAL EC-1	
PRESERVE EXISTING VEGETATION	SEE CASQA MANUAL EC-2	
GRAVEL OR SAND BAG BARRIERS	SEE CASQA MANUAL SE-6 SE-8	
FIBER ROLLS OR STRAW WATTLES	SEE CASQA MANUAL SE-5	
DIVERT RUN-ON FROM SURROUNDING AREAS	SEE CASQA MANUAL EC-9 SE-5 SE-6 SE-1	<u>13</u>
CHECK DAMS	SEE CASQA MANUAL SE-4	
SPILL PREVENTION AND CONTROL	SEE CASQA MANUAL WM-4	
SOLID WASTE MANAGEMENT	SEE CASQA MANUAL WM-5	
LIQUID WASTE MANAGEMENT	SEE CASQA MANUAL WM-10	
SANITARY WASTE MANAGEMENT	SEE CASQA MANUAL WM-9	
STOCKPILED WASTE MANAGEMENT	SEE CASQA MANUAL WM-3	
MATERIAL STORAGE	SEE CASQA MANUAL WM-1	
MATERIAL HANDLING	SEE CASQA MANUAL WM-2	
VEHICLE AND EQUIPMENT FUELING	SEE CASQA MANUAL NS-9	
ILLICIT CONNECTION / DISCHARGE CONTROL	SEE CASQA MANUAL NS-6	
WATER CONSERVATION PRACTICE	SEE CASQA MANUAL NS-1	
DEWATTERING OPERATIONS	SEE CASQA MANUAL NS-2	
WIND EROSION CONTROL	SEE CASQA MANUAL WE-1	
(NOT ALL WILL BE GRAPHICALLY ILLUSTRATED WITH	N SITE MAPS)	

CONSTRUCTION SITE STORM WATER PRIORITY: LOW TITLE SHEET FOR:

MONTEZUMA CREEK CHANNEL

CITY OF SAN DIEGO, CALIFORNIA

MAP #66


TRA	NSPORT	P.T.S NO			
FOR CITY	ENGINEE	<u> </u>	DATE		V.T.M
DESCRIPTION	BY	APPROVED	DATE	FILMED	
ORIGINAL	REC				
					NAD83 COORDINATES
AS-BUILTS					LAMBERT COORDINATES
CONTRACTOR		DATE STARTE			_1_D
INSPECTOR		DATE COMPLE	ETED		ا ا

CONSTRUCTION CHANGE TABLE WARNING CHANGE DATE EFFECTED OR ADDED SHEET NUMBERS APPROVAL NO. 1/2 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE.



DEVELOPMENT SERVICES DEPARTMENT

W:\17204-L_TO*39_IHHA_FY17\4_Montezuma Map 66\Civil\Sheets\17204L_Montezuma01.dgn W:\17204-L_TO*39_IHHA_FY17\4_Montezuma Map 66\Civil\Sheets\SD CorpStds 2005.dscript 21-MAR-2018 16:24



MAINTENANCE BMPs

1. ALL BEST MANAGEMENT PRACTICES (BMPs) WILL BE IMPLEMENTED PRIOR TO OR CONCURRENT WITH CONSTRUCTION AND MAINTAINED THROUGHOUT THE PROJECT. A QUALIFIED CONTACT PERSON WILL BE RESPONSIBLE FOR IMPLEMENTING THE WATER POLLUTION CONTROL PLAN (WPCP). ALL WORK SHALL BE COMPLETED BETWEEN SEPTEMBER 15TH AND FEBRUARY 15TH UNLESS AN EXTENSION IS GRANTED IN CONFORMANCE WITH ALL APPLICABLE PERMITS.

2. CONTRACTOR WILL LIMIT ALL CONSTRUCTION RELATED ACTIVITIES TO THE PROJECT FOOTPRINT. 3. EXISTING VEGETATION TO BE PRESERVED IN PLACE SHALL BE CLEARLY MARKED WITH A BUFFER AREA FOLLOWING THE GUIDANCE OF BMP FACT SHEET EC-2.

4. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANUP OF SILT AND MUCH ON STREETS AND OTHER PAVED SURFACES DUE TO EXCAVATION ACTIVITIES. STREET SWEEPING AND VACUUMING WILL BE MANAGED FOLLOWING THE GUIDANCE OF BMP FACT SHEET SE-7.

5. WEATHER TRIGGERED ACTION PLAN SHALL BE IMPLEMENTED WHEN THERE IS A FORECASTED 50% OR GREATER CHANCE OF LIKELY PRECIPITATION OF 0.1 INCH OR GREATER BY THE NATIONAL WEATHER SERVICE FORECAST.

6. CONTRACTOR SHALL RESTORE ALL EROSION CONTROL DEVICES TO WORKING ORDER AFTER EACH RUNOFF -PRODUCING RAINFALL.

7. TEMPORARY EROSION OR SEDIMENT CONTROL MEASURES WILL BE REMOVED UPON COMPLETION OF MAINTENANCE UNLESS THEIR REMOVAL WOULD RESULT IN GREATER ENVIRONMENTAL IMPACT THAN LEAVING THEM IN PLACE.

8. HAZARDOUS MATERIALS USED DURING MAINTENANCE WILL NOT BE STORED WITHIN 50 FEET FROM STORM WATER FACILITIES. HAZARDOUS MATERIALS SHALL BE MANAGED AND STORED IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS. A REGISTERED FIRST-RESPONSE, PROFESSIONAL HAZARDOUS MATERIALS CLEAN-UP/REMEDIATION SERVICE SHALL BE LOCALLY AVAILABLE ON CALL.

9. THE TREATMENT, STORAGE, AND DISPOSAL OF WASTEWATER DURING THE LIFE OF THE PROJECT MUST BE DONE IN ACCORDANCE WITH WASTE DISCHARGE REQUIREMENTS ESTABLISHED BY THE SAN DIEGO WATER BOARD PURSUANT

10. SPILLS SHALL BE MANAGED FOLLOWING THE GUIDANCE OF BMP FACT SHEET WM-4. SPILL CLEANUP MATERIALS SHALL BE AVAILABLE ONSITE AT ALL TIMES.

11. THE CONTRACTOR SHALL PROVIDE EQUIPMENT NECESSARY TO EXTINGUISH SMALL BRUSH FIRES (FROM SPARKING VEHICLES, ETC.) ON-SITE DURING ALL PHASES OF PROJECT ACTIVITIES, ALONG WITH TRAINED PERSONNEL FOR USE OF SUCH EQUIPMENT.

12. THE CONTRACTOR SHALL MONITOR THE 5 DAY WEATHER FORECAST. IF ANY PRECIPITATION IS FORECASTED, THE SITE SHALL BE SECURED TO PREVENT ANY CONSTRUCTION RELATED MATERIALS FROM LEAVING THE SITE AND ENTERING THE CHANNELS. NO CONSTRUCTION ACTIVITIES SHALL OCCUR DURING RAIN EVENTS.

13. SAMPLING AND ANALYSIS, MONITORING AND REPORTING, AND POST-MAINTENANCE MANAGEMENT OF THE PROJECT SHALL BE CONDUCTED AS DÉTERMINED NECESSARY BY THE CITY OF SAN DIEGO.

14. CHANNELS WILL BE INSPECTED WITHIN 72 HOURS OF THE FIRST 2-YEAR STORM FOLLOWING MAINTENANCE. IF SUBSTANTIAL EROSION HAS OCCURRED, EROSION CONTROL MEASURES RECOMMENDED BY THE FIELD ENGINEER WILL BE IMPLEMENTED TO REMEDIATE EROSION AREAS AND TO MINIMIZE FUTURE EROSION.

15. CONTRACTOR SHALL PROVIDE TRAINING FOR ALL PERSONNEL RESPONSIBLE FOR THE PROPER INSTALLATION, INSPECTION, AND MAINTENANCE OF ONSITE BMPs.

16. THE QUALIFIED CONTACT PERSON WILL ASSIGN A MONITOR FOR DAILY INSPECTION OF THE BMPs EACH MORNING. THE MONITOR WILL CHECK THE NATIONAL WEATHER SERVICE FORECAST, COMPLETE BMP INSPECTION CHECKLIST, PERFORM ANY NECESSARY BMP MAINTENANCE/REPAIRS, AND REPORT THE RESULTS TO THE QUALIFIED CONTACT PERSON. COMPLETED INSPECTION CHECKLIST WILL BE KEPT WITH THE WPCP.

17. PREVIOUSLY UNDISTURBED STAGING AREAS WILL BE REVEGETATED WITHIN 30 DAYS OF COMPLETION OF MAINTENANCE ACTIVITIES. THE REVEGETATED AREAS WILL BE MONITORED FOR A PERIODS OF NOT LESS THAN 25 MONTHS AFTER PLANTING.

18. FINAL LOCATION OF CHANNEL CENTERLINE WILL BE DETERMINED IN THE FIELD AND COORDINATED WITH THE NECESSARY PROJECT SPECIALIST (BIOLOGIST, HISTORICAL MONITOR, ETC.)

MONTEZUMA CREEK CHANNEL - MAP NO. 66 IMP MAINTENANCE METHODOLOGY TABLE

FACILITY/CHANNEL	MONTEZUMA CHANNEL - MAP NO.66 MONTEZUMA CHANNEL WEST OF 54TTO 60"PIPE
DIMENSIONS	TRAPEZOIDAL EARTHEN CHANNEL 620' LENGTH APPROX. 16.5' TOP WIDTH 6' BOTTOM WIDTH 3.5' IN DEPTH 0.5'-1' OF SEDIMENT MAXIMUM CUBIC YARDS OF MATERIAL REMOVAL: 8,600
MAINTENANCE METHOD	MECHANIZED VEGETATION MAINTENANCE ONLY
EQUIPMENT (EQUIPMENT WILL BE EQUIVALENT OR SMALLER IN SIZE/TYPE)	* GRADALL (5100 SERIES) * TRACK STEER (CAT 289D) * EXCAVATOR (CAT 349) * FRONT-END LOADER (CAT 966) * DUMP TRUCKS(S) (12 YD) * 6"PUMPS OR SMALLER
SCHEDULE	IN CHANNEL MAINTENANCE WILL TAKE APPROXIMATELY 30 DAYS 7:00 AM TO 7:00 PM
STAFFING	10 TO 14 PEOPLE
MAINTENANCE PROCEDURE	
CHANNEL SEQUENCE	STATION 13+19.4 TO 15+95 AND 16+27.7 TO 16+56.9
ACCESS & LOADING AREA(S)	ACCESS AREA: (STATION 13+88.6) - TRACK STEER DRIVES INTO CHANNEL VIA EARTHEN RAMP. LOADING AREA: (12+53) - GRADALL SITS ABOVE CHANNEL, AT REAR OF 4883 COLLWOOD BLVD, AND LOADS TRUCKS.
STAGING & STOCKPILE AREA	EQUIPMENT AND TRUCKS WILL BE STAGED ON ASPHALT PAVED PARKING LOT OF AND ON EASEMENT AT REAR OF 4883 COLLWOOD BLVD. ALL MATERIALS WILL BE HAULED IMMEDIATELY TO A LEGAL DISPOSAL SITE (MIRAMAR LANDFILL).
METHODOLOGY	1. DRY WEATHER FLOW DIVERSION BERM (TIGER DAM/SANDBAGS) & DIVERSION PUMP(S) WILL BE PLACED AT EASTERN LIMITS OF CHANNEL CLEANING. DIVERSION PIPES WILL BE PLACED ON EASTERN SIDE OF THE CHANNEL AND EXTENDED TO A DISCHARGE AREA WEST OF THE PROJECT MAINTENANCE LIMITS. 2. TRACK STEER /EXCAVATOR/FRONT-END LOADER ENTER/EXIT(S) CHANNEL AT ACCESS & LOADING AREA(S). 3. TRACK STEER/FRONT END-LOADER PUSHES VEGETATION & SEDIMENT TO EXCAVATOR/FRONT-END LOADER, STATIONED IN THE CHANNEL 4. TRACK STEER/FRONT-END LOADER SCOOPS MATERIAL & LOADS MATERIAL INTO WAITING DUMP TRUCKS, LOCATED AT BOTTOM OF ACCESS RAMP. 5. DUMP TRUCKS HAUL MATERIAL TO LEGAL DISPOSAL SITE. 6. TRACK STEER/EXCAVATOR/FRONT-END LOADER EXIT CHANNEL. 7. DRY WEATHER DIVERSION BERM, DIVERSION PUMP(S) & HOSES REMOVED.
POST-MAINTENANCE	1. DEMOBILIZE EQUIPMENT. 2. REMOVE TEMPORARY CONSTRUCTION BMPS.
OTHER NOTES	1. SWEEPER SWEEPS ADJACENT PUBLIC RIGHTS-OF-WAY AND PRIVATE ACCESS AREA AT PROJECT'S COMPLETION. 2. EQUIPMENT FUELED OUTSIDE CHANNEL & LOCATED AT LEAST 150' FROM WATERS OF US/STATE. 3. DEWATERING PUMP(S) MAY BE USED AT VARIOUS LOCATIONS TO REMOVE PONDED WATER PRIOR TO EQUIPMENT ENTERING THE CHANNEL. WATER WILL BE DISCHARGED JUST WEST OF THE PROJECT MAINTENANCE LIMITS.

ENGINEER OF WORK

CARSON P. EDGINGTON R.C.E. 76519 DATE

MONTEZUMA CREEK CHANNEL MAP #66

(Tran	CITY OI ISPORTAT	I.O. NO			
FOR CITY ENGINEER DATE					V.T.M
DESCRIPTION	BY	APPROVED	DATE	FILMED	
ORIGINAL	REC				
					NAD83 COORDINATES
AS-BUILTS					LAMBERT COORDINATES
CONTRACTOR	<u> </u>	DATE STARTED DATE COMPLET			-3-D

MAINTENANCE METHODOLOGIES:

J-17204-L

W:\17204-L_TO=39_IHHA_FY17\4_Montezuma Map 66\Civil\Sheets\17204L_Montezuma03.dgn
W:\17204-L_TO=39_IHHA_FY17\4_Montezuma Map 66\Civil\Sheets\SD CorpStds 2005.dscript
21-MAR-2018 13:41

MASTER MAINTENANCE PROGRAM (MMP) PROTOCOL REQUIREMENTS:

- 1. BIO-1: RESTRICT VEHICLES TO ACCESS DESIGNATED IN THE MMP.
- 2. BIO-2: FLAG AND DELINEATE ALL SENSITIVE BIOLOGICAL RESOURCES TO REMAIN WITHIN OR ADJACENT TO MAINTENANCE AREA PRIOR TO INITIATION OF MAINTENANCE ACTIVITIES IN ACCORDANCE WITH THE SITE SPECIFIC INDIVIDUAL BIOLOGICAL ASSESSMENT (IBA), INDIVIDUAL HYDROLOGY AND HYDRAULIC ASSESSMENT (IHHA), AND/OR INDIVIDUAL MAINTENANCE PLAN (IMP) PREPARED FOR THE WORK.
- 3. BIO-3: CONDUCT A PRE-MAINTENANCE MEETING ON SITE PRIOR TO THE START OF ANY MAINTENANCE ACTIVITY THAT OCCURS WITHIN OR ADJACENT TO SENSITIVE BIOLOGICAL RESOURCES. THE PRE-MAINTENANCE MEETING SHALL INCLUDE A QUALIFIED BIOLOGIST, FIELD ENGINEER, PLANNER, EQUIPMENT OPERATORS/SUPERINTENDENT AND OTHER KEY PERSONNEL CONDUCTING OR INVOLVED IN CHANNEL MAINTENANCE ACTIVITIES. THE QUALIFIED BIOLOGIST SHALL POINT OUT OR IDENTIFY SENSITIVE BIOLOGICAL RESOURCES TO BE AVOIDED DURING MAINTENANCE, FLAG/DELINEATE SENSITIVE RESOURCES TO BE AVOIDED, REVIEW SPECIFIC MEASURES TO PROTECT SENSITIVE BIOLOGICAL RESOURCES AS NECESSARY. THE BIOLOGIST SHALL ALSO REVIEW THE PROPOSED EROSION CONTROL METHODS TO CONFIRM THEY WILL NOT POSE RISK TO WILDLIFE (E.G., NON-BIODEGRADABLE BLANKETS MAY ENTANGLE WILDLIFE).
- 4. BIO-4: AVOID THE INTRODUCTION OF INVASIVE PLANT SPECIES WITH PHYSICAL EROSION CONTROL MEASURES.
- 5. BIO-5: CONDUCT APPROPRIATE PRE-MAINTENANCE SURVEYS IF MAINTENANCE IS PROPOSED DURING THE BREEDING SEASON OF A SENSITIVE ANIMAL SPECIES (JANUARY 15 TO AUGUST 31). IF SENSITIVE ANIMAL SPECIES COVERED BY THE PROGRAM ENVIRONMENTAL IMPACT REPORT (PEIR) ARE IDENTIFIED, THEN APPLICABLE MEASURES FROM THE MITIGATION MONITORING AND REPORTING PLAN (MMRP) SHALL BE IMPLEMENTED UNDER THE DIRECTION OF A QUALIFIED BIOLOGIST TO AVOID SIGNIFICANT DIRECT AND/OR INDIRECT IMPACTS TO IDENTIFIED SENSITIVE ANIMAL SPECIES. IF SENSITIVE ANIMAL SPECIES ARE IDENTIFIED DURING PRE-MAINTENANCE SURVEYS THAT ARE NOT COVERED BY THE PEIR, SWD SHALL CONTACT THE APPROPRIATE WILDLIFE AGENCIES AND ADDITIONAL ENVIRONMENTAL REVIEW UNDER CEQA WILL BE REQUIRED.
- 6. BIO-6: REMOVE ARUNDO THROUGH ONE, OR A COMBINATION OF, THE FOLLOWING METHODS;(1) FOLIAR SPRAY (SPRAYING HERBICIDE ON LEAVES AND STEMS WITHOUT CUTTING FIRST) WHEN ARUNDO OCCURS IN MONOTYPIC STANDS, OR (2) CUT AND PAINT (CUTTING STEMS CLOSE TO THE GROUND AND SPRAYING OR PAINTING HERBICIDE ON CUT STEM SURFACE) WHEN ARUNDO IS INTERMIXED WITH NATIVE PLANTS. WHEN SEDIMENT SUPPORTING ARRUNDO MUST BE REMOVED, THE SEDIMENT SHALL BE EXCAVATED TO A DEPTH SUFFICIENT TO REMOVE THE RHIZOMES, WHEREVER FEASIBLE. FOLLOWING REMOVAL OF SEDIMENT CONTAINING RHIZOMES, LOOSE RHIZOME MATERIAL SHALL BE REMOVED FROM THE CHANNEL AND DISPOSED OFFSITE. AFTER THE INITIAL TREATMENT, THE AREA OF REMOVAL SHALL BE INSPECTED ON A QUARTERLY BASIS FOR UP TWO YEARS, OR UNTIL NO RESPROUTING IS OBSERVED DURING AN INSPECTION. IF RESPROUTING IS OBSERVED, THE CUT AND PAINT METHOD SHALL BE APPLIED TO ALL RESPROUTS.
- 7. BIO-7: AVOID MECHANIZED MAINTENANCE WITHIN 300 FEET OF A COOPER'S HAWK NEST, 900 FEET OF A NORTHERN HARRIER'S NEST, OR 500 FEET OF ANY OTHER RAPTOR'S NEST UNTIL ANY FLEDGLINGS HAVE LEFT THE NEST.
- 8. WM-1: DISPOSE AND TRANSPORT COMPOSTABLE GREEN WASTE MATERIAL TO AN APPROVED COMPOSTING FACILITY, IF AVAILABLE.
- 9. WM-2: RE-USE EXCAVATED MATERIAL, WHENEVER POSSIBLE, AS FILL MATERIAL, AGGREGATE SAND REPLENISHMENT, OR OTHER RAW MATERIAL USES. RE-USED MATERIAL (AGGREGATES, SOIL, SAND OR SILT) SHALL BE DOCUMENTED IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS.
- 10. WM-3: SEPARATE WASTE TIRES FROM EXCAVATED MATERIAL AND TRANSPORT THEM TO AN APPROPRIATE DISPOSAL FACILITY. IF MORE THAN NINE TIRES ARE IN A VEHICLE OR WASTE BIN AT ANY ONE TIME, THEY SHALL BE TRANSPORTED UNDER A COMPLETED COMPREHENSIVE TRIP LOG (CTL) TO DOCUMENT THAT THE TIRES WERE TAKEN TO AN APPROPRIATE DISPOSAL FACILITY.
- 11. WM-4: LOG AND TRANSPORT ANY HAZARDOUS MATERIALS ENCOUNTERED DURING MAINTENANCE TO A HAZARDOUS WASTE STORAGE, RECYCLING, TREATMENT OR DISPOSAL FACILITY. PERSONNEL HANDLING HAZARDOUS MATERIALS SHALL HAVE THE APPROPRIATE TRAINING TO HANDLE, STORE, TRANSPORT, AND/OR DISPOSE THE MATERIAL. HAZARDOUS MATERIALS (E.G., MACHINE OIL, MERCURY SWITCHES, AND REFRIGERANT GASES) SHALL BE REMOVED FROM APPLIANCES AND DISPOSED IN ACCORDANCE WITH THIS PROTOCOL.
- 12. WQ-2: PREVENT OFF-SITE SEDIMENT TRANSPORT DURING MAINTENANCE THROUGH THE USE OF EROSION AND SEDIMENT CONTROLS WITHIN STORM WATER FACILITIES, ALONG ACCESS ROUTES AND AROUND STOCKPILE/STAGING AREAS. INSTALL BMPS SUCH AS SILT FENCES, FIBER ROLLS; GRAVEL BAGS; TEMPORARY SEDIMENT BASINS; STABILIZED MAINTENANCE ACCESS POINTS (E.G., SHAKER PLATES); CONTAINMENT BARRIERS (E.G., SILT FENCE, FIBER ROLLS AND/OR BERMS) FOR MATERIAL STOCKPILES; AND PROPERLY FITTED COVERS FOR MATERIAL TRANSPORT VEHICLES. REMOVE TEMPORARY EROSION OR SEDIMENT CONTROL MEASURES UPON COMPLETION OF MAINTENANCE UNLESS THEIR REMOVAL WOULD RESULT IN GREATER ENVIRONMENTAL IMPACT THAN LEAVING THEM IN PLACE.
- 13. WQ-3: STORE BMP MATERIALS ON-SITE TO PROVIDE COMPLETE PROTECTION OF EXPOSED AREAS AND PREVENT OFF-SITE SEDIMENT TRANSPORT.
- 14. WQ-4: PROVIDE TRAINING FOR PERSONNEL RESPONSIBLE FOR THE PROPER INSTALLATION, INSPECTION, AND MAINTENANCE OF ON-SITE BMPS.
- 15. WQ-5: REVEGETATE SPOIL AND STAGING AREAS WITHIN 30 DAYS OF COMPLETION OF MAINTENANCE ACTIVITIES.

 MONITOR AND MAINTAIN REVEGETATED AREAS FOR A PERIOD OF NOT LESS THAN 25 MONTHS FOLLOWING PLANTING.
- 16. WQ-7: AVOID STORING HAZARDOUS MATERIALS USED DURING MAINTENANCE WITHIN 50 FEET FROM STORM WATER FACILITIES. HAZARDOUS MATERIALS SHALL BE MANAGED AND STORED IN ACCORDANCE WITH APPLICABLE LOCAL, STATE, AND FEDERAL REGULATIONS.
- 17. WQ-8: STORE MAINTENANCE-RELATED TRASH IN AREAS AT LEAST 50 FEET FROM STORM WATER FACILITIES, AND REMOVE ANY TRASH RECEPTACLES REGULARLY (AT LEAST WEEKLY).
- 18. WQ-9: INSTALL A CHECK DAM OR OTHER COMPARABLE MECHANISM WHENEVER THE VELOCITY OF STORM WATER DURING A "BANK-FULL" STORM EVENT WOULD BE EXPECTED TO EXCEED THE VELOCITIES IDENTIFIED FOR UNLINED CHANNELS PER TABLE 1-104.108 OF THE CITY'S DESIGN MANUAL. THESE STRUCTURES MAY BE REMOVED WHEN VEGETATION GROWTH HAS REACHED A POINT WHERE THE STRUCTURE IS NO LONGER REQUIRED.
- 19. WQ-10: INSPECT EARTHEN-BOTTOM STORM WATER FACILITIES WITHIN 30 DAYS OF THE FIRST 2-YEAR STORM FOLLOWING MAINTENANCE. IMPLEMENT EROSION CONTROL MEASURES RECOMMENDED BY THE FIELD ENGINEER, SUCH AS FIBER BLANKETS, TO REMEDIATE SUBSTANTIAL EROSION WHICH HAS OCCURRED AND TO MINIMIZE FUTURE EROSION.

PEIR ENVIRONMENTAL MITIGATION MEASURES

GENERAL MITIGATION MEASURE 1 OF THE MITIGATION MONITORING AND REPORTING PROGRAM (MMRP) ADOPTED FOR THE MMP REQUIRES ALL OF THE MITIGATION MEASURES IDENTIFIED IN THE PROGRAM EIR (PEIR) BE INCLUDED WITH THE MAINTENANCE DOCUMENTS AND CONTRACT SPECIFICATIONS FOR EACH MAINTENANCE ACTIVITY. TO FULFILL THIS REQUIREMENT, THE MMRP IS INCLUDED IN ITS ENTIRETY AS ATTACHMENT 1 TO THIS IMP.

ADDITIONAL MAINTENANCE REQUIREMENTS

1. THE CITY SHALL NOTIFY CALIFORNIA DEPARTMENT OF FISH & WILDLIFE (CDFW), IN WRITING, AT LEAST FIVE DAYS PRIOR TO INITIATION OF CONSTRUCTION PRIOR TO COMPLETION OF CONSTRUCTION (PROJECT) ACTIVITIES. NOTIFICATION SHALL BE SENT TO CDFW'S SOUTH COAST OFFICE, ATTN: STREAMBED ALTERATION PROGRAM-SM# 1600-2011-0271-R5.

- 2. AVOID THE INTRODUCTION OF INVASIVE PLANT SPECIES WITH PHYSICAL EROSION CONTROL MEASURES.
- 3. PRIOR TO COMMENCING ANY MAINTENANCE ACTIVITY WHICH MAY IMPACT SENSITIVE BIOLOGICAL RESOURCES, THE MONITORING BIOLOGIST SHALL VERIFY THAT THE FOLLOWING ACTIONS HAVE BEEN TAKEN, AS APPROPRIATE:
 - -FENCING, FLAGGING, SIGNAGE OR OTHER MEANS TO PROTECT SENSITIVE RESOURCES TO REMAIN AFTER MAINTENANCE HAS BEEN IMPLEMENTED;

-NOISE ATTENUATION MEASURES NEEDED TO PROTECT SENSITIVE WILDLIFE ARE IN PLACE AND EFFECTIVE;

- -NESTING BIRDS HAVE BEEN IDENTIFIED AND NECESSARY MAINTENANCE SETBACKS HAVE BEEN ESTABLISHED
- IF MAINTENANCE IS TO OCCUR BETWEEN JANUARY 15 AND AUGUST 31.
- 4. IF ANY WILDLIFE IS ENCOUNTERED DURING THE COURSE OF MAINTENANCE, SAID WILDLIFE SHALL BE ALLOWED TO LEAVE THE MAINTENANCE AREA UNHARMED.



5620 FRIARS ROAD SAN DIEGO, CA 92110 619.291.0707 (FAX)619.291.4165 J-17204-L

rickengineering.com Riverside - Orange - San Luis Obispo - Bakersfield - Sacramento - Phoenix - Tucson ENGINEER OF WORK

CARSON P. EDGINGTON R.C.E. 76519 DATE

P. EDGINGTON NO. 76519

* STATE OF CALLFORN

MASTER MAINTENANCE PROGRAM (MMP) PROTOCOL REQUIREMENTS AND PEIR ENVIRONMENTAL MITIGATION MEASURES: MONTEZUMA CREEK CHANNEL MAP #66

TRAN	CITY OF ISPORTATI	I.O. NO			
FOR CITY ENGINEER DATE					V.T.M
DESCRIPTION	BY	APPROVED	DATE	FILMED	
ORIGINAL	REC				
					NAD83 COORDINATES
AS-BUILTS					LAMBERT COORDINATES
ONTRACTOR DATE STARTED NSPECTOR DATE COMPLETED				-4-D	

City of San Diego FY 19 Montezuma Creek Channel Maintenance MMP Map 66 Certification No. R9-2018-0107

ATTACHMENT 3 CEQA MITIGATION MONITORING AND REPORTING PROGRAM

CHAPTER 11.0 MITIGATION MONITORING AND REPORTING PROGRAM

Section 21081.6 of the State of California Public Resources Code requires a Lead or Responsible Agency that approves or carries out a project where an environmental impact report (EIR) has identified significant environmental effects to adopt a "reporting or monitoring program for adopted or required changes to mitigate or avoid significant environmental effects." The City of San Diego is the lead Agency for the Master Program PEIR, and, therefore, is responsible for implementation of the MMRP. Because the PEIR recommends measures to mitigate these impacts, an MMRP is required to ensure that adopted mitigation measures are implemented.

As Lead Agency for the proposed project under CEQA, the City of San Diego will administer the MMRP for the following environmental issue areas: biological resources, historical resources, land use policies, paleontological resources, and water quality.

GENERAL

General Mitigation 1: Prior to commencement of work, the ADD Environmental Designee of the Entitlements Division shall verify that mitigation measures for impacts to biological resources (Mitigation Measures 4.3.1 through 4.3.20), historical resources (Mitigation Measures 4.4.1 and 4.4.2), land use policy (Mitigation Measures 4.1.1 through 4.1.13), paleontological resources (Mitigation Measure 4.7.1), and water quality (Mitigation Measures 4.8.1 through 4.8.3) have been included in entirety on the submitted maintenance documents and contract specifications, and included under the heading, "Environmental Mitigation Requirements." In addition, the requirements for a Pre-maintenance Meeting shall be noted on all maintenance documents.

General Mitigation 2: Prior to the commencement of work, a Pre-maintenance Meeting shall be conducted and include, as appropriate, the MMC, SWD Project Manager, Biological Monitor, Historical Monitor, Paleontological Monitor, Water Quality Specialist, and Maintenance Contractor, and other parties of interest.

General Mitigation 3: Prior to the commencement of work, evidence of compliance with other permitting authorities is required, if applicable. Evidence shall include either copies of permits issued, letters of resolution issued by the Responsible Agency documenting compliance, or other evidence documenting compliance and deemed acceptable by the ADD Environmental Designee.

General Mitigation 4: Prior to commencement of work and pursuant to Section 1600 et seq. of the State of California Fish & Game Code, evidence of compliance with Section 1605 is required, if applicable. Evidence shall include either copies of permits issued, letters of resolution issued by the Responsible Agency documenting compliance, or other evidence documenting compliance and deemed acceptable by the ADD Environmental Designee.

BIOLOGICAL RESOURCES

Potential impacts to biological resources would be reduced to below a level of significance through implementation of the following mitigation measures as well as Mitigation Measures 4.1-1 through 4.1-25.

Mitigation Measure 4.3.1: Prior to commencement of any activity within a specific annual maintenance program, a qualified biologist shall prepare an IBA for each area proposed to be maintained. The IBA shall be prepared in accordance with the specifications included in the Master Program.

Mitigation Measure 4.3.2: No maintenance activities within a proposed annual maintenance program shall be initiated before the City's Assistant Deputy Director (ADD) Environmental Designee and state and federal agencies with jurisdiction over maintenance activities have approved the IMPs and IBAs including proposed mitigation for each of the proposed activities. In their review, the ADD Environmental Designee and agencies shall confirm that the appropriate maintenance protocols have been incorporated into each IMP.

Mitigation Measure 4.3.3: No maintenance activities within a proposed annual maintenance program shall be initiated until the City's ADD Environmental Designee and Mitigation Monitoring Coordinator (MMC) have approved the qualifications for biologist(s) who shall be responsible for monitoring maintenance activities which may impact sensitive biological resources.

Mitigation Measure 4.3.4: Prior to undertaking any maintenance activity included in an annual maintenance program, a mitigation account shall be established to provide sufficient funds to implement all biological mitigation associated with the proposed maintenance activities. The fund amount shall be determined by the ADD Environmental Designee. The account shall be managed by the City's SWD, with quarterly status reports submitted to DSD. The status reports shall separately identify upland and wetland account activity. Based upon the impacts identified in the IBAs, money shall be deposited into the account, as part of the project submittal, to ensure available funds for mitigation.

Mitigation Measure 4.3.5: Prior to commencing any activity that could impact wetlands, evidence of compliance with other permitting authorities is required, if applicable. Evidence shall include copies of permits issued, letters of resolution issued by the Responsible Agency documenting compliance, or other evidence documenting compliance and deemed acceptable by the ADD Environmental Designee.

Mitigation Measure 4.3.6: Prior to commencing any activity where the IBA indicates significant impacts to biological resources may occur, a pre-maintenance meeting shall be held on site with the following in attendance: City's SWD Maintenance Manager (MM), MMC, and Maintenance Contractor (MC). The biologist selected to monitor the activities shall be present. At this meeting, the monitoring biologist shall identify and discuss the maintenance protocols that apply to the maintenance activities.

At the pre-maintenance meeting, the monitoring biologist shall submit to the MMC and MC a copy of the maintenance plan (reduced to 11"x17") that identifies areas to be protected, fenced, and monitored. This data shall include all planned locations and design of noise attenuation walls or other devices. The monitoring biologist also shall submit a maintenance schedule to the MMC and MC indicating when and where monitoring is to begin and shall notify the MMC of the start date for monitoring.

Mitigation Measure 4.3.7: Within three months following the completion of mitigation monitoring, two copies of a written draft report summarizing the monitoring shall be prepared by the monitoring biologist and submitted to the MMC for approval. The draft monitoring report shall describe the results including any remedial measures that were required. Within 90 days of receiving comments from the MMC on the draft monitoring report, the biologist shall submit one copy of the final monitoring report to the MMC.

Mitigation Measure 4.3.8: Within six months of the end of an annual storm water facility maintenance program, the monitoring biologist shall complete an annual report which shall be distributed to the following agencies: the City of San Diego DSD, CDFG, RWQCB, USFWS, and Corps. At a minimum, the report shall contain the following information:

- Tabular summary of the biological resources impacted during maintenance and the mitigation;
- Master table containing the following information for each individual storm water facility or segment which is regularly maintained;
- Date and type of most recent maintenance;
- Description of mitigation which has occurred; and
- Description of the status of mitigation which has been implemented for past maintenance activities.

Mitigation Measure 4.3.9: Wetland impacts resulting from maintenance shall be mitigated in one of the following three-two ways: (1) habitat creation, restoration, and/or enhancement-concurrent with maintenance, (2) habitat creation, restoration, and/or enhancement prior to maintenance, or (32) mitigation credits. The amount of mitigation When mitigation is proposed to be accomplished through concurrent creation, restoration or enhancement, the amount of planting-shall be in accordance with ratios in Table 4.3-10 unless different mitigation ratios are required by state or federal agencies with jurisdiction over the impacted wetlands. In this event, the mitigation ratios required by these agencies will supersede, and not be in addition to, the ratios defined in Table 4.3-10. When previously created, restored or enhanced wetland habitat is proposed to be used for mitigation, the ratio shall be 1:1, provided the habitat has been determined to be successfully established by the ADD Environmental Designee in consultation with the Resource Agencies prior to commencing the maintenance activity. Mitigation credits may be used at a ratio of 1:1, provided the mitigation credits are from a mitigation bank which has been approved by the Resource Agencies.—No maintenance shall commence until the ADD Environmental Designee has

determined that mitigation proposed for a specific maintenance activity meets one of these three two options.

Table 4.3-10 WETLAND MITIGATION RATIOS					
WETLAND TYPE	MITIGATION RATIO ¹				
Southern riparian forest	3:1				
Southern sycamore riparian woodland	3:1				
Riparian woodland	3:1				
Coastal saltmarsh	4:1				
Coastal brackish marsh	4:1				
Southern willow scrub	2:1				
Mule fat scrub	2:1				
Riparian scrub ¹	2:1				
Freshwater marsh ²	<u> 12</u> :1				
Cismontane alkali marsh	4:1				
Disturbed wetland	<u> 12</u> :1				
Streambed/natural flood channel	NA2:1				

¹ Mitigation ratio within the Coastal Zone will be 3:1

Mitigation locations for wetland impacts shall be selected using the following order of preference, based on the best mitigation value to be achieved.

- 1. Within impacted watershed, within City limits.
- 2. Within impacted watershed, outside City limits on City-owned or other publicly-owned land.
- 3. Outside impacted watershed, within City limits.
- 4. Outside impacted watershed, outside City limits on City-owned or other publically-owned land.

In order to mitigate for impacts in an area outside the limits of the watershed within which the impacts occur, the SWD must demonstrate to the satisfaction of the ADD Environmental Designee in consultation with the Resource Agencies that no suitable location exists within the impacted watershed.

Mitigation Measure 4.3.10: Whenever maintenance will impact wetland vegetation, a wetland mitigation plan shall be prepared in accordance with the Conceptual Wetland Restoration Plan contained in Appendix H of the Biological Technical Report, included as Appendix D.3 of the PEIR.

² <u>Mitigation ratio within the Coastal Zone will be 4:1</u> ⁴ Mitigation done in advance or through purchase of mitigation credits would be at a 1:1 ratio.

Mitigation which involves habitat enhancement, restoration or creation shall include a wetland mitigation plan containing the following information:

- Conceptual planting plan including planting zones, grading, and irrigation;
- Seed mix/planting palette;
- Planting specifications;
- Monitoring program including success criteria; and
- Long-term maintenance and preservation plan.

Mitigation which involves habitat acquisition and preservation shall include the following:

- Location of proposed acquisition;
- Description of the biological resources to be acquired including support for the conclusion that the acquired habitat mitigates for the specific maintenance impact; and
- Documentation that the mitigation area would be adequately preserved and maintained in perpetuity.

Mitigation which involves the use of mitigation credits shall include the following:

- Location of the mitigation bank;
- Description of the credits to be acquired including support for the conclusion that the acquired habitat mitigates for the specific maintenance impact; and
- Documentation that the credits are associated with a mitigation bank which has been approved by the appropriate Resource Agencies.

Mitigation Measure 4.3.11: Upland impacts shall be mitigated through payment into the City's Habitat Acquisition Fund, acquisition and preservation of specific land, or purchase of mitigation credits in accordance with the ratios identified in Table 4.3-11. Upland mitigation shall be completed within six months of the date the related maintenance has been completed.

Table 4.3-11 UPLAND HABITAT MITIGATION RATIOS ¹						
Vegetation Type	Tier	Location of Impact with Respect to the MHPA				
		Inside	Outside			
Coast live oak woodland	I	2:1	1:1			
Scrub oak chaparral	I	2:1	1:1			
Southern foredunes	I	2:1	1:1			
Beach	I	2:1	1:1			
Diegan coastal sage scrub	II	1:1	1:1			
Coastal sage-chaparral scrub	II	1:1	1:1			
Broom baccharis scrub	II	1:1	1:1			
Southern mixed chaparral	IIA	1:1	0.5:1			
Non-native grassland	IIIB	1:1	0.5:1			
Eucalyptus woodland	IV					
Non-native vegetation/ornamental	IV					
Disturbed habitat/ruderal	IV					
Developed	IV					

¹Assumes mitigation occurs within an MHPA

Mitigation Measure 4.3.12: Loss of habitat for the coastal California gnatcatcher shall be mitigated through the acquisition of suitable habitat or mitigation credits at a ratio of 1:1. Mitigation shall take place within the MHPA, and shall be accomplished within six months of the date maintenance is completed.

Mitigation Measure 4.3.13: Prior to commencing any maintenance activity which may impact sensitive biological resources, the monitoring biologist shall verify that the following actions have been taken, as appropriate:

- Fencing, flagging, signage, or other means to protect sensitive resources to remain after maintenance have been implemented;
- Noise attenuation measures needed to protect sensitive wildlife are in place and effective; and/or
- Nesting raptors have been identified and necessary maintenance setbacks have been established if maintenance is to occur between January 15 and August 31.

The designated biological monitor shall be present throughout the first full day of maintenance, whenever mandated by the associated IBA. Thereafter, through the duration of the maintenance activity, the monitoring biologist shall visit the site weekly to confirm that measures required to protect sensitive resources (e.g., flagging, fencing, noise barriers) continue to be effective. The monitoring biologist shall document monitoring events via a Consultant Site Visit Record. This record shall be sent to the MM each month. The MM will forward copies to MMC.

Mitigation Measure 4.3.14: Whenever off-site mitigation would result in a physical disturbance to the proposed mitigation area, the City will conduct an environmental review of the proposed mitigation plan in accordance with CEQA. If the off-site mitigation would have a significant impact on biological resources associated with the mitigation site, mitigation measures will be identified and implemented in accordance with the MMRP resulting from that CEQA analysis.

Mitigation Measure 4.3.15: Impacts to listed or endemic sensitive plant species shall be offset through implementation of one or a combination of the following actions:

- Impacted plants would be salvaged and relocated;
- Seeds from impacted plants would be collected for use at an off-site location;
- Off-site habitat that supports the species impacted shall be enhanced and/or supplemented with seed collected on site; and/or
- Comparable habitat at an off-site location shall be preserved.

Mitigation which involves relocation, enhancement or transplanting sensitive plants shall include the following:

- Conceptual planting plan including grading and, if appropriate, temporary irrigation;
- Planting specifications;
- Monitoring Program including success criteria; and
- Long-term maintenance and preservation plan.

Mitigation Measure 4.3.16: Maintenance activities shall not occur within the following areas:

- 300 feet from any nesting site of Cooper's hawk (Accipiter cooperii);
- 1,500 feet from known locations of the southern pond turtle (*Clemmys marmorata pallida*);
- 900 feet from any nesting sites of northern harriers (*Circus cyaneus*);
- 4,000 feet from any nesting sites of golden eagles (*Aquila chrysaetos*); or
- 300 feet from any occupied burrow or burrowing owls (*Athene cunicularia*).

Mitigation Measure 4.3.17: If evidence indicates the potential is high for a listed species to be present, based on historical records or site conditions, then clearing, grubbing, or grading (inside and outside the MHPA) shall be restricted during the breeding season where development may impact the following species:

- Light-footed clapper rail (between February 15 and August 15);
- Western snowy ployer (between March 1 and September 15);
- Least tern (between April 1 and September 15);
- Cactus wren (between February 15 and August 15); or
- Tricolored black bird (between March 1 and August 1.

When other sensitive species, including, but not limited to, the arroyo toad, burrowing owl, or Quino checkerspot butterfly are known or suspected to be present all appropriate protocol surveys and mitigation measures shall be implemented.

Mitigation Measure 4.3.18: If a subject species is not detected during the protocol survey, the qualified biologist shall submit substantial evidence to the ADD Environmental Designee and an applicable resource agency which demonstrates whether or not mitigation measures such as noise walls are necessary between the dates stated above for each species. If this evidence concludes that no impacts to this species are anticipated, no mitigation measures would be necessary.

Mitigation Measure 4.3.19: If the SWD chooses not to do the required surveys, then it shall be assumed that the appropriate avian species are present and all necessary protection and mitigation measures shall be required as described in Mitigation Measure 4.3.21

Mitigation Measure 4.3.20: If no surveys are completed and no sound attenuation devices are installed, it will be assumed that the habitat in question is occupied by the appropriate species and that maintenance activities would generate more than 60dB(A) L_{eq} within the habitat requiring protection. All such activities adjacent to the protected habitat shall cease for the duration of the breeding season of the appropriate species and a qualified biologist shall establish a limit of work.

Mitigation Measure 4.3.21: If maintenance occurs during the raptor breeding season (January 15 to August 31), a pre-maintenance survey for active raptor nests shall be conducted in areas supporting suitable habitat. If active raptor nests are found, maintenance shall not occur within 300 feet of a Cooper's hawk nest, 900 feet of a northern harrier's nest, or 500 feet of any other raptor's nest until any fledglings have left the nest.

Mitigation Measure 4.3.22: If removal of any eucalyptus trees or other trees used by raptors for nesting within a maintenance area is proposed during the raptor breeding season (January 15 through August 31), a qualified biologist shall ensure that no raptors are nesting in such trees. If

maintenance occurs during the raptor breeding season, a pre-maintenance survey shall be conducted and no maintenance shall occur within 300 feet of any nesting site of Cooper's hawk or other nesting raptor until the young fledge. Should the biologist determine that raptors are nesting, the trees shall not be removed until after the breeding season. In addition, if removal of grassland or other habitat appropriate for nesting by northern harriers, a qualified biologist shall ensure that no harriers are nesting in such areas. If maintenance occurs during the raptor breeding season, a pre-maintenance survey shall be conducted and no maintenance shall occur within 900 feet of any nesting site of northern harrier until the young fledge.

Mitigation Measure 4.3.23: If maintenance activities would occur at known localities for listed fish species or within suitable habitat for other highly sensitive aquatic species (i.e., southwestern pond turtle), avoidance or minimization measures (i.e., exclusionary fencing, dewatering of the activity area, live-trapping, and translocation to suitable habitat) must be implemented.

Mitigation Measure 4.3.24: If maintenance activities will occur within areas supporting listed and/or narrow endemic plants, the boundaries of the plant populations designated sensitive by the resource agencies will be clearly delineated with flagging or temporary fencing that must remain in place for the duration of the activity.

Mitigation Measure 4.3.25: In order to avoid impacts to nesting avian species, including those species not covered by the MSCP, maintenance within or adjacent to avian nesting habitat shall occur outside of the avian breeding season (January 15 to August 31) unless postponing maintenance would result in a threat to human life or property.

HISTORICAL RESOURCES

Potential impacts to historical resources would be reduced to below a level of significance through implementation of the following mitigation measures.

Mitigation Measure 4.4.1: Prior to commencement of the first occurrence of maintenance activity within a drainage facility included in the Master Program, an archaeologist, meeting the qualifications specified by the City's HRG, shall determine the potential for significant historical resources to occur in the maintenance area. If the archaeologist determines that the potential is moderate to high, an IHA shall be prepared. Based on the IMP for the proposed maintenance activity, the archaeologist shall determine the APE, which shall include access, staging, and maintenance areas. The IHA shall include a field survey of the APE with a Native American monitor, using the standards of the City's HRG. In addition, the archaeologist shall request a record search from the SCIC. Based on the results of the field survey and record search, the archaeologist shall conduct an archaeological testing program for any identified historical resources, using the standards of the City's HRG. If significant historical resources are identified, they shall be taken to the Historical Resources Board for designation as Historic Sites. Avoidance or implementation of an Archaeological Data Recovery Program (ADRP) and Archaeological Monitoring Program shall be required to mitigate project impacts to significant historical resources. The archaeologist shall prepare a report in accordance with City guidelines. At a minimum, the IHA report shall include:

• Description of maintenance to be performed, including length, width, and depth;

D. Final Monitoring Report(s)

- 1. The PI shall submit one copy of the approved Final Monitoring Report to the RE or BI as appropriate, and one copy to MMC (even if negative), within 90 days after notification from MMC of the approved report.
- 2. The RE shall, in no case, issue the Notice of Completion until receiving a copy of the approved Final Monitoring Report from MMC which includes the Acceptance Verification from the curation institution.

LAND USE

Potential impacts to land use policies in the City's General Plan would be reduced to below a level of significance through implementation of the following mitigation measures.

Mitigation Measure 4.1.1: Prior to commencing maintenance on any storm water facility within, or immediately adjacent to, a Multi-Habitat Planning Area (MHPA), the ADD Environmental Designee shall verify that all MHPA boundaries and limits of work have been delineated on all maintenance documents.

Mitigation Measure 4.1.2: A qualified biologist (possessing a valid Endangered Species Act Section 10(a)(1)(a) recovery permit) shall survey those habitat areas inside and outside the MHPA suspected to serve as habitat (based on historical records or site conditions) for the coastal California gnatcatcher, least Bell's vireo and/or other listed species. Surveys for the appropriate species shall be conducted pursuant to the protocol survey guidelines established by the U.S. Fish and Wildlife Service. When other sensitive species, including, but not limited to, the arroyo toad, burrowing owl, or Quino checkerspot butterfly are known or suspected to be present all appropriate protocol surveys and mitigation measures identified in Subchapter 4.3, Biological Resources, required shall be implemented.

Mitigation Measure 4.1.3: If a listed species is located within 500 feet of a proposed maintenance activity and maintenance would occur during the associated breeding season, an analysis of the noise generated by maintenance activities shall be completed by a qualified acoustician (possessing current noise engineer license or registration with monitoring noise level experience with listed animal species) and approved by the ADD Environmental Designee. The analysis shall identify the location of the 60 dB(A) L_{eq} noise contour on the maintenance plan. The report shall also identify measures to be undertaken during maintenance to reduce noise levels.

Mitigation Measure 4.1.4: Based on the location of the $60 \, dB(A) \, L_{eq}$ noise contour and the results of the protocol surveys, the Project Biologist shall determine if maintenance has the potential to impact breeding activities of listed species. If one or more of the following species are determined to be significantly impacted by maintenance, then maintenance (inside and outside the MHPA) shall avoid the following breeding seasons unless it is determined that maintenance is needed to protect life or property.

• Coastal California gnatcatcher (between March 1 and August 15 inside the MHPA only; no restrictions outside MHPA);

- Least Bell's vireo (between March 15 and September 15); and
- Southwestern willow flycatcher (between May 1 and September 1).

Mitigation Measure 4.1.5: If maintenance is required during the breeding season for a listed bird to protect life or property, then the following conditions must be met:

- At least two weeks prior to the commencement of maintenance activities, under the direction of a qualified acoustician, noise attenuation measures (e.g., berms, walls) shall be implemented to ensure that noise levels resulting from maintenance activities shall not exceed 60 dB(A) hourly average at the edge of occupied habitat. Concurrent with the commencement of maintenance activities and the maintenance of necessary noise attenuation facilities, noise monitoring shall be conducted at the edge of the occupied habitat area to ensure that noise levels do not exceed 60 dB(A) hourly average. If the noise attenuation techniques implemented are determined to be inadequate by the qualified acoustician or biologist, then the associated maintenance activities shall cease until such time that adequate noise attenuation is achieved or until the end of the breeding season of the subject species, as noted above.
- Maintenance noise shall continue to be monitored at least twice weekly on varying days, or more frequently depending on the maintenance activity, to verify that noise levels at the edge of occupied habitat are maintained below 60 dB(A) hourly average. If not, other measures shall be implemented in consultation with the biologist and the ADD, as necessary, to reduce noise levels to below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. Such measures may include, but are not limited to, limitations on the placement of maintenance equipment and the simultaneous use of equipment.
- Prior to the commencement of maintenance activities that would disturb sensitive
 resources during the breeding season, the biologist shall ensure that all fencing, staking
 and flagging identified as necessary on the ground have been installed properly in the
 areas restricted from such activities.
- If noise attenuation walls or other devices are required to assure protection to identified wildlife, then the biologist shall make sure such devices have been properly constructed, located and installed.

Mitigation Measure 4.1.6: A pre-maintenance meeting shall be held with the Maintenance Contractor, City representative and the Project Biologist. The Project Biologist shall discuss the sensitive nature of the adjacent habitat with the crew and subcontractor. Prior to the pre-maintenance meeting, the following shall be completed:

• The Storm Water Division (SWD) shall provide a letter of verification to the Mitigation Monitoring Coordination Section stating that a qualified biologist, as defined in the City of San Diego Biological Resources Guidelines, has been retained to implement the

projects MSCP monitoring Program. The letter shall include the names and contact information of all persons involved in the Biological Monitoring of the project. At least thirty days prior to the pre-maintenance meeting, the qualified biologist shall submit all required documentation to MMC, verifying that any special reports, maps, plans and time lines, such as but not limited to, revegetation plans, plant relocation requirements and timing, MSCP requirements, avian or other wildlife protocol surveys, impact avoidance areas or other such information has been completed and updated.

• The limits of work shall be clearly delineated. The limits of work, as shown on the approved maintenance plan, shall be defined with orange maintenance fencing and checked by the biological monitor before initiation of maintenance. All native plants or species of special concern, as identified in the biological assessment, shall be staked, flagged and avoided within Brush Management Zone 2, if applicable.

Mitigation Measure 4.1.7: Maintenance plans shall be designed to accomplish the following.

- Invasive non-native plant species shall not be introduced into areas adjacent to the MHPA. Landscape plans shall contain non-invasive native species adjacent to sensitive biological areas, as shown on the approved maintenance plan.
- All lighting adjacent to, or within, the MHPA shall be shielded, unidirectional, low
 pressure sodium illumination (or similar) and directed away from sensitive areas using
 appropriate placement and shields. If lighting is required for nighttime maintenance, it
 shall be directed away from the preserve and the tops of adjacent trees with potentially
 nesting raptors, using appropriate placement and shielding.
- All maintenance activities (including staging areas and/or storage areas) shall be
 restricted to the disturbance areas shown on the approved maintenance plan. The project
 biologist shall monitor maintenance activities, as needed, to ensure that maintenance
 activities do not encroach into biologically sensitive areas beyond the limits of work as
 shown on the approved maintenance plan.
- No trash, oil, parking or other maintenance-related activities shall be allowed outside the established maintenance areas including staging areas and/or storage areas, as shown on the approved maintenance plan. All maintenance related debris shall be removed off-site to an approved disposal facility.
- Access roads through MHPA-designated areas shall comply with the applicable policies contained in the "Roads and Utilities Construction and Maintenance Policies" identified in Section 1.4.2 of the City's Subarea Plan.

Mitigation Measure 4.1.8: Prior to commencing any maintenance in, or within 500 feet of any area determined to support coastal California gnatcatchers, the ADD Environmental Designee shall verify that the MHPA boundaries and the following project requirements regarding the coastal California gnatcatcher are shown on the maintenance plans:

NO MAINTENANCE ACTIVITIES SHALL OCCUR BETWEEN MARCH 1 AND AUGUST 15, THE BREEDING SEASON OF THE COASTAL CALIFORNIA GNATCATCHER, UNTIL THE FOLLOWING REQUIREMENTS HAVE BEEN MET TO THE SATISFACTION OF THE ADD ENVIRONMENTAL DESIGNEE:

- a. A QUALIFIED BIOLOGIST (POSSESSING A VALID ENDANGERED SPECIES ACT SECTION 10(a)(1)(A) RECOVERY PERMIT) SHALL SURVEY THOSE HABITAT AREAS <u>WITHIN THE MHPA</u> THAT WOULD BE SUBJECT TO MAINTENANCE NOISE LEVELS EXCEEDING 60 DECIBELS [dB(A)] HOURLY AVERAGE FOR THE PRESENCE OF THE COASTAL CALIFORNIA GNATCATCHER. SURVEYS FOR THE COASTAL CALIFORNIA GNATCATCHER SHALL BE CONDUCTED PURSUANT TO THE PROTOCOL SURVEY GUIDELINES ESTABLISHED BY THE U.S. FISH AND WILDLIFE SERVICE WITHIN THE BREEDING SEASON PRIOR TO THE COMMENCEMENT OF ANY MAINTENANCE. IF GNATCATCHERS ARE PRESENT, THEN THE FOLLOWING CONDITIONS MUST BE MET:
 - 1. BETWEEN MARCH 1 AND AUGUST 15, MAINTENANCE OF OCCUPIED GNATCATCHER HABITAT SHALL BE PERMITTED. AREAS RESTRICTED FROM SUCH ACTIVITIES SHALL BE STAKED OR FENCED UNDER THE SUPERVISION OF A QUALIFIED BIOLOGIST; AND
 - 2. BETWEEN MARCH 1 AND AUGUST 15, NO MAINTENANCE ACTIVITIES SHALL OCCUR WITHIN ANY PORTION OF THE SITE WHERE MAINTENANCE ACTIVITIES WOULD RESULT IN NOISE LEVELS EXCEEDING 60 dB(A) HOURLY AVERAGE AT THE EDGE OF OCCUPIED GNATCATCHER HABITAT. AN ANALYSIS SHOWING THAT NOISE GENERATED BY MAINTENANCE ACTIVITIES WOULD NOT EXCEED 60 dB(A) HOURLY AVERAGE AT THE EDGE OF OCCUPIED HABITAT MUST BE COMPLETED BY A QUALIFIED ACOUSTICIAN (POSSESSING CURRENT NOISE ENGINEER LICENSE OR REGISTRATION WITH MONITORING NOISE LEVEL EXPERIENCE WITH LISTED ANIMAL SPECIES) AND APPROVED BY THE CITY MANAGER AT LEAST TWO WEEKS PRIOR TO THE COMMENCEMENT OF MAINTENANCE ACTIVITIES. PRIOR TO THE COMMENCEMENT OF MAINTENANCE ACTIVITIES DURING THE BREEDING SEASON. AREAS RESTRICTED FROM SUCH ACTIVITIES SHALL BE STAKED OR FENCED UNDER THE SUPERVISION OF A **OUALIFIED BIOLOGIST: OR**
 - 3. AT LEAST TWO WEEKS PRIOR TO THE COMMENCEMENT OF MAINTENANCE ACTIVITIES, UNDER THE DIRECTION OF A QUALIFIED ACOUSTICIAN, NOISE ATTENUATION MEASURES (e.g.,

BERMS, WALLS) SHALL BE IMPLEMENTED TO ENSURE THAT NOISE LEVELS RESULTING FROM MAINTENANCE ACTIVITIES WILL NOT EXCEED 60 dB(A) HOURLY AVERAGE AT THE EDGE OF HABITAT OCCUPIED BY THE COASTAL CALIFORNIA GNATCATCHER. CONCURRENT WITH THE COMMENCEMENT OF MAINTENANCE ACTIVITIES AND THE MAINTENANCE OF NECESSARY NOISE ATTENUATION FACILITIES. NOISE MONITORING* SHALL BE CONDUCTED AT THE EDGE OF THE OCCUPIED HABITAT AREA TO ENSURE THAT NOISE LEVELS DO NOT EXCEED 60 dB(A) HOURLY AVERAGE. IF THE NOISE ATTENUATION TECHNIQUES IMPLEMENTED ARE DETERMINED TO BE INADEQUATE BY THE QUALIFIED ACOUSTICIAN OR BIOLOGIST, THEN THE ASSOCIATED MAINTENANCE ACTIVITIES SHALL CEASE UNTIL SUCH TIME THAT ADEQUATE NOISE ATTENUATION IS ACHIEVED OR UNTIL THE END OF THE BREEDING SEASON (AUGUST 16).

- * Maintenance noise shall continue to be monitored at least twice weekly on varying days, or more frequently depending on the maintenance activity, to verify that noise levels at the edge of occupied habitat are maintained below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. If not, other measures shall be implemented in consultation with the biologist and the ADD environmental designee, as necessary, to reduce noise levels to below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. Such measures may include, but are not limited to, limitations on the placement of maintenance equipment and the simultaneous use of equipment.
- b. IF COASTAL CALIFORNIA GNATCATCHERS ARE NOT DETECTED DURING THE PROTOCOL SURVEY, THE QUALIFIED BIOLOGIST SHALL SUBMIT SUBSTANTIAL EVIDENCE TO THE CITY MANAGER AND APPLICABLE RESOURCE AGENCIES WHICH DEMONSTRATES WHETHER OR NOT MITIGATION MEASURES SUCH AS NOISE WALLS ARE NECESSARY BETWEEN MARCH 1 AND AUGUST 15 AS FOLLOWS:
 - 1. IF THIS EVIDENCE INDICATES THE POTENTIAL IS HIGH FOR COASTAL CALIFORNIA GNATCATCHER TO BE PRESENT BASED ON HISTORICAL RECORDS OR SITE CONDITIONS, THEN CONDITION A.III SHALL BE ADHERED TO AS SPECIFIED ABOVE.
 - 2. IF THIS EVIDENCE CONCLUDES THAT NO IMPACTS TO THIS SPECIES ARE ANTICIPATED, NO MITIGATION MEASURES WOULD BE NECESSARY.

- return to PI with copy submitted to MMC.
- 4. The PI shall include the Acceptance Verification from the curation institution in the Final Monitoring Report submitted to the RE or BI and MMC.
- D. Final Monitoring Report(s)
 - 1. The PI shall submit two copies of the Final Monitoring Report to MMC (even if negative), within 90 days after notification from MMC of the approved report.
 - 2. The RE shall, in no case, issue the Notice of Completion until receiving a copy of the approved Final Monitoring Report from MMC which includes the Acceptance Verification from the curation institution.

WATER QUALITY

Potential impacts to water quality would be reduced to below a level of significance through implementation of the following mitigation measures.

Mitigation Measure 4.8.1: Prior to commencement of any activity within a specific annual maintenance program, a qualified water quality specialist shall prepare an IWQA for each area proposed to be maintained. The IWQA shall be prepared in accordance with the specifications included in the Master Program. If the IWQA indicates that maintenance would impact a water pollutant where the existing level for that pollutant exceeds or is within 25 percent of the standard established by the San Diego Basin Plan, mitigation measures identified in Table 4.8-8 shall be incorporated into the IMP to reduce the impact to within the established standard for that pollutant.

Table 4.8-8 MITIGATION MEASURES FOR REDUCED POLLUTANT REMOVAL CAPACITY										
MITIGATION	MEASURI	ES FOR R	EDUCED	POLLUTA	NT REMU	OVAL CAP	<u>ACITY</u>			
	Pollutant Type									
Mitigation Measure	Bacteria	Metals	Nutrients	Pesticides	Sediment	TDS/ Chloride Sulfates	Trash			
Remove kelp on beaches					•	•				
Sweep streets	•	•	•	•	•	•	•			
Retrofit residential landscaping to reduce runoff	•	•	•		•					
Install artificial turf	•	•	•	•	•		•			
Install inlet devices on storm drains		•	•		•					
Replace impermeable surfaces with permeable surfaces		<u>•</u>	•		<u>•</u>		<u>•</u>			

Table 4.8-8 (cont.) MITIGATION MEASURES FOR REDUCED POLLUTANT REMOVAL CAPACITY										
MITIGATION	MEASURI	ES FOR R	EDUCED	POLLUTA	NI KEMO	OVAL CAP	<u>ACITY</u>			
	Pollutant Type									
						TDS/				
Mitigation	.	3.5 . 3	N T (• (D (1.1)	G 11	<u>Chloride</u>	75. 1			
<u>Measure</u>	<u>Bacteria</u>	<u>Metals</u>	<u>Nutrients</u>	<u>Pesticides</u>	<u>Sediment</u>	<u>Sulfates</u>	<u>Trash</u>			
<u>Install modular</u>										
storm water		•	•	•	•	•	•			
<u>filtration systems</u>		<u> </u>	_	_		_				
<u>Install storm water</u>		•								
retention basins		<u> </u>)	_	<u> </u>			
Install catch basin										
media filters		_	_		_	_	_			
Create vegetated							•			
<u>swales</u>	_	_	_	_	_		_			
Restore wetlands	•	•	•	•	•	•	•			
Install check dams	_	•	_	_	•	_	•			

Mitigation Measure 4.8.2: No maintenance activities within a proposed annual maintenance program shall be initiated before the City's ADD Environmental Designee and state and federal agencies with jurisdiction over maintenance activities have approved the IMPs and IWQAs including proposed mitigation and BMPs for each of the proposed activities. In their review, the ADD Environmental Designee and agencies shall also confirm that the appropriate maintenance protocols have been incorporated into each IMP.

Mitigation Measure 4.8.3: Prior to commencing any activity where the IWQA indicates significant water quality impacts may occur, a pre-maintenance meeting shall be held on site with following in attendance: City's SWD, MM, MMC, and MC. A qualified water quality specialist shall also be present. At this meeting, the water quality specialist shall identify and discuss mitigation measures, protocols and BMPs identified in the IWQA that must be carried out during maintenance. After the meeting, the water quality specialist shall provide DSD with a letter indicating that the applicable mitigation measures, protocols and BMPs identified in the IWQA have been appropriately implemented.