

# Notice of Dredge or Fill Discharge Applications received from 8/5/2009

Report Generated On: Monday, June 07, 2010

File Number	Project Name	County	City	Federal/NF	Brief Description	Applicant Organization	Agent Organization	Staff
362010-04	330 PM36.25 Culvert Failure	San Bernardino	San Bernardino	Federal	Excavation and removal of failed culvert, installation of similarly sized new culvert, and replacement of excavated fill, and pavement of roadway surface.	Caltrans District 8, Biological Construction Monitoring		MKB
362010-02	Hunts Lane Seperation	San Bernardino	Colton and San Bernardino	Federal	Construct a roadway grade seperation by raising the Hunts Lane profile and providing a new bridge over railroad tracks. In addition, the profiles of cross-streets at Riverwood St., Commercial Rd., and Oliver Holmes Rd. will be raised to meet the new grade along Hunts Lane.	San Bernardino Associated Governments	Vandermost Consulting Services, Inc	MKB
362010-01	Maple Ln Drainage @ Sdwlk Imprvmnts	San Bernardino	Big Bear City	Federal	Fill highly incised drainage ditch with approximately 24,000 cubic yards of native fill material to stabilize grade, then place 1,230 linear feet of 48 inch pipe covered by 6 feet of fill. Ditch will be reconstructed as natural channel.	San Bernardino County Public Works Department		MKB
362009-17	TM-18393	San Bernardino	Chino Hills		Development of a 28-unit single family residential units within a 34.73 property boundary. Unavoidable permanent impacts to 0.17 ac of ACOE juresdiction of which 0.05 ac consist of juresdictional wetlands and temp impacts of which 0.002 ac consists of jjuresdictional wetlands	Stonefield Development Inc.	Glenn Lukos & Assocs	MKB
362009-16	Mill Creek Wetlands	San Bernardino	Chino	Federal	Proposed creation of a regional natural water quality treatment system by diverting dry and wet weather flows into and throughout a series of pods.	City of Ontario	Vandermost Consulting Services, Inc.	MKB
362009-15	Mission Blvd Widening	San Bernardino	Ontario	Federal	Mission to be widened from four to six lanes from Archibald to Haven Ave. with the addition of left turn deceleration lanes and drainage improvements as well.	City of Ontario	LSA Associates, Inc.	MKB
362009-14	East Branch Extension Phase I Improvement Project/ Crafton Hills Reservoir enlargement	San Bernardino	Yucaipa	Federal	The proposed East Branch Extension Phase I Improvements Project constructs a new pipeline, a new dam, and enlarges the existing Crafton Hills Reservoir from its current storage capacity of 85 acre-feet (af) to approximately 225 af.	Department of Water Resources		MKB
362009-13	Maintenance Station Upgrade at SR-38 in SB Cnty at PM 20.2.	San Bernardino	Angelous Oak	Federal	The purpose of this project is to overlay the maintenance station, install a fence over the perimeter, and replace a metal pipe that collects storm water runoff to un unnamed wash that ultimately flows to the Santa Ana River.	Caltrans	Caltrans	MKB
362009-12	SCE Transmission Pole Replacement-Prado Basin	San Bernardino	Chino Hills	Federal	SCE to replace two deteriorated transmission poles #s 1395230E & 45877E, located within the Prado Basin. Project is covered under the NWP 12 permit for Utility Line Activities and NMP 18 for Minor Discharge.	Southern California Edison	ICF Jones & Stokes/SCE	MKB
332010-18	Drainage Channel Improvement	Riverside	Unincorporated Del Luz, Temecula	Federal	Collect and transport surface runoff, to cycle sediment and nutrients, increase infiltration, and attenuate flow velocity.		LSA	MKB
332010-17	Lamb Cyn Landfill Expansion	Riverside	Beaumont	Federal	The placement of soil, landfill waste, and associated materials, within the 202.1-ac expansion area, and within a single 0.062-ac off-site drainage area ('D5') within the adjacent, active landfill operation.	Riverside County Waste Management Department	Riverside County Waste Management Department	MKB

File Number	Project Name	County	City	Federal/NF	Brief Description	Applicant Organization	Agent Organization	Staff
332010-16	Route 79 Improvements	Riverside	San Jacinto	Federal	Caltrans proposes to make drainage improvements, to have Metal Beam Guard Rail replacements, to restripe the road, and modify the lighting on Sandersen Ave between Ramona Expressway and Gilman Springs.	California Department of Transportation		MKB
332010-15	Day Creek Channel Stage 6	Riverside	Mira Loma	Federal	To convey the 100-year peak flow within the existing channel right of way and reconstruct the interim earthen/riprap channel as a lined channel, with subsequent O&M.	Riverside County Flood Control and Water Conservation District	Riverside County Flood Control and Water Conservation District	MKB
332010-12	Santa Ana Trunk Sewer Rplcmnt	Riverside	Riverside	Federal	Replace the existing aging trunk sewers located parallel to the Santa Ana River from the Tequesquite Avenue east to the City’s water quality treatment plant.	City of Riverside	City of Riverside Department of Public Works	MKB
332010-11	Box Springs Feeder Repair	Riverside	Riverside	Federal	Repair of twelve PCCP pipe sections using five excavation sites, including three excavation sites in Sycamore Canyon Wilderness Park.	Metropolitan Water District of Southeran California		MKB
332010-10	Brookside Streambed Rchrg	Riverside	Beaumont	Federal	Divert SWP water from Noble Creek Pipeline located beneath Orchard Street, to a proposed recharge area locate in Noble Creek located 1.1 miles to the south.	San Gorgonio Pass Water Agency	Michael Brandman Associates	MKB
332010-08	SCE Honeycrisp DSP Project	Riverside	Beaumont and South Calimesa	Federal	Construction and installation of 5 new vaults containing underground 12kV circuits. Will connect the substation with 2 underground 12kV distribution conduit systems, and each will convey 2 12kV circuits.	Southern California Edison	ICF	MKB
332010-07	Four Corners Storm Drain Prjct	Riverside	Lake Elsinore	Federal	Proposing to place ungrouted riprap along eroded sideslope and bury it w/approximately 18-24 in of topsoil to help stabilize the sideslope and protect it from further erosion.	Riverside County Flood Control and Water Conservation District	Riverside County Flood Control and Water Conservation District	MKB
332010-06	State Route 74 PM49.68 Rdwy Failure	Riverside	Area 5.4 Miles east of Hemet City Limits	Federal	Placement of new culvert in elevated roadway dike. 72 inch concrete pipe.	Caltrans District 8, Biological Construction Monitoring		MKB
332010-05	Corona Drains, E Ontario Ave Strm Drain, Stge 1	Riverside	Unincorporated Temescal Area and City of Corona	Federal	Project would ensure that the 100-year peak flows are conveyed within the proposed storm drain. Removal of 362 lineal feet of trapezoidal concrete channel, excavation to lower the invert of the channel and construction of approximately 362 lineal feet of concrete channel.	Riverside County Flood Control and Water Conservation District	Riverside County Flood Control and Water Conservation District	MKB
332010-04	El Cerrito Rd Improvement Project	Riverside	El Cerrito	Federal	Improve quality of life to community of El Cerrito by reducing traffic congestion in El Cerrito between Interstate 15 and East Ontario Ave/Temescal Canyon road and by providing storm drain facilities that will accommodate 100-year storm flows.	Redevelopment Agency for the County of Riverside	Krieger & Stewart	MKB
332010-03	Foothill Pkwy Westerly Rdwy Ext. Project	Riverside	Corona	Federal	To complete a critical east/west connection from its current terminus, approximately 600 feet west of Skyline Drive to Green River Road.	City of Corona	RBF Consulting	MKB
332010-02	SR60/ I 215 E Junction East-West HOV Project	Riverside	Box Springs, Riverside	Federal	To construct 2 new HOV connector lanes from those currentlty under construction to the existing HOV lanes on SR-60 at Day Street. The north frontage road (Box Springs Road) will be realigned and widened to accommodate the widening of northbound I-215 over the railroad tracks.	Riverside County Transportation Commission	LSA Associates, Inc.	MKB
332010-01	Hwy 74 Culvert Repair	Riverside	5.4 Miles east of Hemet City Limits	Federal	Storm runoff from hillside caused a 3’x4’ box culvert to be washed out under Hwy 74, which caused a 75’ section of roadway to be destroyed as well.	Caltrans District 8, Biological Construction Monitoring		MKB

File Number	Project Name	County	City	Federal/NF	Brief Description	Applicant Organization	Agent Organization	Staff
332009-25	Florida Promenade	Riverside	Hemet	Federal	100-110-unit hotel and related offsite improvements on a 7.23-acre site near the intersection of Myers Street and Florida Ave. in Hemet	DBJ Development Corporation		MKB
332009-24	Tequesquite Sewer Protection	Riverside	Riverside	Federal	Emergency work needed on 20 foot section of exposed of 27-inch sanitary sewer line that	City of Riverside		MKB
332009-23	I-215 W. Perimeter Drainage	Riverside	Menifee	Federal	Storm drain improvements involving construction of a culvert and reconstruction of a ditch adjacent to a new retail development.	Donahue Schriber Realty Group, Inc.	LSA Associates Inc.	MKB
332009-22	Heacock Bridge Replacement	Riverside	Moreno Valley	Federal	Replacement of Heacock Street Bridge which crosses over Perris Valley Storm Drain Lateral "A". Also, replacement of undersized drainage structure with a four-celled reinforced concrete box to convey 100 yr flows.	City of Moreno Valley Public Works Department	Ultra Systems	MKB
332009-21	I-15 V-Ditch Extension	Riverside	Norco		Extension of existing v-ditch on CalTrans property along the east side of I-15 between 3rd St and Wraymar in Norco.	Caltrans	Caltrans	MKB
332009-20	San Jacinto River Stage 2	Riverside	Community of Gilma Hot Springs		San Jacinto River Between Hwy 79 and Sanderson Ave. Restoration work to reconstruct failed concrete-lined sideslope including a 2.5 feet high floodwall of the San Jacinto River;s North levee.	Riverside County Flood Control and Water Conservation District	Riverside County Flood Control and Water Conservation District	MKB
332009-18	Ironwood Ave & Indian Detention Basin	Riverside	Moreno Valley	Federal	Imrpovements to Ironwood avenue to include rerouting storm sewer lines H and H-1 to flow directly into Indian Detention Basin. This will impact all flows to Bale Creek.	Public Works Dept, Capital Projects, City of Moreno Valley	AECOM	MKB
332009-17	Nason Street @ SR60 Interchange Improvement	Riverside	Moreno Valley	Federal	State Route 60/Sonny Bono Memorial Interchange improvements (Nason Street @ SR 60) and auxillary lanes. The project will improve ramp operation by reconfiguring the freeway rampls at Nason Street and adding turning lanes.	City of Moreno Valley	Parsons Brinkerhoff	MKB
332009-16	Centential Park_ Jurupa	Riverside	Riverside	Federal	Jurupa Area Recreationi on & Parks District (JARP) is proposing the creation of a recreational (sports) facility, through the modification of an existing earthen detention basin (the Jurupa Basin). The conversion would cuase the basioni to serve a dual purpose.	Jurupa Area Recreation & Park District	Cadre Environmental	MKB
332009-15	SCE_Pole Replacement_Pole #227972E_Mead Valley	Riverside	Mead Valley Area	Federal	Replacement and relocation of Valley-Bunker-Cajalco Pole No. 2276972E. New pole to be positioned on the east bank of the drainage ditch on raised ground approximately 2 feet above existing surface water level. During these activities, dewatering barriers will be used to remove water within the ditch.	Southern California Edison	ICF Jones & Stokes/SCE	MKB
332009-14	SARI Line Repairs (Reaches IV-A and IV-B)	Riverside	Corona		Inspections of interior SARI pipeline within these reaches have identified evidence of decay and bio-growth, which inhibits the flow of water through the pipe. Not making the repairs could result in failure, resulting in untreated wastewater to discharge into the water table behind Prado Dam. Proposed repairs to include Live Sliplining of Reach IV-B, Reach Lower IV-A and a portion of Reach Upper IV-A . The remaining Reach Upper IV-A to be repaired using Cured In Place Pipe (CIPP). Perminant impacts approx 0.028 acre due to necessary manhole extentions to compensate for increased sediment load buildup behind the dam.	11615 Sterling Avenue	RBF Consulting	MKB

File Number	Project Name	County	City	Federal/NF	Brief Description	Applicant Organization	Agent Organization	Staff
302010-17	Black Star Canyon Bridges	Orange	eastern-central Orange county	Federal	To reconstruct three bridges and replace them with pre-cast Portland Cement Concrete slabs to enable them to carry fire trucks to fight fires in the Cleveland National Forest.	Orange County Public Works		MKB
302010-11	Tiffany Pl Drainage Relocation	Orange	East Tustin	Federal	To abandon two deteriorating corrugated metal pipes (CMPs: which may soon collapse and thereby cause an adjacent home to sink) and install a new reinforced concrete pipe (RCP) in order to meet current standards of public health and safety.	Orange County Public Works		MKB
302010-03	SLAT Station 328+36 Dschrg	Orange	Irvine Park	Federal	To replace an existing discharge pipe to maintain operational integrity.	Metropolitan Water District of Southern California		MKB
302010-02	Santiago Cyn Rd Culvert @ Hicks Cyn Haul Rd	Orange	Santiago Canyon Road	Federal	Proposing a roadway drainage improvement project along Santiago Canyon Road which removes approximately 78 linear feet of CMP and is replaced with 48" Reinforced Concrete Pipe.	Orange County Public Works	URS Corp	MKB
302010-01	Residence Dock Rplcmnt	Orange	Newport Beach	Federal	Single-family residence dock replacement to allow berthing of owner's new boat. Remove and replace existing dock.		Shellmaker Inc.	MKB
302009-57	Back Bay Science Center - Boat Dock Replacement	Orange	Newport Beach		R & R old boat dock and replace with new (larger) U-Shaped Dock Structure	Department of Fish and Game, South Coast Region	California Department of Fish and Game	MKB
302009-55	Peters Canyon & Santa Ana Gardens Channels Maintenance Project	Orange	Tustin		Removal and replacement of lining in order to prevent further erosion.	Orange County Public Works		MKB
302009-54	Peters Canyon Dam Debris Removal	Orange	Santa Ana	Federal	Removal of debris that's accumulated behind Peters Canyon main dam outlet, as well as access areas and roads.	Orange County Public Works	Orange County Public Works	MKB
302009-51	Santiago Creek North Bike Trail North Segment	Orange	Orange	Federal	Construction of a off-road bike trail, north side of Villa Park Road (Hewes to Cannon).	City of Orange		MKB
302009-50	San Diego Creek Channel (Reach II)	Orange	Irvine	Federal	O & M Project from Campus Drive to just South of the I-405 Freeway	Orange County Public Works	ICF Jones & Stokes Associates	MKB
302009-49	Santiago Creek Crossing AZ Crossing	Orange	Unincorporated	Federal	At Arizona, downstream from Villa Park Dam, the project consitsts of raisingf the crossing approximately 2.5 feet. Project components include leveling the exisiting crossing to a smooth grade with a dozer, then three 18-foot sections of 28-inch by 20-inch squash CMPs will be laid perpendicular to the creek crossing to allow for water movement. Approx. 37 cu yds of cover will be placed on top of the pipes to build a ne 13-foot wide crossing.	OC Public Works	RBF Consulting	MKB
302009-48	Loftus Channel Improvements @ Birch Hills Golf Course	Orange	Brea		The in-place replacement of a 29.7 ft section of 18-in corrugated pipe w/ 43 ft of 18-in reinforced corrugated pipe.	Birch/Kraemer, LLC	PCR Services Corporation (PCR)	MKB

File Number	Project Name	County	City	Federal/NF	Brief Description	Applicant Organization	Agent Organization	Staff
302009-47	Barranca Channel (F09) Maintenance	Orange	Irvine		Bank stabilization at three sites within the Barranca Channel between McGaw and Jamboree in Irvine.	Orange County Public Works	Orange County Public Works	MKB
302009-45	East Garden Grove Wintersburg Channel (Tide Gates - Warner Ave)	Orange	Huntington Beach		This project was formerly under File Number 302007-20, prior to being withdrwn on 1/29/09. Improvements to a 9,568-linear foot section of the East Garden Grove-Wintersburg Channel (C05)/C06). The project includes soil-mix columns sandwiched between two parallel sheet pile walls. The resulting 3-tiered lines against inundation will replace the existing levees. Upon completion of the sheet pile excavation the County will then excavate the earthen side slopes back to the sheet piles to provide for the 100-yr storm water conveyance capacity within this channel reach. As part of this project, Slater Bridge is planned to be removed.	County of Orange, OC Public Works/Regulatory Permitting	BonTerra Consulting	MKB
302009-44	Los Alamos Channel-South Reach	Orange	Seal Beach		Maintenance Project includes excavation of 3050 cubic yards of eroded earthen fill in placement of approximately 5150 cubic yards of ungrouted 18-inch rock (8200 tons) along portions of the east side slope and a small area on the west side slope.	Orange County Public Works/Regulatory Permits	OCPW/Regulatory Permits	MKB
302009-43	Los Alamitos Channel Maintenance Project - Northern Reach	Orange	Los Alamitos	Federal	To improve the existing flood control channel and prevent further bank/slope erosion. Project consists of excavation of 4,700 cy of eroded earthen fill, increasing the channel width from 7.5 to 12 ft, and placement of approximately 14,000 tons of ungrouted 24" rock (8,750 cy) along the side slopes and the bottom invert for aproximately 2,534 linear ft (0.48 mi.) The grade of the slopes remain unchanged; therefore the existing profile (typical section) will increase in width at the bottom of the channel and the tops of the banks by 4.5 feet.	OC Public Works/ Regulatory Permits	OC Public Works/Regulatory Permits	MKB
302009-42	C05 Wintersburg Channel Maint Proj	Orange		Federal	Replacement of a section of 18 inch diameter corrugated metal pipe (CMP) that discharges to the existing outfall structure. The old pipe will be replaced with a new section of 18" CMPand to repair the eroded areas of the channel bank, immediately adjacent to the existing outfall structure within the Withersburg Channel (C05)	Orange County Public Works	OCPW	MKB
302009-41	Agua Chinon Retarding Basin	Orange	Unicorporated	Federal	Maintenance operations to clear out sediment flows that had accumulated within the Agua Chinon Retarding Basin following 2007 Santiago Canyon Fire.	Orange County Public Works		MKB
302009-40	Modena-Irvine Channel Bridge Widening	Orange	Tustin & Irvine	Federal	Add S/B Auxiliary Lane from Tustin Ranch Road to Jamboree Road and Widen Jamboree Road Off Ramp. Widening and Improvements along the I-5 Interchange.	CalTrans (District 12)		MKB
302009-39	Interstate 405/ Interstate 605 High Occupacy Vehicle Connector Project	Orange	Seal Beach	Federal	Add additional HOV lanes in each direction of I-405 through the Seal Beach Boulevard interchange; Connect the I-405 HOV lanes north of Seal Beach blvd to the HOV lanes on I-605 via a new direct connector structure. Reconstruct north 405-west 22 Connector; Reconstruct the east 22-north 405 Connector; Reconstruct east 22-north 605 Connector; Reconstruct the Seal Beach overcrossing. Convert trapezoidal Bixby Storm Channel to rectangular box channel to accomadate road widening and increase flow capacity	California Department of Transportation	TRC	MKB