

Eagle Mountain Pumped Storage Project – Seepage Analyses for Upper and Lower Reservoirs

Prepared by: Nick Miller and Dick Westmore, GEI Consultants, Inc.

January 5, 2009, revised January 5, 2011

This memorandum summarizes preliminary estimates of seepage from the proposed Upper and Lower Reservoirs for the Eagle Mountain Pumped Storage Project. In addition, this TM provides opinions on the potential effectiveness of using the available fine mine tailings as a seepage control blanket to minimize seepage losses from the Upper and Lower Reservoirs. This treatment measure was proposed in the earlier project concepts developed in the 1990s. We also assessed the potential effectiveness of other seepage control measures at the two reservoirs.

Due to the current access constraints at the site, all geotechnical and geological information used for the seepage estimates was obtained from prior investigations and studies conducted by GeoSyntec Consultants, GSi/Water, and GeoPentech in support of studies for a proposed landfill. The results of those studies represent an initial step in characterizing potential seepage impacts associated with the Eagle Mountain Project. Seepage impacts are of particular concern to the Metropolitan Water District of Southern California (MWD), the State Water Quality Board, and others in the region.

Site Geology

Bedrock geologic units present at the site can be generally classified as either igneous or meta-sedimentary. The igneous units include several varieties of granitic rock including porphyritic quartz monzonite, diorite, monzonite porphyry, and granodiorite. The meta-sedimentary units include quartzites, meta-arkoses, and marbles formed by metamorphism and/or hydrothermal-alteration or sandstones, conglomerates, arkoses, and carbonate rocks deposited in the Paleozoic or Precambrian age.

Surficial geology of the Eagle Mountain area generally consists of unconsolidated alluvial deposits. The alluvial deposits include sands, silts, gravels, and debris-flow deposits. The most significant alluvial deposits are found on the eastern edge of the site area, where they form a laterally extensive alluvial fan that extends and thickens to the east into the Chuckwalla Valley. Some of these deposits are exposed in the east wall of the east pit and underlie the eastern portion of the Lower Reservoir.

The alluvial deposits within the Chuckwalla Valley extend to significant depths below the ground surface and generally consist of sands, silty sands, sands and gravel, cobbles and boulders. Within the sandy alluvial deposits in the Chuckwalla Valley a predominately clay layer was logged in borings at depths varying from about 600 to 900 feet, and is generally about 100 to 300 feet in thickness.

The entire Central Pit (Upper Reservoir) is incised into bedrock. Alluvial deposits in the area of the Upper Reservoir are smaller in extent and are generally confined to laterally discontinuous, generally thin deposits along the bottoms of the canyons.

Rock containing little to no mineral value (waste rock and tailings) generated by the former Kaiser operations were deposited in numerous areas near the site. These mining by-products include several distinctly different materials, including both bedrock and alluvial overburden, and tailings produced as a result of the mining and separation of iron ore-bearing rock from host rock. The tailings include both fine and coarse varieties.

The hydraulically-placed fine tailings exist in settling ponds to the southeast of the proposed Upper Reservoir. Total volume of these materials is estimated to potentially be over 19 million cubic yards. Laboratory testing indicated that the fine tailings vary in composition, ranging from silty sand and sandy silt to clayey silt to silty clay. In general, soils with higher sand content are located near the slurry discharge point while finer grained soils are present in the distal portions of each pond.

Coarse tailings were placed at several locations around the site, although the largest deposit lies in a stockpile located immediately south of the proposed Lower Reservoir. The total volume of coarse tailings in this stockpile is estimated to be about 50 million cubic yards. The majority of the coarse tailings were classified as clean gravels or sandy gravels containing significant percentages of cobbles and boulders and few fines.

The chemical composition of these materials will be fully investigated during Phase 1 Pre-design investigations. Those studies are described in Section 12.1 of this document.

Upper Reservoir

The Upper Reservoir will occupy the former Central Pit of the Kaiser Mine. The reservoir is elongated generally east-west, with a maximum dimension of about 5,300 feet. North-south dimensions vary between 1,500 and 2,000 feet near the maximum planned reservoir surface (El. 2485). The existing low point in the Upper Reservoir is located in the eastern half of the pit and extends down to El. 2230. Due to topographic conditions, there will be two dams required to create the upper reservoir. The current concept is to construct these dams using roller-compacted concrete (RCC) with aggregate materials being derived from the abundant coarse mine tailings at the site or from other on-site aggregate sources with suitable characteristics for RCC.

Available geologic mapping shows the north side of the pit to be underlain by granitic rock units, while the central and southern portions of the pit are underlain by metasedimentary units and iron ore. Areas of the proposed Upper Reservoir are also covered with coarse tailings. Two borings completed in the bottom of the Upper Reservoir site (MW-10 and CH-10) provide insights on the hydrogeologic character of the rock materials. Rock core was obtained from boring CH-10. The boring was drilled to a total depth of 1,389 feet. Water was first observed at a depth of 1,309 feet. Rock lithology in the upper 350 feet of the boring was found to be moderately fractured, interbedded igneous and metasedimentary rock. Monitoring well MW-10, a 13.5-inch diameter borehole, was drilled to a total depth of 1,480 feet below ground surface. Water was first encountered at a depth of 506 feet; however, the static water level subsequently dropped and later stabilized at a depth of 1,040 feet. Borehole locations and logs are provided in the Appendix of this report.

Lower Reservoir

The Lower Reservoir will be located in the former East Pit of the Kaiser Mine. No dams are required to provide the needed storage at the Lower Reservoir. The pit has a maximum dimension of about 5,400 feet in an east-west direction, and a maximum dimension of about 2,000 feet in a north-south direction when measured at the normal maximum reservoir water surface at El. 1092. The pit narrows to the west to a minimum width of about 300 feet. The pit includes two low points or bowls, one in the east, and one in the western half of the pit. These low points are separated by a bedrock saddle, which is mantled with tailings deposits on the west side. The low point within the east bowl is at El. 776, while the lowest point within the west bowl is at El. 715. The intervening saddle is at about El. 880.

The proposed Lower Reservoir can be divided into two zones on the basis of geology. The eastern one-quarter of the site is excavated in Quaternary alluvial sediments, including fan deposits and debris flow deposits. In the eastern wall of the pit, a vertical section of about 300 feet of alluvial deposits is exposed. The western three-quarters of the site are underlain by granitic rocks and undifferentiated metasedimentary rocks and rocks of the upper quartzite unit. The granitic rocks are located along the northern face of the pit, while the metasedimentary rocks are found along the south pit face and the lower portions of the north face. Quartzite is located in the central portion of the pit and underlies the unconsolidated deposits.

A total of eight borings were used to characterize the geology in the area that would be occupied by the Lower Reservoir and surrounding areas; these include: MW-13, CH-5A, P-1, MW-1, MW-2, P-11, P-12, and C-10. Borings MW-13, CH-5A were completed along the western and northwestern corner of the Lower Reservoir site. These two borings show slightly fractured, interbedded igneous and metasedimentary rock extending to depths below El. 500. The static water level was subsequently measured in boring MW-13 at about 285 feet below the ground surface. The boring for P-1 is located on the bedrock saddle which divides the East Pit into two sections. This boring was drilled to a depth of 270 feet, and also shows interbedded igneous and metasedimentary rock for the entire depth. A static water level was subsequently measured at 177 feet below the ground surface in P-1.

Boreholes MW-1, MW-2, P-11, P-12, and C-10 were located east of the pit, and were projected onto the geologic section prepared for our analysis. The logs of these boreholes were reviewed to estimate the extent of alluvial deposits found on the eastern edge of the site. Generally, the alluvial deposits form a laterally extensive alluvial fan that extends and thickens to the east into the Chuckwalla Valley. These five borings encountered predominately fine to coarse sand, with gravel and cobbles in several locations. The borings also indicate a relatively thin, predominately clay layer interbedded within the primarily sandy alluvial deposits. The clay layer ranges in elevations from about 600 to 900 feet, and is generally about 100 to 300 feet thick. The groundwater in the bedrock and alluvium generally drops from west to east and from north to south. The groundwater was estimated to be approximately 240 feet below the ground surface at the point where boring P-12 is projected onto the geologic section. Borehole locations and logs are provided in the Appendix.

Seepage Analyses

The expected quantity of seepage through the Upper and Lower Reservoirs was evaluated by performing seepage analyses. The seepage analyses were performed using the two-dimensional, finite element program GeoStudio 2007, specifically the SEEP/W module.

The majority of the seepage from the proposed reservoirs is anticipated to travel from west to east towards the Chuckwalla Valley, similar to the existing ground water conditions at the site. Based on these ground water levels and the geologic conditions, the hydraulic gradient produced by the proposed reservoirs will be greater in the west-east direction than the hydraulic gradient in the north-south direction; therefore, all seepage flow rates and annual seepage volumes were estimated using west-east profiles. However, there is potential for seepage from the proposed reservoirs to travel from north to south. For this reason, north-south seepage profiles were also developed for both reservoirs only for estimating the ground water levels at specific down-gradient facilities of concern. We performed the analyses for the reservoirs using cross sections prepared for the locations shown in plan view on Figure 1. The representative cross sections used for the Upper Reservoir and Lower Reservoir seepage analyses are shown on Figures 2 through 5.

Hydraulic Conductivity

The estimates of hydraulic conductivity for the various geologic materials present at the site were developed based on the available results of field permeability tests, laboratory permeability tests, correlations with published values based on material descriptions and gradations, and empirical correlations between grain size and permeability. The hydraulic conductivity values used in the seepage analyses are presented in Table 1.

Table 1. Summary of Material Hydraulic Conductivities

Material	Hydraulic Conductivity (centimeters/sec)	Hydraulic Conductivity (feet/sec)	Conductivity Ratio
Rock – Upper Reservoir (moderately fractured)	1.00E-04	3.28E-06	1.00
Rock – Lower Reservoir (slightly fractured)	1.00E-05	3.28E-07	1.00
Sand	5.00E-03	1.64E-04	0.25
Clay (sandy)	1.00E-05	3.28E-07	1.00
Liner - (fine tailings)	2.16E-06	7.09E-08	1.00

The value for hydraulic conductivity of the rock in the Lower Reservoir was based on packer pressure testing conducted in 5 boreholes (borings 2, 3, 5A, 11 and 12). None of these boreholes were located within the Lower Reservoir, but are considered to be representative of the rock unit surrounding and within the reservoir. The calculated hydraulic conductivities ranged from 1×10^{-6} cm/s (centimeters/second) to 1×10^{-4} cm/s, with a geometric mean of 1×10^{-5} cm/s. The geometric mean was selected to represent the rock at the Lower Reservoir. Based on boreholes CH-10 (located in Upper Reservoir) and CH-5A (located on rim of Lower Reservoir), the rock at higher elevations is considered to be more fractured, which typically increases the hydraulic conductivity. Because the rock at the Upper Reservoir is considered to be more fractured than the rock in the Lower Reservoir, the hydraulic conductivity was increased by an order of magnitude to account for increased fracturing.

The alluvial deposits will have the highest conductivity and are represented by the sand category in Table 1. The hydraulic conductivity used for the sand category was based on the average of 17 empirical correlations between grain size and permeability. The range of hydraulic conductivities for the sand category was between 1×10^{-2} cm/s to 1×10^{-5} cm/sec, with an average of 5.0×10^{-3} cm/s.

The hydraulic conductivity used for the clay layer was based on an average of two laboratory permeability tests, which gave a value of 1.0×10^{-5} cm/s. Estimates of hydraulic conductivities for the fine tailings liner were based on an average of field and laboratory permeability tests. The results of field permeability tests on the fine tailings ranged from 9.2×10^{-9} to 4.3×10^{-7} cm/s; laboratory permeability test yielded results between 5.8×10^{-9} to 8.2×10^{-6} cm/s. The average hydraulic conductivity from these field and laboratory tests was 2.16×10^{-6} cm/s. This averaged hydraulic conductivity value was adjusted proportionally to evaluate varying thicknesses of the liner. Calculations for the hydraulic conductivity used for the various materials are presented in the Appendix.

West-East Profile Analysis Results

Seepage flow rates and gradients were estimated for both the Upper and Lower Reservoirs of the Eagle Mountain Pumped Storage Project at both the minimum and maximum water surface elevations. Seepage flow rates were also estimated using liner thicknesses of 3, 5, and 8 feet for both reservoirs, at minimum and maximum water storage elevations. The seepage blankets would only be placed on the reservoir floors and on zones of the reservoir basin slopes where ground slopes are flat enough to support stable fill placement under rapid draw-down reservoir conditions. For the initial analyses, only seepage blankets were considered. Other treatment measures to reduce reservoir seepage are described later in this memorandum.

The seepage flow rates were determined based on a unit width of the geologic section. To estimate the total seepage rate for the entire reservoir, the unit width seepage rate was multiplied by the average top width for that water surface elevation. The minimum and maximum average top widths for the two reservoirs are shown in Table 2.

Table 2. Reservoir Water Surface Elevation Average Top Widths

Reservoir	Minimum Water Surface Elevation Average Top Width (feet)	Maximum Water Surface Elevation Average Top Width (feet)	Average Top Width Used for Average Annual Seepage Calculations (feet)
Central Pit Upper Reservoir	595	1485	1040
East Pit Lower Reservoir	680	1100	890

The estimated unit width seepage quantities and average annual seepage volumes for the Upper Reservoir are presented in Table 3. Seepage quantities and volumes for the Upper Reservoir with various liner options are also shown in Table 3. The resultant groundwater levels from seepage of the Upper Reservoir at maximum water surface elevation are shown on Figure 6.

Table 3. Upper Reservoir Seepage Analysis Results – Seepage Blanket Only

	Parameter	Max.	Min.	Average
NO LINER	Unit Width Seepage Rate (cfs)	0.00195	0.00124	0.00160
	Annual Seepage (ac-ft/yr)	2097	535	1202

3' THICK LINER	Unit Width Seepage Rate (cfs)	0.00178	0.00106	0.00142
	Annual Seepage (ac-ft/yr)	1913	456	1068
5' THICK LINER	Unit Width Seepage Rate (cfs)	0.00174	0.00091	0.00133
	Annual Seepage (ac-ft/yr)	1874	394	1000
8' THICK LINER	Unit Width Seepage Rate (cfs)	0.00170	0.00070	0.00120
	Annual Seepage (ac-ft/yr)	1823	303	903

cfs – cubic feet per second ac-ft/yr – acre-feet per year
 Max. – Maximum Min. – Minimum

The estimated unit width seepage quantities and average annual seepage volumes for the Lower Reservoir are presented in Table 4. Seepage quantities and volumes for the Lower Reservoir with various liner options are also shown in Table 4. The resultant groundwater levels from seepage of the Lower Reservoir at maximum water surface elevation are shown on Figure 7. The remaining computer outputs of the analyses are included in the Appendix.

Table 4. Lower Reservoir Seepage Analysis Results – Seepage Blanket Only

	Parameter	Max.	Min.	Average
NO LINER	Unit Width Seepage Rate (cfs)	0.00356	0.00181	0.00269
	Annual Seepage (ac-ft/yr)	2836	891	1731
3' THICK LINER	Unit Width Seepage Rate (cfs)	0.00348	0.00177	0.00262
	Annual Seepage (ac-ft/yr)	2768	871	1690
5' THICK LINER	Unit Width Seepage Rate (cfs)	0.00347	0.00175	0.00261
	Annual Seepage (ac-ft/yr)	2765	863	1683
8' THICK LINER	Unit Width Seepage Rate (cfs)	0.00347	0.00175	0.00261
	Annual Seepage (ac-ft/yr)	2764	860	1681

cfs – cubic feet per second ac-ft/yr – acre-feet per year
 Max. – Maximum Min. – Minimum

Based on the seepage analyses of the Eagle Mountain Pumped Storage Project and assuming no reservoir seepage treatments, the estimated annual average seepage volume from the Upper Reservoir is approximately 1,200 acre-feet, and the estimated annual average seepage volume from the Lower Reservoir is approximately 1,700 acre-feet. The estimated annual seepage volume for the Lower Reservoir is about 500 acre-feet more than the Upper Reservoir because the eastern wall of the Lower Reservoir primarily consists of alluvial sediments and debris flow deposits, which have significantly higher hydraulic conductivities.

Based on the seepage analysis, the fine tailings blanket liner options for the Upper Reservoir reduce the average annual seepage volume. The estimated reduction in average annual seepage volume for the Upper Reservoir ranged from about 11 to 25 percent, depending on the liner thickness. The maximum reduction for the Upper Reservoir was approximately 300 acre-feet annually, with an eight-foot thick liner in place.

The fine tailings blanket liner in the Lower Reservoir was estimated to be relatively ineffective. This is because the upper half of the walls in the pit, which consist of the alluvium deposit, are

too steep to support the fine tailings liner. And, since the majority of seepage from the Lower Reservoir will be through this alluvium deposit, the analyses indicated little change due to the various liner options. The estimated reduction in average annual seepage volume for the Lower Reservoir was about 2.5 percent, regardless of the liner thickness. The maximum reduction for the Lower Reservoir was approximately 50 acre-feet annually, with an eight-foot thick liner constructed where possible. Based on this analysis, additional seepage reduction measures beyond a fine tailings blanket liner will be required for the Lower Reservoir.

North-South Profile Analysis Results

Seepage and ground water elevations along a north-south profile toward the CRA were estimated for both the Upper and Lower Reservoirs of the Eagle Mountain Pumped Storage Project at both the minimum and maximum water surface elevations. The seepage analysis from the proposed Upper Reservoir at maximum water surface elevation is shown on Figure 8. Generally, the maximum water surface elevation in the Upper Reservoir is projected to cause the ground water levels near the location of the CRA to rise approximately 45 feet above the estimated existing ground water levels. Results of the seepage analysis from the proposed Lower Reservoir at maximum water surface elevation are shown on Figure 9. Generally, the maximum water surface elevation in the Lower Reservoir is projected to cause the ground water levels near the location of the CRA to rise approximately 150 feet above the estimated existing ground water levels. The remaining computer outputs of the analyses are included in the Appendix.

Potential Impacts from Reservoir Seepage

Concerns have been raised about the potential impacts of seepage from the reservoirs on the concrete lining of the Colorado River Aqueduct (CRA), which is owned and operated by MWD. The potential impacts to the CRA from reservoir seepage were analyzed using both west-east and north-south profiles for each of the project reservoirs. The impacts of seepage were expected to be the most noticeable in the west-east profiles due to the close proximity of the Lower Reservoir to the CRA; however, the impacts along the north-south profiles were also investigated to fully assess the seepage concerns.

Based on the west-east seepage analysis for the Lower Reservoir, assuming no seepage treatments and continuous seepage at the maximum reservoir water surface elevation, the estimated groundwater elevation near the location of the CRA is estimated to stabilize at approximately El. 915, as shown on Figure 7. The current static groundwater elevation at this location is about at El. 675, which is about 240 feet lower than the modeled ground water surface elevation with fully-developed reservoir seepage. The ground surface elevation near the CRA is approximately El. 1000, which is about 85 feet higher than the groundwater elevation predicted under worse-case conditions for seepage from the Lower Reservoir. Because the estimated ground water elevation is predicted to be well below the ground surface, no uplift forces are predicted on the concrete lining of the CRA.

Based on the north-south seepage analysis of seepage from the Upper and Lower Reservoirs, the Lower Reservoir produced the greatest increases from the estimated ground water elevations; therefore, the Lower Reservoir seepage results were used to analyze the impacts to the CRA facilities. The CRA facilities that could potentially be impacted by reservoir seepage along the north-south profiles include the CRA Pump Station and CRA channel near the pump station, as shown on Figure 1. Based on the north-south seepage analysis from the Lower Reservoir, and assuming no seepage treatments and continuous seepage at the maximum reservoir water surface elevation, the estimated ground water elevation near the location of the CRA is estimated to reach approximately El. 745 feet, as

shown on Figure 9. The current static ground water elevation at this location is assumed to be about at El. 580 feet. However, this elevation may be conservatively high, because ground water wells and elevation data are not available at this location, but data was extrapolated to develop a conservative estimate. Therefore, the existing ground water elevation is estimated to be about 165 feet lower than the modeled ground water surface elevation with fully developed reservoir seepage. The ground surface elevation near the CRA is approximately El. 985 feet, which is estimated to be about 240 feet higher than the ground water elevation predicted under worse-case conditions for seepage from the Lower Reservoir. Because the estimated ground water elevation is predicted to be well below the ground surface, no uplift forces are predicted on the concrete lining of the CRA or at the pump station.

In addition, we estimate that the steady-state groundwater profile for the Lower Reservoir shown on Figure 7 will take at least 15 years to fully develop from the estimated seepage volume, assuming a two year filling period and the reservoir remains at the maximum water surface elevation after filling. We also estimate that the steady-state groundwater profiles for the Upper Reservoir shown on Figures 6 and 8 will take at least 50 years to fully develop, assuming a two year filling period and the reservoir remains at the maximum water surface elevation after filling. Furthermore, it is estimated to take at least 30 years for groundwater levels near the Upper Reservoir to reach and daylight at the nearest surface drainage channel. If the groundwater levels do daylight in the adjacent surface drainage channels, any seepage will be collected and conveyed to the Lower Reservoir. However, the reservoirs can never be completely full at the same time, and reservoir levels will cycle up and down in response to energy demands and hydroelectric operations. Realistically, we expect that the estimated steady-state groundwater levels from seepage from the Eagle Mountain Project may not fully develop during the estimated project service life of 50 years.

Hydrocompaction has also been identified as a potential impact that could be associated with seepage from reservoirs of the Eagle Mountain Project. The potential for hydrocompaction in soils is related to the grain size of the sediments and how they were deposited. Fan deposits, such as those present near the project site, when deposited by flash-flood type of events, are highly susceptible to compaction when wetted either from above or below. Under worse-case conditions, our analyses indicate that groundwater levels will be about 80 feet below ground surface and will not reach the near-surface zones where hydrocompaction would be the most problematic.

Studies conducted for MWD in the Chuckwalla Aquifer (Upper Chuckwalla Groundwater Basin Storage GeoPentech 2003) addressed hydrocompaction. The studies suggested that to depths of 100 feet, hydrocompaction could range from 0.56 to 1.8 percent, depending on soil composition. As such, surface subsidence may total from 0.5 to 1.8 feet. Therefore, additional reduction of seepage is needed and seepage recovery wells are needed to reduce hydrocompaction to negligible levels.

Other Seepage Treatment and Monitoring Measures

The Project plans to limit seepage from the project reservoirs to the maximum extent possible. This includes the Upper Reservoir, Lower Reservoir, and the brine disposal ponds¹ that will be part of the water quality management system for the project, which is described in the draft License Application. A more-detailed hydrogeologic analysis will be prepared during final design of the project. We will also undertake detailed geologic mapping of the reservoirs during project design. Upon completion of the hydrogeologic analysis and detailed geologic

¹ The brine ponds will be lined with clay or geomembrane materials, and to the extent that can be realistically achieved, they will be "zero seepage" facilities.

mapping, engineering design solutions will be provided to reduce seepage from the project reservoirs in order to reduce the potential for hydrocompaction and impacts to groundwater levels and water quality.

Seepage control from the project reservoirs will be accomplished using systematic procedures and steps that have been applied successfully at similar projects. These procedures will include the following:

- After access to the site is obtained, a team of geologists and geotechnical engineers will conduct a detailed reconnaissance of the reservoir basins and pond areas to identify zones where leakage and seepage would be expected to occur. These areas will include faults, fissures and cracks in the bedrock, and zones that have direct connection to the alluvial deposits of the Chuckwalla Valley. During the reconnaissance, the team will evaluate the effectiveness of various methods for seepage and leakage control to mitigate the effects of these particular features.
- Seepage and leakage control methods will be further investigated utilizing data from the geologic reconnaissance and hydrogeologic modeling studies. Potential methods for seepage and leakage control will include curtain grouting of the foundation beneath the dam footprint and around the reservoir rim, as needed; backfill concrete placement and/or slush grouting of the faults, fissures and cracks recognized in the field reconnaissance; placement of low permeability materials, as technically feasible, over zones too large to be grouted and over areas of alluvium within the Lower Reservoir; seepage and leakage collection systems positioned based on the results of the hydrogeologic analyses; and clay or membrane lining of the brine ponds associated with the project's water quality management system. The collection systems would recycle water into the project reservoirs or the RO (reverse osmosis) system.
- Design and construction of the seepage and leakage control measures, which will be aided by the results of the groundwater modeling.
- Design and construction of a comprehensive monitoring program, consisting of observation wells and piezometers that will be used to assess the effectiveness of the seepage and leakage control measures.
- Based on monitoring results, additional actions may be taken to further control leakage and seepage from the reservoirs and ponds. Such measures may include curtain grouting and the expansion of seepage and leakage collection systems.

We modified the seepage model described above to reflect implementation of the above noted measures, in addition to the use of seepage blankets on the bottom and flatter-sloped areas of the two reservoirs. We assumed that the following measures would provide the indicated levels of seepage reduction:

- Grouting measures in fractured bedrock zones are expected to reduce the effective seepage area by 30% in the Upper Reservoir and 20 % in the Lower Reservoir. Grouting in the Lower Reservoir was not assumed to be possible or effective in the exposed alluvium on the eastern end of the reservoir. The

percentage reduction due to grouting of fractured bedrock zones was estimated based on rock quality index (RQI) test results from the earlier subsurface exploration programs. The RQI for the top 100 feet of the boreholes was averaged for each reservoir. The percentage reduction was estimated assuming $100 - RQI_{avg}$ divided by two.

- The exposed alluvium in the eastern portion of the Lower Reservoir extends over a total perimeter distance of approximately 5,000 feet with the maximum depth of approximately 315 feet below the normal water surface elevation. The average slope of the pit walls in this zone is about 3 to 1 (horizontal: vertical), although the upper half of the pit has steep slopes near 1.5 to 1 in inclination. A possible treatment option, which will be investigated during final design for feasibility and effectiveness, would be to blanket the entire zone with a stepped RCC or soil cement overlay. This would reduce the effective seepage area by at least 80%. However, this approach could be very expensive. Therefore, other treatment options will be explored during final design.

Results of these analyses are presented below:

Table 5. Upper Reservoir Seepage Analysis Results – Grouting and Seepage Blanket

	Parameter	Max.	Min.	Average
3' THICK LINER	Unit Width Seepage Rate (cfs)	0.00126	0.00078	0.00102
	Annual Seepage (ac-ft/yr)	1351	338	768
5' THICK LINER	Unit Width Seepage Rate (cfs)	0.00124	0.00072	0.00098
	Annual Seepage (ac-ft/yr)	1332	310	738
8' THICK LINER	Unit Width Seepage Rate (cfs)	0.00122	0.00061	0.00092
	Annual Seepage (ac-ft/yr)	1308	265	689

cfs – cubic feet per second ac-ft/yr – acre-feet per year
Max. – Maximum Min. – Minimum

Table 6. Lower Reservoir Seepage Analysis Results – Grouting, Seepage Blanket and RCC or Soil Cement Treatment over the Alluvium

	Parameter	Max.	Min.	Average
3' THICK LINER	Unit Width Seepage Rate (cfs)	0.00206	0.00135	0.00171
	Annual Seepage (ac-ft/yr)	1641	665	1099
5' THICK LINER	Unit Width Seepage Rate (cfs)	0.00170	0.00106	0.00138
	Annual Seepage (ac-ft/yr)	1358	521	890
8' THICK LINER	Unit Width Seepage Rate (cfs)	0.00131	0.00090	0.00111
	Annual Seepage (ac-ft/yr)	1045	443	713

cfs – cubic feet per second ac-ft/yr – acre-feet per year
Max. – Maximum Min. – Minimum

Based on the seepage analysis of the Upper Reservoir, the grouting of rock fractures could potentially reduce seepage from the reservoir an additional 200 to 300 acre-feet depending on the fine tailings blanket liner thickness. The estimated total reduction in average annual seepage volume from the Upper Reservoir, using both grouting and blanket liner, ranged from about 36 to 41 percent, depending on the liner thickness. The maximum reduction for the Upper Reservoir was approximately 500 acre-feet annually, with an eight-foot thick liner plus grouting in place. The estimated groundwater levels resulting from seepage from the Upper Reservoir utilizing the additional seepage control measures are a minimum of approximately 125 feet lower than the estimated ground surface and are shown on Figure 10 at the average reservoir water surface elevation.

Based on the seepage analysis of the Lower Reservoir, the grouting of rock fractures and RCC or soil cement treatment on the alluvium could potentially reduce seepage from the reservoir an additional 600 to 1,000 acre-feet depending on the fine tailings blanket liner thickness. The estimated total reduction in average annual seepage volume from the Lower Reservoir using a blanket liner, grouting rock fractures and treatment of alluvium, ranged from about 37 to 59 percent, depending on the liner thickness. The maximum reduction for the Lower Reservoir was approximately 1,000 acre-feet annually. The estimated groundwater levels resulting from seepage from the Lower Reservoir utilizing the additional seepage control measures are a minimum of approximately 265 feet lower than the estimated ground surface and are shown on Figure 11 at the average reservoir water surface elevation.


We anticipate that any water that may escape the engineered seepage and leakage solutions will be captured by groundwater wells that will be operated to mitigate above-normal hydrostatic pressures on the CRA. The groundwater level control wells will be operated to maintain the groundwater levels within ± 5 feet of the historic levels in areas where hydrocompaction could potentially occur and adversely impact the CRA or other infrastructure. The combined pumping from the wells will be about 100 gpm from each of the proposed extraction wells for a total of 900 gpm. These wells will return the intercepted water to the Lower Reservoir. The wells, if found to be needed, will be located based on the results of detailed hydrogeologic modeling studies. Groundwater level and quality monitoring will be performed at monitoring wells and the project's extraction and water supply wells. Groundwater level and water quality sampling will be performed at:

- One up-gradient and 3 to 5 down-gradient wells around each reservoir and the brine disposal pond to detect seepage.
- Nine monitoring wells in the valley sediments to assess changes related to seepage or from project pumping.
- Two residential/municipal wells nearest the project to ensure safe drinking water.
- Extraction wells
- Groundwater levels will initially be monitored on a monthly basis, which may later be extended to quarterly or annual monitoring. Water quality sampling and testing will be performed initially on a quarterly basis.

Based on implementation of the above-noted measures, we believe that our engineering design would mitigate any potential impacts to the CRA. The proposed measures to minimize and collect seepage will help insure that seepage emanating from the reservoirs is returned to the reservoirs prior to reaching the CRA.

Source: GeoPentech, 2003. Upper Chuckwalla Groundwater Basin Storage, Draft Report. Produced for Metropolitan Water District.

P:\Land Projects\072610 EAGLE MOUNTAIN\dwg\Seepage Profile.dwg Jan 2009



Eagle Mountain Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy




Project 080472


PLAN VIEW OF
RESERVOIR GEOLOGIC
CROSS SECTIONS


December 2008

Figure 1




HYDRAULIC CONDUCTIVITIES:
 ROCK = 1.0e-04 cm/s
 LINER = 2.2e-06 cm/s


Eagle Mountain Pumped Storage Project Eagle Mountain, California	 GEI Consultants	UPPER RESERVOIR WEST-EAST GEOLOGIC CROSS SECTION
Eagle Crest Energy	Project 080472	December 2008 Figure 2



HYDRAULIC CONDUCTIVITIES:


ROCK = 1.0e-05 cm/s
 SAND = 5.0e-03 cm/s
 CLAY = 1.0e-05 cm/s
 LINER = 2.2e-06 cm/s

<p>Eagle Mountain Pumped Storage Project Eagle Mountain, California</p>		<p>LOWER RESERVOIR WEST-EAST GEOLOGIC CROSS SECTION</p>
<p>Eagle Crest Energy</p>	<p>Project 080472</p>	<p>December 2008 Figure 3</p>





HYDRAULIC CONDUCTIVITIES:
 ROCK = 1.0e-05 cm/s
 SAND = 5.0e-03 cm/s

Eagle Mountain Pumped Storage Project Eagle Mountain, California	 GEI Consultants	UPPER RESERVOIR NORTH-SOUTH GEOLOGIC CROSS SECTION	
Eagle Crest Energy			Project 080472



HYDRAULIC CONDUCTIVITIES:
 SAND = 5.0e-03 cm/s

Eagle Mountain Pumped Storage Project Eagle Mountain, California	 Project 080472	LOWER RESERVOIR NORTH-SOUTH GEOLOGIC CROSS SECTION
Eagle Crest Energy		December 2008 Figure 5



Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.

Eagle Mountain Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy




Project 080472

UPPER RESERVOIR
MAXIMUM WATER SURFACE
WEST-EAST
SEEPAGE RESULTS

December 2008

Figure 6



Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.

Eagle Mountain Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy




Project 080472

LOWER RESERVOIR
MAXIMUM WATER SURFACE
WEST-EAST
SEEPAGE RESULTS

December 2008

Figure 7



Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.

Eagle Mountain Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy




Project 080472


UPPER RESERVOIR
MAXIMUM WATER SURFACE
NORTH-SOUTH
SEEPAGE RESULTS


December 2008

Figure 8



Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.

<p>Eagle Mountain Pumped Storage Project Eagle Mountain, California</p>	 <p>Project 080472</p>	<p>LOWER RESERVOIR MAXIMUM WATER SURFACE NORTH-SOUTH SEEPAGE RESULTS</p> <p>August 2008 Figure 9</p>
<p>Eagle Crest Energy</p>		



Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.

Eagle Mountain Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy




Project 080472

UPPER RESERVOIR
MAXIMUM SEEPAGE
TREATMENT RESULTS
(AVG. WATER LEVEL)

December 2008

Figure 10



Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.

Eagle Mountain Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy



Project 080472

LOWER RESERVOIR
MAXIMUM SEEPAGE
TREATMENT RESULTS
(AVG. WATER LEVEL)

December 2008

Figure 11

APPENDIX

GEI Consultants, Inc.
 080470 Eagle Mountain Pumped Storage Project
 Reservoir Seepage Analysis (SEEP/W)
 9/4/2008
 NDM

EAGLE MOUNTAIN - CENTRAL PIT SEEPAGE RESULTS
SEEPAGE BLANKET ONLY

Reservoir Paramters

Max WSE	2485 ft
Min WSE	2343 ft
Max Reservoir WSE Area	48 acres
Min Reservoir WSE Area	191 acres
Max WSE Average Top Width	1485 ft
Min WSE Average Top Width	595 ft
Average Top Width	1040 ft

	Parameter	Max	Min	Average
NO LINER	Unit Width Seepage Rate (cfs)	0.00195	0.00124	0.00160
	Annual Seepage (ac-ft/yr)	2097	535	1202
3' THICK LINER	Unit Width Seepage Rate (cfs)	0.00178	0.00106	0.00142
	Annual Seepage (ac-ft/yr)	1913	456	1068
5' THICK LINER	Unit Width Seepage Rate (cfs)	0.00174	0.00091	0.00133
	Annual Seepage (ac-ft/yr)	1874	394	1000
8' THICK LINER	Unit Width Seepage Rate (cfs)	0.00170	0.00070	0.00120
	Annual Seepage (ac-ft/yr)	1823	303	903

GEI Consultants, Inc.
 080470 Eagle Mountain Pumped Storage Project
 Reservoir Seepage Analysis (SEEP/W)
 9/4/2008
 NDM

EAGLE MOUNTAIN - CENTRAL PIT SEEPAGE RESULTS
GROUTING AND SEEPAGE BLANKET

Reservoir Paramters

Max WSE	2485 ft
Min WSE	2343 ft
Max Reservoir WSE Area	48 acres
Min Reservoir WSE Area	191 acres
Max WSE Average Top Width	1485 ft
Min WSE Average Top Width	595 ft
Average Top Width	1040 ft

	Parameter	Max	Min	Average
NO LINER	Unit Width Seepage Rate (cfs)	0.00195	0.00124	0.00160
	Annual Seepage (ac-ft/yr)	2097	535	1202
3' THICK LINER	Unit Width Seepage Rate (cfs)	0.00126	0.00078	0.00102
	Annual Seepage (ac-ft/yr)	1351	338	768
5' THICK LINER	Unit Width Seepage Rate (cfs)	0.00124	0.00072	0.00098
	Annual Seepage (ac-ft/yr)	1332	310	738
8' THICK LINER	Unit Width Seepage Rate (cfs)	0.00122	0.00061	0.00092
	Annual Seepage (ac-ft/yr)	1308	265	689

GEI Consultants, Inc.
 080470 Eagle Mountain Pumped Storage Project
 Reservoir Seepage Analysis (SEEP/W)
 9/4/2008
 NDM

EAGLE MOUNTAIN - EAST PIT SEEPAGE RESULTS

SEEPAGE BLANKET ONLY

Reservoir Paramters

Max WSE	1095 ft
Min WSE	925 ft
Max Reservoir WSE Area	163 acres
Min Reservoir WSE Area	63 acres
Max WSE Average Top Width	1100 ft
Min WSE Average Top Width	680 ft
Average Top Width	890 ft

	Parameter	Max	Min	Average
NO LINER	Unit Width Seepage Rate (cfs)	0.00356	0.00181	0.00269
	Annual Seepage (ac-ft/yr)	2836	891	1731
3' THICK LINER	Unit Width Seepage Rate (cfs)	0.00348	0.00177	0.00262
	Annual Seepage (ac-ft/yr)	2768	871	1690
5' THICK LINER	Unit Width Seepage Rate (cfs)	0.00347	0.00175	0.00261
	Annual Seepage (ac-ft/yr)	2765	863	1683
8' THICK LINER	Unit Width Seepage Rate (cfs)	0.00347	0.00175	0.00261
	Annual Seepage (ac-ft/yr)	2764	860	1681

GEI Consultants, Inc.
 080470 Eagle Mountain Pumped Storage Project
 Reservoir Seepage Analysis (SEEP/W)
 9/4/2008
 NDM

EAGLE MOUNTAIN - EAST PIT SEEPAGE RESULTS
GROUTING, SEEPAGE BLANKET, AND RCC TREATMENT

Reservoir Paramters

Max WSE	1095 ft
Min WSE	925 ft
Max Reservoir WSE Area	163 acres
Min Reservoir WSE Area	63 acres
Max WSE Average Top Width	1100 ft
Min WSE Average Top Width	680 ft
Average Top Width	890 ft

	Parameter	Max	Min	Average
NO LINER	Unit Width Seepage Rate (cfs)	0.00356	0.00181	0.00269
	Annual Seepage (ac-ft/yr)	2836	891	1731
3' THICK LINER	Unit Width Seepage Rate (cfs)	0.00206	0.00135	0.00171
	Annual Seepage (ac-ft/yr)	1641	665	1099
5' THICK LINER	Unit Width Seepage Rate (cfs)	0.00170	0.00106	0.00138
	Annual Seepage (ac-ft/yr)	1358	521	890
8' THICK LINER	Unit Width Seepage Rate (cfs)	0.00131	0.00090	0.00111
	Annual Seepage (ac-ft/yr)	1045	443	713

**Eagle Mountain Pumped Storage Project
Upper Reservoir - SEEP/W Output**

GEI Consultants, Inc.
080470 Eagle Mountain Pumped Storage Project
Reservoir Seepage Analysis (SEEP/W)
1/4/2011
NDM


Model Mesh Properties - Upper Reservoir (East-West)


Draw Mesh Properties [?] [X]

Approx. Global Element Size:


Mesh: 10740 Nodes, 10453 Elements

Enter a new Global Element Size to adjust the entire mesh size.
Otherwise, select regions, lines, points, or layers and adjust the
appropriate mesh properties.






EXISTING CONDITIONS




NO LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




NO LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




3' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




5' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




8' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




3' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




5' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




8' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




3' LINER W/ GROUTING

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




5' LINER W/ GROUTING

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




8' LINER W/ GROUTING

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




3' LINER W/ GROUTING

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.



5' LINER W/ GROUTING


Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.





8' LINER W/ GROUTING

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.


Model Mesh Properties - Upper Reservoir (North-South)









Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.




Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 200 feet of head.


**Eagle Mountain Pumped Storage Project
Lower Reservoir - SEEP/W Output**

Model Mesh Properties - Lower Reservoir (East-West)






EXISTING CONDITIONS




NO LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.




NO LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.




3' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.




5' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.




8' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.




3' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 20 feet of head.




5' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 20 feet of head.




8' LINER

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 20 feet of head.




3' LINER W/ GROUTING AND RCC TREATMENT

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.




5' LINER W/ GROUTING AND RCC TREATMENT

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.




8' LINER W/ GROUTING AND RCC TREATMENT

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.




3' LINER W/ GROUTING AND RCC TREATMENT

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 20 feet of head.



5' LINER W/ GROUTING AND RCC TREATMENT

Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 20 feet of head.






8' LINER W/ GROUTING AND RCC TREATMENT


Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 20 feet of head.

GEI Consultants, Inc.
080470 Eagle Mountain Pumped Storage Project
Reservoir Seepage Analysis (SEEP/W)
1/4/2011
NDM


Model Mesh Properties - Lower Reservoir (North-South)







Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.



Note: The color contouring displayed on the figure illustrates the total head across the cross section. The contour intervals shown are equal to 50 feet of head.

**SEEP/W Input
Materials Properties Data**


GEI Consultants, Inc.
080470 Eagle Mountain Pumped Storage Project
Reservoir Seepage Analysis (SEEP/W)
7/24/2008
NDM

Summary of SEEP/W Material Properties


Material	Hydraulic Conductivity (cm/sec)	Hydraulic Conductivity (ft/sec)	Conductivity Ratio
Rock – Upper Reservoir (Moderately Fractured)	1.00E-04	3.28E-06	1
Rock – Lower Reservoir (Slightly Fractured)	1.00E-05	3.28E-07	1
Sand	5.00E-03	1.64E-04	0.25
Clay (sandy)	1.00E-05	3.28E-07	1.00
Liner - (fine tailings)	2.16E-06	7.09E-08	1.00
RCC Treatment	1.00E-08	3.28E-10	1.00

Material Properties - Hydraulic Conductivity Functions


Rock - Lower Reservoir Ratio = 1.0




Rock - Upper Reservoir Ratio = 1.0




Sand Ratio = 0.25




Clay Ratio = 1.0



3' Liner Ratio = 1.0



5' Liner Ratio = 1.0




Material Properties - Hydraulic Conductivity Functions

8' Liner

Ratio = 1.0


8' Liner, Ksat = 2.6587e-08 ft/s (4)



RCC Liner

Ratio = 1.0


RCC, Ksat = 3.28e-10 ft/s (2)



Material Properties - Volumetric Water Content Functions


Rock - Lower Reservoir

Ratio = 1.0




Rock - Upper Reservoir

Ratio = 1.0




Sand

Ratio = 0.25



Clay

Ratio = 1.0



GEI Consultants, Inc.
 080470 Eagle Mountain Pumped Storage Project
 Reservoir Seepage Analysis (SEEP/W)
 7/24/2008
 NDM

Chuckwalla Report, Hydraulic Conductivities Summary

Boring	Description	USCS	Depth	Hydraulic Conductivity (cm/sec)
C-1	Sand	SP	201	1.00E-05
C-1	Clayey Sand	SC	201	2.10E-05
C-1	Silty Sand	SM	322	3.00E-06
C-5	Fat Clay	CH	142	9.20E-10
C-5	Clayey Sand	SC-SM	62	2.70E-07
C-5	Silty Sand	SM	62	3.00E-07
C-9	Silty sand	SM	145	3.50E-05
TP#2	Silty Sand	SM	14	1.20E-04
TP#3	Silty Sand	SM	5	3.90E-04

Average

SM	9.14E-05
SC	1.06E-05


GEI Consultants, Inc.
 080470 Eagle Mountain Pumped Storage Project
 Reservoir Seepage Analysis (SEEP/W)
 7/24/2008
 NDM

Emperical

Boring	Description	USCS	Depth	D5 (mm)	Hydraulic Conductivity (cm/sec)
C-1	Sand w/ Silt	SP-SM	17	0.08	7.00E-03
C-1	Sand w/ Silt	SP-SM	58	0.06	4.00E-03
C-1	Silty Sand	SM	101	0.0015	3.47E-05
C-1	Sand w/ Silt	SP-SM	110	0.0015	3.47E-05
C-1	Sand w/ Silt	SP-SM	123	0.008	1.61E-04
C-1	Sand w/ Silt	SP-SM	423	0.06	4.00E-03
C-5	Sand w/ Gravel	SW	59	0.2	3.25E-02
C-5	Gravel w/ S&S	GP-GM	81	0.05	2.50E-03
C-5	Sand w/ Silt	SP-SM	101	0.1	1.00E-02
C-5	Gravel w/ S&S	GP-GM	121	0.065	4.75E-03
C-5	Sand w/ Silt	SP-SM	280	0.006	1.22E-04
C-9	Sand w/ Silt	SW-SM	17	0.05	2.50E-03
C-10	Sand w/ Silt	SP-SM	8	0.01	2.00E-04
C-10	Sand w/ Silt	SP-SM	16	0.06	4.00E-03
C-10	Sand	SP	78	0.08	7.00E-03
C-10	Sand w/ Silt	SP	130	0.05	2.50E-03
C-1	Sand	SP	201	--	1.00E-05
Average					4.78E-03

Lookup Table

D5 (mm)	Hydraulic Conductivity (cm/sec)	Increment
0.001	2.50E-05	0.019444444
0.01	2.00E-04	0.057500000
0.05	2.50E-03	0.150000000
0.1	1.00E-02	0.225000000
0.5	1.00E-01	1.800000000
1	1.00E+00	1.000000000



GEI Consultants, Inc.
080470 Eagle Mountain Pumped Storage Project
Reservoir Seepage Analysis (SEEP/W)
7/24/2008
NDM

Liner - Fine Tailings

Hydraulic Conductivities - cm/sec

Test Type	Min	Max	Average
Field	9.20E-09	4.30E-07	2.20E-07
Lab	5.80E-09	8.20E-06	4.10E-06
Average =	7.50E-09	4.32E-06	2.16E-06 cm/sec
	2.46E-10	1.42E-07	7.09E-08 ft/sec

BOREHOLE NO.	LOCATION		GROUND ELEV. FT.	DEPTH DRILLED FT.	BOTTOM ELEV. FT.	DEPTH TO BEDROCK FT.	CASING BOTTOM DEPTH FT.	ELEV. FT.	DEPTH OF SCREENED INTERVAL		HOLE SIZE IN.	DRILLING DATES		HEIGHT OF CASING FT.	SPFH TO 1ST WATER FT.	ELEV. OF 1ST WATER FT.	5/20/92 SWL ELEV. FT.	5/26/92 SWL ELEV. FT.	6/17/92 SWL ELEV. FT.	7/1/92 SWL ELEV. FT.	7/15/92 SWL ELEV. FT.	7/29/92 SWL ELEV. FT.	8/13/92 SWL ELEV. FT.	8/26/92 SWL ELEV. FT.	BOREHOLE NO.	REMARKS				
	NORTHING STATION	EASTING OFFSET							FROM	TO		BEGN.	END																	
									10/15/92	10/15/92		10/15/92	10/15/92														10/15/92	10/15/92	10/15/92	10/15/92
MW-1	619559.37	2240186.01	1045.00	420	645.00	N/A	365	660.00	325	351	10	4/27/92	3/26/92	2.29	904.3	706.79	706.15	706.37	706.57	706.78	706.96	706.60	706.44	706.15	706.15	MW-1	MUD ROTARY			
MW-2	618081.48	2210448.20	1033.01	435	598.01	N/A	435	626.01	394	435	10	3/25/92	4/4/92	2.03	904.3	685.11	686.01	685.84	685.84	685.25	685.20	685.10	684.25	683.84	683.30	MW-2	AIR HAMMER			
MW-3	616877.30	2232528.30	1043.84	360	668.84	11	330	636.84	289	350	8	4/4/92	4/10/92	1.25	904.4	755.41	758.61	757.84	754.01	756.61	755.72	755.25	755.34	756.01	753.08	MW-3	REVERSE CIRC. HAMMER			
MW-4	616423.25	2232765.45	762.73	140	616.73	0	140	635.73	60	140	10	3/25/92	3/25/92	4.17	904.4	762.29	763.90	763.66	763.66	763.19	762.69	763.07	763.61	762.61	762.75	MW-4	REVERSE CIRC. HAMMER			
MW-5	618340.71	2235160.12	911.26	245	666.26	233	240	671.26	180	240	10	3/24/91	3/27/91	2.00	904.7	764.12	666.79	669.29	668.30	669.02	666.71	669.34	669.07	667.86	666.73	MW-5	REVERSE CIRC. HAMMER			
MW-6	616266.05	2232508.17	1347.80	640	707.80	400	640	727.80	560	640	10	3/21/91	4/9/91	2.75	904.5	761.51	772.14	772.32	772.35	771.27	768.54	769.50	768.36	771.80	769.50	MW-6	REVERSE CIRC. HAMMER			
MW-7	618416.09	2232507.48	1605.82	765	830.82	0						10/25/92	9/11/91	6/14/91	2.31	900	913.82		916.45	914.46	915.53	915.82	915.24	916.73	915.40	MW-7	AIR HAMMER			
MW-8 (OLD)	619339.88	2232018.00	1785.54	964	804.54	1	N/A	N/A	N/A	6.25	6/25/91	6/25/91	N/A	910	858.54													MW-8 (OLD)	AIR HAMMER	
MW-8 (NEW)	619339.88	2232018.00	1785.54	871	894.54	11	840	928.54	791.5	843.5	13.5	3/31/92	4/21/92	4.45	908	908.54		908.53	907.56	908.8	906.84	906.60	906.73	908.00	907.54	MW-8 (NEW)	AIR HAMMER			
MW-9	619812.02	2232026.54	2396.92	1544	252.92	1	N/A	N/A	N/A	6.5	10/25/91	10/25/91	N/A	910	908.54														MW-9	AIR HAMMER
MW-10	622820.36	2221618.45	2311.25	1213.7	1097.25	7	1170	1133.25	1069	1170	13.5	2/16/92	3/9/92	3.22	908	922.25	1444.85	1448.44	1429.06	1427.27	1415.27	1271.06	1285.23	1298.32	1292.82	MW-10	MUD ROTARY			
MW-11	617735.19	2221467.83	1783.25	1130	673.25	20	1115	669.25	627	910.71	13.5	3/16/92	3/25/92	0.32	905	858.25				1027	944.13	944.13	944.13	942.96	942.96	942.96	MW-11	MUD ROTARY AND AIR HAMMER		
MW-12	624274.96	2236034.89	1268.77	550	688.77	3	400	775.77	565	420	13.5	3/25/92	3/25/92	0.71	490	710.77	683.68	682.72	676.11	679.61	655.44	654.56	652.62	646.44	646.44	MW-12	AIR HAMMER			
MW-13	619099.2	2232353.31	1051.48	430	621.48	3	364.7	626.78	260	364.7	14.75	4/15/92	4/29/92	4.58	910.0	741.48	776.23	774.11	737.25	762.72	762.63	761.89	756.64	760.61	758.1	MW-13	AIR HAMMER			
COFH-2	621263.17	2232163.99	1769.96	1179	1169.21	19	1179	1169.06	N/A	N/A	3.8	2/21/92	5/13/92	2.32	1120	1168.21						1120.03	1119.82	1115.67	1121.44	1117.78	COFH-2	CORED		
COFH-3	619821.91	2232150.29	1758.62	661	1097.62	10	N/A	N/A	N/A	3.8	5/8/92	3/21/92	N/A	A	N/A														COFH-3	CORED
COFH-3A	619821.91	2232150.29	1758.62	904.5	854.17	10	F	900	858.57	N/A	N/A	3.0/8.1	3/21/92	4/10/92	1.03	650	898.67	976.75		902.56	907.33	906.87	907.59	912.63	906.92	906.06	COFH-3A	CORED TROOGE 0-122		
COFH-4	625160.42	2232913.48	1605.68	900	675.68	10	F	900	675.58	N/A	N/A	3.0/8.1	3/16/92	3/25/92	1.42	675	1003.58	1068.73	1051.73	1052.29	1496.05	1493.65	1491.85	1487.34	1487.91	1485.36	COFH-4	CORED		
COFH-5A	619821.91	2232150.29	1607.20	900	707.2	13	F	900	707.2	N/A	N/A	3.0/8.1	4/8/92	4/28/92	1.50	791	866.2												COFH-5A	CORED
COFH-10	622896.74	2221688.07	2307.76	1389	918.76	7	1389	918.76	N/A	N/A	3.8	2/13/92	3/5/92	0.25	1309	998.76				1290.38			1315.51					COFH-10	CORED	
COFH-11	617737.58	2221468.24	1781.59	1100	681.59	19	1100	681.59	N/A	N/A	3.8	4/14/92	4/29/92	N/A	910	871.59													COFH-11	CORED
COFH-12	624000.32	2234697.22	1207.88	545	662.88	3	525	682.88	300	525	13.5	3/17/92	5/17/92	N/A	475	742.88													COFH-12	CORED
P-1	618311.22	2236615.36	876.70	270	606.7	15	270	619.7	270	270	5.625	3/23/92	3/23/92	2.75	500	676.7	699.37	700.27	700.49	698.45	698.24	698.79	698.41	697.37	697.66	P-1	AIR HAMMER			
P-2	619599.91	2232847.91	1144.18	600	784.18	20	625	788.18	605	625	6.5	4/6/92	3/23/92	3/26/92	2.80	625	886.18	917.49	917.49	917.82	917.71	918.91	920.26	922.33	923.02	923.02	P-2	AIR HAMMER		
P-3	618377.15	2232760.68	1564.50	625	769.5	34	625	769.5	575	625	6.5	4/29/92	4/28/92	1.88	504	880.51	736.40	736.31	735.4	735.19	735.29	734.97	733.52	733.02	733.51	P-3	AIR HAMMER & SAM-CASE			
P-4	614255.38	2232840.59	1567.00	625	762	37	675	712	575	625	6.5	4/11/92	4/28/92	2.00	525	862							918.08	841.75	915.75	917.75	P-4	AIR HAMMER & SAM-CASE		
P-6	619199.92	2232775.89	1050.51	425	625.51	0	409	643.51	309	409	5.5	4/22/92	4/26/92	2.63	285	787.51	791.26	790.88	786.02	782.38	779.51	775.76	772.42	769.01	766.74	P-6	AIR HAMMER			
P-7	619091.96	2232383.61	1050.90	425	625.96	0	423	627.9	373	423	5.5	4/29/92	4/26/92	2.42	275	775.96	756.29	765.09	755.79	752.75	754.34	753.67	756.29	754.38	751.84	P-7	AIR HAMMER			
P-8	619090.92	2232337.93	1050.80	400	650.8	0	373	677.8	323	373	5.5	4/29/92	4/26/92	2.29	185	886.6	779.02	780.71	774.68	787.11	786.14	784.35	783.53	783.14	782.6	P-8	AIR HAMMER			
P-9		1000'	525	505'		260	520	510	470	520	5.625	4/29/92	5/6/92	0.75	475	555'			600'	599.58	600.25	600.25	600.46	589.5	601.75	589.58	P-9	AIR HAMMER & SAM-CASE		
P-10		1120'	675	645'		180	675	645	625	675	5.625	5/11/92	5/11/92	2.33	570	550'			591'	591.21	591.41	591.15	591.88	590.25	592.41	590.67	P-10	AIR HAMMER & SAM-CASE		
P-11		800'	485	445'		N/A	470	372	350	470	5.5	5/12/92	5/18/92	3.28	425	555'			576'	577.31	577.56	577.87	578.67	577.8	580.34	578	P-11	AIR HAMMER & SAM-CASE		
P-12		842'	600	342'		N/A	500	342	450	600	5.625	5/29/92	5/30/92	2.89	420	422'					509.25	522.75	503.86	502.06	503.81	500.61	P-12	AIR HAMMER & SAM-CASE		
P-13		1320'	725	625'		0	725	625	675	725	5.5	6/16/92	6/16/92	2.41	650	678'						600.25	600.71	601	603.06	602.41	601.66	P-13	AIR HAMMER	

APPROXIMATE ELEVATIONS - NOT YET SURVEYED
 (1) PIONEER DRILLING
 (2) BAYLAK DRILLING
 (3) LAYNE ENVIRONMENTAL DRILLING
 (4) NOT CONSTRUCTED
 (5) NOT DRILLING

(6) PIONEER DRILLING
 (7) WELL WAS ARTISAN WHEN DRILD
 (11) VIDEO LOG


(16) E-LOG, GAMMA LOG, CALIPER LOG, SOUND LOG
 (17) E-LOG, GAMMA LOG
 (18) PHOTOS TAKEN OF CORE
 (19) HOLE ABANDONED
 * READING ACCURATE TO WITHIN ONE FOOT

GENERAL DATA SUMMARY SHEET
 UPDATED 8/27/92
 Eagle Mountain Landfill, Riverside County, California
 MINE RECLAMATION CORPORATION
 GSWater

BOREHOLE NO.	LOCATION		GROUND ELEV. FT.	DEPTH DRILLED FT.	BOTTOM ELEV. FT.	DEPTH TO BEDROCK FT.	CASING DEPTH FT.	CASING ELEV. FT.	DEPTH OF SCREENED INTERVAL		HOLE SIZE IN	DRILLING DATES		HEIGHT OF CASING FT.	DEPTH TO 1ST WATER FT.	ELEV. OF 1ST WATER FT.	5/20/92 SWL ELEV. FT.	6/3/92 SWL ELEV. FT.	6/17/92 SWL ELEV. FT.	7/1/92 SWL ELEV. FT.	7/15/92 SWL ELEV. FT.	7/29/92 SWL ELEV. FT.	8/13/92 SWL ELEV. FT.	9/25/92 SWL ELEV. FT.	BOREHOLE NO.	REMARKS						
	NORTHING STATION	EASTING OFFSET							FROM	TO		BEGIN	END																			
DFH-20	617767.38	2240015.1	1082.75										11/22/54	1/25/55	21																	
DFH-21	617658.42	2240015.1	1082.75														668.151	665.86	666.33	666.1	666.02	668.33	665.9	667.5	667.37		DFH-20					
DFH-11	617192.26	2240748.33	928.48														673.191	673.33	672.17	672.8	672.73	672.67	672.43	670.74	671.82		DFH-11					
DFH-1	616745.80	2247800.25	918.48		1530	4116.32		961									654.73	654.38	654.94	654.71	656.89	655.6	654.66	653.31	653.85		DFH-1					
DFH-1	616114.60	2250435.42	871.29		1250	4381.71		1270									645.45	645.49	645.51	643	647.84	648.35	645.39	648.35	644.21		DFH-1					
DFH-1	617540.11	2247822.56	915.68		1548.6	4033.42		1150									665.75	675.58	675.81	675.5	675.33	675.25	674.38	676.75	674.3		DFH-1					
DFH-10	617075.25	2244534.30	972.41														670.12	669.82	669.81	668.65	671.29	669.85	669.54	670.54	668.18		DFH-10					
DFH-15	616689.21	2244535.32	978.71														667.66	662.71	663.17	663.88	663.04	662.73	663.18	664.5	662.88		DFH-15					
DFH-24	617792.85	2240912.57	1064.42														698.67	698.76	698.81	698.51	698.42	698	697.13	697.25	698.13		DFH-24					
MISC. WELLS																											MISC. WELLS					
SCHOOL			748.5			211.5		740	500								722	719	718.75	718.08	718.46	718.62	718.25	718.33		SCHOOL	ROTARY					
OW1			742		1328	666																					OW1	MUD ROTARY				
OW2			730		687	44		55	258		331	527		1.00													OW2	MUD ROTARY				
OW3			727		690	30		570	167		273	562		5													OW3	MUD ROTARY				
OW4			697		660	37		500	187		170	410															OW4	MUD ROTARY				
KAISER MN	614055.23	2244637.33	978.48														668.41	668.18	666.41	666.00	668.99	668.26	668.26	667.74	667.98		KAISER MN					

NOTES: * APPROXIMATE ELEVATIONS
 ** READINGS ACCURATE TO WITHIN ONE FOOT

BOREHOLE DATA SUMMARY SHEET
 UPDATED 8/27/92
 Esda Mountain Landfill, Riverside County, California
 MINE RECLAMATION CORPORATION
 GSA/uzer



BORING LOG

PROJECT: EAGLE MOUNTAIN
 LOCATION:
 JOB NUMBER: 0187073.03
 GEOLOGIST / ENGINEER: S. GARBACCO / K. USTER
 DRILLER: PIONEER
 DRILLING METHOD: MUD ROTARY

HOLE / WELL #: M.W.-1
 DIAMETER: 10"
 TOTAL DEPTH: 400'
 DATE STARTED: APRIL 27, 1989
 DATE COMPLETED: MAY 18, 1989
 SAMPLING DEVICE:
 PAGE: 1 OF 7

SCS ENGINEERS
 Geotechnical Engineers
 5711 Long Beach Blvd.
 45th Floor
 Long Beach, CA
 90807-3218
 (714) 488-1800
 FAX (714) 487-1000

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
0						DIRECT AIR ROTARY USED TO SET STEEL CASING
1		10" DIAMETER LOCKING WICHAMANT COVER				
2						
3						
4						
5						
6	5" DIAMETER SCHEDULE 80 PVC					LIGHT TAN SILTY FINE TO VERY COARSE SAND WITH 25% GRAVEL TO 2" (BOULDERS > 1 FOOT OBSERVED IN BOREHOLE) GRAVEL IS MOSTLY GRANITE WITH EPIDOTE VEIN QUARTZ AND MINOR MAGNETITE - HEMATITE ORE
7		10" DIAMETER STEEL CASING				
8						
9						
10						
11						
12						MUD ROTARY MUD REMOVES FINES
13						
14						
15		CONCRETE-BENTONITE GROUT				
16						
17						
18						
19						
20						

BORING LOG

PROJECT: EAGLE MOUNTAIN
 JOB NUMBER: 0187073.03

HOLE / WELL #: M.W.-1
 PAGE: 3 OF 7

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
90						
95						SAME AS ABOVE 40% QUARTZ, 40% FELDSPAR, 20% DARK COLORED GRAINS
100						
105		7" DIAMETER SCHEDULE 80 PVC				
110						CUTTINGS ARE COARSE SAND SIZED 50% QUARTZ, 40% FELDSPAR, 10% DARK COLORED GRAINS
115						
120		CONCRETE-BENTONITE GROUT				45% QUARTZ, 40% FELDSPAR, 15% DARK COLORED GRAINS
125						
130						
135						
140						
145						
150						50% QUARTZ, 35% FELDSPAR, 15% DARK COLORED GRAINS

BORING LOG

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073.03

HOLE/WELL #: M.W.-1
PAGE: 4 OF 7

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USGS SYMBOL	DESCRIPTION
156						
160						45% QUARTZ, 40% FELDSPAR, 15% DARK COLORED GRAINS
165						
170		1" DIAMETER SCHEDULE 80 PVC				
175						
180						
185						
190		CONCRETE - BENTONITE GROUT				190' - 246' SILT - CLAY, VERY LITTLE SAND IN CUTTINGS, SLOW DRILLING
195						
200						
205						
210						
215						

BORING LOG

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073.03

HOLE/WELL #: M.W.-1
PAGE: 5 OF 7

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USGS SYMBOL	DESCRIPTION
220						
225						
230						
235		1" DIAMETER SCHEDULE 80 PVC				
240		CONCRETE - BENTONITE GROUT				
245						COARSE SAND SIZED GRAINS, SURROUNDED TO ANGULAR, 50% QUARTZ; 25% FELDSPAR, 25% EPIDOTE, IRON ORE, GRANITE FRAGMENTS
250						
255						
260						260' COBBLES - BOULDERS
265						264' COBBLES - BOULDERS
270						
275						
280						
285						
290						
295						
300						
305						
310						
315						
320						
325						
330						
335						
340						
345						
350						
355						
360						
365						
370						
375						
380						
385						
390						
395						
400						
405						
410						
415						
420						
425						
430						
435						
440						
445						
450						
455						
460						
465						
470						
475						
480						
485						
490						
495						
500						
505						
510						
515						
520						
525						
530						
535						
540						
545						
550						
555						
560						
565						
570						
575						
580						
585						
590						
595						
600						
605						
610						
615						
620						
625						
630						
635						
640						
645						
650						
655						
660						
665						
670						
675						
680						
685						
690						
695						
700						
705						
710						
715						
720						
725						
730						
735						
740						
745						
750						
755						
760						
765						
770						
775						
780						
785						
790						
795						
800						
805						
810						
815						
820						
825						
830						
835						
840						
845						
850						
855						
860						
865						
870						
875						
880						
885						
890						
895						
900						
905						
910						
915						
920						
925						
930						
935						
940						
945						
950						
955						
960						
965						
970						
975						
980						
985						
990						
995						
1000						

BORING LOG

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073.03

HOLE/WELL #: MW-1
PAGE: 5 OF 7

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS/ FOOT	USCS SYMBOL	DESCRIPTION
285		5" DIAMETER SCHEDULE 40 PVC				284' - 290' COBBLES - BOULDERS
290						
295		HOLE CAVER				
300						COARSE SAND SIZED CUTTINGS, 30% MAFIC ROCK FRAGMENTS, 30% QUARTZ, 30% FELDSPAR, 10% EPIDOTE
305		HOLE CAVER				
310						
315		NATIVE SOIL				318' COBBLES - BOULDERS
320						
325		HOLE CAVER				328' - 330' COBBLES - BOULDERS
330						
335		HOLE CAVER				
340						
345		HOLE CAVER				
350						

BORING LOG

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073.03

HOLE/WELL #: MW-1
PAGE: 7 OF 7

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS/ FOOT	USCS SYMBOL	DESCRIPTION
350		HOLE CAVER				WATER AT 350.7 MUD THINS OUT
355						
360		HOLE CAVER				
365						
370		HOLE CAVER				374' - 377' SILT - CLAY VERY LITTLE SAND IN CUTTINGS, SLOW DRILLING
375						
380		HOLE CAVER				380' COBBLES - BOULDERS
385						COARSE SAND SIZED CUTTINGS, 40% QUARTZ, 30% FELDSPAR, 30% IRON ORE, EPIDOTE, MAFIC ROCK FRAGMENTS
390		HOLE CAVER				
395						
400		HOLE CAVER				398' - 400' ANGULAR CHIPS OF IRON ORE TO 0.2" T.D. = 400'
405						

BORING LOG

PROJECT: EAGLE MOUNTAIN
 LOCATION:
 JOB NUMBER: 0187073.09
 GEOLOGIST/ENGINEER: B. GARBACCIO
 DRILLER: BEYUK
 DRILL RIG: PORTADRILL
 DRILLING METHOD: AIR ROTARY / MUD ROTARY

HOLE / WELL #: BH 4 / MW 2
 DIAMETER: 10"
 TOTAL DEPTH: 455'
 DATE STARTED: MARCH 28, 1990
 DATE COMPLETED: APRIL 4, 1990
 SAMPLING DEVICE: CYCLONE
 PAGE: 1 OF 9

SCS ENGINEERS
 Environmental Consultants
 3711 Long Beach Blvd.
 1940 P.O. Box
 Long Beach, CA
 90807-3219
 (714) 438-1664
 FAX (714) 437-1028

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
0						START WITH AUGER TO SET SURFACE CASING
1		15" DIAMETER STEEL SURFACE CASING			SC - GC	0 - 15' - TAN - LIGHT BROWN CLAYEY SAND WITH GRAVEL, COBBLES AND BOULDERS (TO 6" OBSERVED); SUBANGULAR TO SUBROUNDED; GRANITE, QUARTZITE, IRON ORE; DRY
2						
3						
4						
5						
6						
7						
8						
9		CONCRETE GROUT TO SURFACE				15' - 60' - DRILLED WITH 8" DOWNHOLE HAMMER
10						
11						CUTTINGS SEGREGATE IN CYCLONE
12						
13		4" DIAMETER CARBON STEEL CASING WITH WELDED COUPLINGS			SP	SAND WITH GRAVEL TO 1" OBSERVED, GRANITE WITH GREENSCHIST ALTERATION, CALC SILICATE ROCK, QUARTZITE, IRON ORE; NO CEMENT, SMALLER FRACTION IS MORE ANGULAR (FRAGMENTS OF LARGER ROCKS)
14						
15						
16						
17						
18						
19						
20						20' - SLIGHT CAVING

BORING

PROJECT: EAGLE MOUNTAIN
 JOB NUMBER: 0187073.09

HOLE / WELL #: BH 4 / MW 2
 PAGE: 2 OF 9

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
30						
40					SP	40' - FINES ARE LOST FROM CYCLONE COARSE SAND AND GRAVEL TO 2" OBSERVED, ANGULAR TO SUBROUNDED, GRANITE, IRON ORE, QUARTZITE; NO CEMENT OR CLAY OBSERVED
50		4" DIAMETER CARBON STEEL CASING WITH WELDED COUPLINGS				40' - 45' - BEGIN TO GET INTO CEMENTED ZONE, SEVERAL OF THE 0.1 - 0.2" GRAVEL GRAINS HAVE TAN CLAY COATINGS
60					SP - GW	60' - SWITCH TO 5" TRICONE BIT
70						SAND AND GRAVEL TO 1" OBSERVED, ANGULAR TO SUBROUNDED, WHOLE CLASTS AND PIECES OF LARGER ROCKS, NO CLAY OR CEMENT; GRANITE, QUARTZITE, IRON ORE, PALE GREEN MARBLE, EPIDOTE; DRY
80						75' - TRACE CEMENT ON 0.1 - 0.2" GRAVEL
90						80' - 85' - SMALL PIECES OF GRAVEL ARE PARTLY COATED WITH CLAY CEMENT, LARGE QUANTITY OF FINE BROWN CLAY IN DUST FROM CYCLONE, COHESIVE WHEN WET; DRY

BORING

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073.09

HOLE/WELL #: BH 4 / MW 2
PAGE: 3 OF 9

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
90						95' - GRAVEL HAS CLAY COATINGS, VERY LITTLE CLAY IN FINES
100					SP	100' - COARSE SAND WITH <10% GRAVEL; FINES ARE NOT COHESIVE WHEN WET; GRAVEL HAS SAND GRAINS CEMENTED TO IT, DRY
110					SP	105' - 110' - SAND WITH 10 - 20% GRAVEL TO 1", VERY LITTLE FINES; GRAVEL HAS CLAY - CEMENT COATINGS, MOSTLY SUBROUNDED; GRANITE, FINE GRAINED CALC SILICATE ROCK, EPIDOTE, WHITE QUARTZITE, RED BROWN VESICULAR VOLCANIC OR DIKE ROCK
120					SP	125' - SAME AS ABOVE
130					SP	135' - VERY LITTLE FINES, GRAVEL IS MOSTLY ANGULAR QUARTZITE FROM LARGER ROCKS; SUBROUNDED GRANITE AND FINE GRAINED CALC SILICATE ROCK HAS CLAY - CEMENT COATINGS
140				SC	145' - 150' - CLAY RICH ZONE WITH COARSE SAND AND GRAVEL TO 0.5"; CLAY IS LIGHT TAN (REDDISH BROWN WHEN WET), GRAVEL IS ANGULAR TO SUBROUNDED; GRANITE, QUARTZITE, BLACK FINE GRAINED MAGIC DIKE ROCK, IRON ORE; SOME PIECES HAVE CLAY COATINGS; DRY	

BORING

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073.09

HOLE/WELL #: BH 4 / MW 2
PAGE: 4 OF 9

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
150						
160					SC	165' - CLAY RICH ZONE WITH SAND - 20% GRAVEL TO 0.5" (MOSTLY < 0.3") OBSERVED, SUBANGULAR TO SUBROUNDED, CLAY COATINGS ON SOME PIECES; META- ARKOSE, GRANITE, QUARTZITE, IRON ORE; DRY
170					SC - GC	180' - 185' - CLAY RICH ZONE WITH COARSE TO VERY COARSE SAND AND GRAVEL; GRAVEL IS ANGULAR TO SUBROUNDED, GRANITE, QUARTZITE, IRON ORE; DRY
180					CL	190' - CLAY RICH ZONE WITH < 20% SAND AND GRAVEL, CLAY IS LIGHT TAN (MEDIUM PINK - BROWN WHEN WET), GRAVEL INCLUDES GRANITE, IRON ORE (MAGNETITE), DICRITE, QUARTZ, EPIDOTE
190					SP - GW	195' - COARSE SAND AND GRAVEL TO 0.5", MOSTLY ANGULAR CHIPS OF GRANITE AND IRON ORE (MAGNETITE)
200				SC	205' - CLAY WITH SAND AND GRAVEL TO 0.5" OBSERVED, ANGULAR TO SUBROUNDED, GRANITE, IRON ORE, QUARTZITE, EPIDOTE; DRY	

BORING

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073 09

HOLE/WELL #: BH 4/MW 2
PAGE: 5 OF 9

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
210						
220						
230		4" DIAMETER CARBON STEEL CASING WITH WELDED COUPLINGS				
		CONCRETE GROUT TO SURFACE				
240						
250						
250						
					SP	225' - COARSE TO VERY COARSE SAND WITH APPROXIMATELY 10% GRAVEL. ROUNDED GRAINS; DRY
					SC - GC	230' - CLAY WITH SAND AND GRAVEL. GRANITE, MAFIC DIKE ROCK, QUARTZITE
					SC - GC	245' - 280' - CLAY WITH SAND AND GRAVEL TO 0.7" OBSERVED. GRAVEL IS ANGULAR TO SUBROUNDED. GRANITE, EPIDOTE, QUARTZITE, IRON ORE, WITH CLAY - CEMENT COATINGS, DRY

BORING

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073 09

HOLE/WELL #: BH 4/MW 2
PAGE: 6 OF 9

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
270						
280						
290		4" DIAMETER CARBON STEEL CASING WITH WELDED COUPLINGS				
		CONCRETE GROUT TO SURFACE				
300						
310						
310					SP	280' - 300' - CLAY WITH COARSE - VERY COARSE SAND AND GRAVEL TO 0.7" OBSERVED. MOSTLY ANGULAR CHIPS OF QUARTZITE AND GRANITE; SUBROUNDED - ROUNDED IRON ORE, META-ARKOSE, GRANITE; DRY
					SP	310' - CLAY WITH SAND AND <10% GRAVEL TO 0.5" OBSERVED. SUBROUNDED, DIORITE, FINE GRAINED CALC SILICATE ROCK, QUARTZITE, MAFIC DIKE ROCK; AGGREGATES OF CEMENTED SAND; DRY
320						
					SR - GW	325' - CLAY WITH SAND AND 10 - 20% GRAVEL TO 0.5" OBSERVED. MOSTLY ANGULAR TO SUBANGULAR, GRANITE, QUARTZITE, FINE GRAINED CALC SILICATE ROCK; SOME GRAINS HAVE CLAY COATINGS; DRY

BORING

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073.09

HOLE/WELL #: BH 4 / MW 2
PAGE: 7 OF 9

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
330					SC	330' - CLAY RICH ZONE SAND WITH GRAVEL TO 1" OBSERVED. SUBANGULAR. GRANITE. DRY
340					CL	340' - 345' - CLAY WITH APPROXIMATELY 10% SAND. CLAY HAS A TRACE OF MOISTURE 346' - 347' - TRACE MOISTURE IN CLAY. GRAVEL HAS MOIST COATINGS 348' - RED IRON ORE IN CUTTINGS
350		4" DIAMETER CARBON STEEL CASING WITH WELDED COUPLINGS CONCRETE GROUT TO SURFACE				
360					SC	365' - CLAY WITH SAND
370		4" BENTONITE SEAL TOP OF SAND 374' CARBON STEEL TO STAINLESS STEEL DIELECTRIC CONNECTOR				370' - DRY 375' - DRY
380		20" STAINLESS STEEL BLANK CASING			GC	380' - CLAY WITH GRAVEL TO 0.5" OBSERVED. MOSTLY FINE GRAINED CAL SILICATE ROCK. CLAY IS VERY SLIGHTLY MOIST

BORING

PROJECT: EAGLE MOUNTAIN
JOB NUMBER: 0187073.09

HOLE/WELL #: BH 4 / MW 2
PAGE: 8 OF 9

DEPTH (FEET)	SAMPLE	COMPLETION DETAIL	SAMPLE #	BLOW COUNTS / FOOT	USCS SYMBOL	DESCRIPTION
390					SP	390' - 396' - COARSE SAND AND GRAVEL WITH AGGREGATES OF SAND CEMENTED TOGETHER
400					SP	400' - LET HOLE STAND OPEN FOR 15 MINUTES - NO WATER 405' - COARSE SAND WITH MINOR GRAVEL, GRANITE AND IRON ORE (MAGNETITE)
410		8 1/2" O.D. 3/16" STAINLESS STEEL SCREEN 396' - 436' 43 MONTGOMERY SAND				
420						INJECT WATER
430					SW	425' - 430' - FINE TO COARSE SAND (NOT TYPICAL) WITH <10% GRAVEL TO 0.3" OBSERVED. ANGULAR, CLEAN - NO CEMENT. MOSTLY GRANITE WITH TRACE MAGNETIC IRON ORE
440		FLUSH THREADED COUPLINGS			SP	435' - 440' - DRILL THROUGH BOULDERS OF IRON ORE. CUTTINGS TURN RED 440' - COARSE SAND GRANITE, GLASSY QUARTZ, MAGNETITE - HEMATITE IRON ORE
						TD = 440' WITH AIR ROTARY

Site / Location CENTRAL PIT	Squad Date 02/16/92	Borehole Dia 14"	Ground Elevation 3311.35'	Borehole No. MW-10
Coordinates / Stationing	Completion Date 03/09/92	Logged By B. WILCOXON, R. REYNOLDS, B. MARSH		Bottom of Borehole (bgs) 1420'
Drill Make and Model INGERSOLL-RAND T 4 W	Drilling Method HAMMER / ROTARY	Drill Fluid AIR / MUD	Top of Bedrock (bgs) 7'	First Encountered 130'
Drilling Contract TOWTO DRILLING SERVICES	Swit Cap Code/Deg/Depth 15' / 15 1/2" 40'	Total Core Recovery % N/A	Total Number of Core Boxes N/A	Static Water Level

REMARKS: Water Data Drilling Data Personnel Changes	Tool Size	Blows / FOOT %	Advance / Recovery	Tool Wear (Min / 8 ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
Foreman: Wayne Beaupre Drill Crew A (Morning) Driver: Frank Night Helpers: Jim Wiser Jason Verdi Drill Crew B (Afternoon) Driver: Mitch Bronson Helpers: Rick Gostovich Walt McKinney No samples taken for the first 310 feet. 310' depth at 5:00 p.m., added 27' rod, and resumed drilling at 5:05 p.m. on 02/16/92. 330' depth at 6:00 p.m., added 27' rod, and resumed drilling at 6:15 p.m. on 02/16/92. 350' depth at 7:45 p.m., added 27' rod, and resumed drilling at 8:00 p.m. on 02/16/92. 370' depth at 10:00 p.m., added 27' rod, and resumed drilling at 10:15 p.m. on 02/16/92.	1 1/2" cone						No samples taken below 310'.	
					310'	310	310.0 - 320.0' IRON ORE	Dark gray, magnetite-rich, compact, hard, extremely strong; containing minor quartzite, calc-silicates.
					320'	320	320.0 - 350.0' QUARTZITE	Yellow-tan, fine grained, very hard, very strong, minor calc-silicates and disseminated magnetite-hematite/sericite grains.
		1 1/2" Air Hammer			330'	330	330.0 - 340.0' IRON ORE	Dark gray, brown, magnetite-rich, hard, strong, minor green-tan calc-silicates, sericite; trace yellow-tan quartzite.
					350'	350	350.0 - 360.0' IRON ORE	Dark gray, brown, magnetite-rich, hard, strong, minor green-tan calc-silicates, sericite; trace yellow-tan quartzite.

	DATE	04/92		BOREHOLE LOG MW-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	FIGURE NO.	
	JOB NO.	G125-19				
	DWG NO.	EM19010/1				
	DRAWN	J HATALA				
	CHECK'D	R HARRIS				
APP'D	D AFFELDT					

REMARKS: Water Data Drilling Data Personnel Changes	Tool Size	Blows / FOOT %	Advance / Recovery	Tool Wear (Min / 8 ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
390' depth at 12:45 a.m., added 27' rod, and resumed drilling at 12:52 a.m. on 02/16/92. 410' depth at 2:07 a.m., added 27' rod, and resumed drilling at 2:19 a.m. on 02/16/92. 430' depth at 5:51 a.m., added 27' rod, and resumed drilling at 6:01 a.m. on 02/16/92. 450' depth at 6:30 a.m., added 27' rod, and resumed drilling at 6:42 a.m. on 02/16/92.	1 1/2" Air Hammer						370	350.0 - 380.0' IRON ORE Dark gray, brown, magnetite-rich, hard, extremely strong; minor green / brown calc-silicates, sericite, trace yellow / brown quartzite.
					380'	380	380.0 - 400.0' QUARTZ MONZONITE	Light yellow to reddish brown, fine grained, hard, very strong; minor green calc-silicates (gossite / sericite).
					390'	390	390.0 - 400.0' IRON ORE	Dark gray to brown magnetite-hematite, hard, extremely strong; minor green calc-silicates (gossite / sericite).
					410'	410	410.0 - 420.0' IRON ORE	Dark gray to brown magnetite-hematite, hard, extremely strong; minor green calc-silicates (gossite / sericite).
		1 1/2" Air Hammer			420'	420	420.0 - 440.0' SKARN	Dark gray calc-silicates (gossite / sericite); hard, moderately strong; trace dark gray iron ore.
					430'	430	430.0 - 440.0' QUARTZ MONZONITE	Reddish brown, fine grained; very hard, very strong; minor dark green calc-silicates (gossite / sericite).
					450'	450	450.0 - 450.0' MARC ORE	

	DATE	04/92		BOREHOLE LOG MW-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	FIGURE NO.	
	JOB NO.	G125-19				
	DWG NO.	EM19010/2				
	DRAWN	J HATALA				
	CHECK'D	R HARRIS				
APP'D	D AFFELDT					

REMARKS: Water Data Drilling Data Personnel Changes	Tool Size	Blows / ROD %	Advance / Recovery	Drill Rate (Min / S ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
<p>657 depth at 9:50 p.m., added 20' rod, and resumed drilling at 11:01 p.m. on 02/25/92.</p> <p>Sreak in hydraulic hose, rig shut down. Resumed drilling at 6:16 p.m. on 02/22/92.</p> <p>677 depth at 11:00 p.m., added 20' rod, and resumed drilling at 11:15 p.m. on 02/25/92.</p> <p>697 depth at 3:00 p.m., added 20' rod, and resumed drilling at 3:20 p.m. on 02/25/92.</p>	14" Air Hammer					610	600 - 620' QUARTZITE Yellow / brown, fine grained; very hard, very strong; minor banding of calc-silicate.	
						620	620 - 630' ANDESITE Dark gray, porphyritic; hard, very strong; minor quartz monzonite.	
			630			630	630 - 640' QUARTZ MONZONITE Light yellow to reddish brown, fine grained; hard, very strong; minor epidote, trace calcite.	
						640	640 - 650' QUARTZITE Dark green / gray, fine grained; very hard very strong; minor epidote, tremolite, trace limonite.	
			650			650	650 - 670' ANDESITE Dark gray, porphyritic; hard, very strong; minor quartz monzonite.	
						660		
			670			670	670 - 690' QUARTZITE Light gray to dark gray green; very hard, very strong; minor limonite.	
						680		
			690			690	690 - 700' ANDESITE	

	DATE	04/92	<p>The PRA Group, Inc CONSULTING ENGINEERS</p> <p>BOREHOLE LOG MW-10</p> <p>EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA</p> <p>MINE RECLAMATION CORPORATION</p>
	JOB NO.	G125-19	
	DWG NO.	EM19010/S	
	DRAWN	J HATALA	
	CHECKED	R HARRIS	
APPD	D AFFELDT		

REMARKS: Water Data Drilling Data Personnel Changes	Tool Size	Blows / ROD %	Advance / Recovery	Drill Rate (Min / S ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
<p>717 depth at 12:30 p.m., added 20' rod, and resumed drilling at 7:45 a.m. on 02/25/92.</p> <p>737 depth at 11:00 a.m., added 20' rod, and resumed drilling at 11:15 a.m. on 02/25/92.</p> <p>757 depth at 4:35 p.m., added 20' rod, and resumed drilling at 4:50 p.m. on 02/25/92.</p> <p>770 depth at 7:15 p.m., added 20' rod, and resumed drilling at 7:30 p.m. on 02/25/92.</p>	13 3/4" Til Cone					690	690 - 700' ANDESITE Medium-dark gray, fine grained; hard, very strong; minor iron ore and quartz monzonite, trace epidote and limonite stain.	
						700		
			710			710	710 - 720' ANDESITE Medium-dark gray, fine grained; hard, very strong; minor iron ore and quartz monzonite, trace epidote and limonite stain.	
		13 1/2" Til Cone				720		
			730			730	730 - 750' IRON ORE Dark gray magnetite-hematite; hard, strong; minor epidote.	
						740		
		12 3/4" Til Cone				750	750 - 760' ANDESITE Medium-dark gray, fine grained; hard, very strong; minor iron ore and quartz monzonite, trace epidote and limonite stain.	
			760			760	760 - 770' QUARTZITE Tan gray to gray green, fine grained; very hard, very strong; minor limonite staining.	
						770		
			770			770	770 - 780' ANDESITE	

	DATE	04/92	<p>The PRA Group, Inc CONSULTING ENGINEERS</p> <p>BOREHOLE LOG MW-10</p> <p>EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA</p> <p>MINE RECLAMATION CORPORATION</p>
	JOB NO.	G125-19	
	DWG NO.	EM19010/6	
	DRAWN	J HATALA	
	CHECKED	R HARRIS	
APPD	D AFFELDT		

REMARKS: Wear Data Coring Data Personnel Changes	Tool Size	Blows / FOOT % Advance / Recovery	DW Rate (Min / 6 ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
787 depth at 10:00 p.m., added 20' rod, and resumed drilling at 12:01 a.m. on 02/25/92. Deviation Survey = 2" 817 depth at 8:25 a.m., added 20' rod, and resumed drilling at 8:35 a.m. on 02/26/92. 837 depth at 10:45 a.m., add to rebar then pump. Added 20' rod, and resumed drilling at 4:50 p.m. on 02/25/92. 857 depth at 4:30 p.m., added 20' rod, and resumed drilling at 4:40 p.m. on 02/26/92.	12 3/4" Tn Cone	20' in 30 hrs 17 min			770	770.0 - 780.0' ANDESITE Medium to dark gray, fine grained; hard, very strong; minor quartzite and iron ore stain, trace iron ore and sodic.	
					780	780.0 - 790.0' QUARTZ MONZONITE Light yellow to reddish brown, fine grained; hard, very strong; minor iron ore, trace iron stain.	
			790' 20' in 6 hrs 27 min		790	790.0 - 810.0' QUARTZITE Light gray green, fine grained; very hard, very strong; minor iron ore.	
		13 1/2" Tn Cone			800		
			810' 20' in 2 hrs 10 min		810		
				820			
				830		810.0 - 850.0' ANDESITE Dark green to gray tan, fine grained; hard, very strong; minor iron ore with disseminated pyrite, trace iron ore.	
	13 3/4" Tn Cone	20' in 2 hrs 57 min		840			
				850		850.0 - 860.0' QUARTZITE	

	DATE	04/92		The PRA Group, Inc CONSULTING ENGINEERS	BOREHOLE LOG MW-10	EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION
	JOB NO.	G125-13				
	DWG NO.	EM19010/7				
	DRAWN	J HATALA				
	CHECKED	R HARRIS				
	APP'D	D AFFELOT				

REMARKS: Wear Data Coring Data Personnel Changes	Tool Size	Blows / FOOT % Advance / Recovery	DW Rate (Min / 6 ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
870 depth at 7:00 p.m., added 20' rod, and resumed drilling at 7:45 p.m. on 02/25/92. 917 depth at 2:04 a.m., added 20' rod, and resumed drilling at 2:19 a.m. on 02/27/92. 957 depth at 5:05 a.m., added 20' rod, and resumed drilling at 5:40 a.m. on 02/26/92.	13 3/4" Tn Cone	20' in 2 hrs 45 min			850	850.0 - 860.0' QUARTZITE Light gray green, fine grained; hard, very strong; minor iron ore and sodic.	
					860	860.0 - 890.0' ANDESITE Light to dark green, fine grained; hard, very strong; minor iron ore, iron ore, trace pyrite.	
			870'		870		
					880		
			890'		890		890.0 - 970.0' QUARTZITE Gray - green, fine grained; very hard, very strong; minor sodic.
				900			
				910		910.0 - 920.0' Trace tremolite and pyrite.	
	13 1/2" Tn Cone	20' in 3 hrs 16 min		920			
				930			

	DATE	04/92		The PRA Group, Inc CONSULTING ENGINEERS	BOREHOLE LOG MW-10	EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION
	JOB NO.	G125-13				
	DWG NO.	EM19010/8				
	DRAWN	J HATALA				
	CHECKED	R HARRIS				
	APP'D	D AFFELOT				

REMARKS: Water Data Drilling Data Personnel Changes	Tool Size	Bore / ROD %	Advance / Recovery	Drill Rate (Min / 6 ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
	13 1/2" Tr Cone					930	890.0 - 970.0' QUARTZITE	Gray - green, fine grained; very hard; very strong; minor epidote.
						940		
						950		
	13 3/4" Tr Cone					960		
						970	970.0 - 990.0' ANDESITE	Dark green, fine grained; hard; very strong; minor quartzite, trace ironite.
						980		
						990	990.0 - 1010.0' QUARTZITE	Light green to gray, fine grained; very hard; very strong.
						1000	1000.0 - 1010.0' Minor gray to light green andesite.	
Deviation Survey = 1.5"						1010	1010.0 - 1070.0' ANDESITE	
1010' depth @ 317 s.m. added 27' more to drilling log (237) 5/12/92								

	DATE	04/92		BOREHOLE LOG MW-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	FIGURE NO.	
	JOB NO.	G125-19				
	DWG NO.	EM19010/9				
	DRAWN	J HATALA				
	CHECKED	R HARRIS				
APPD	D AFFELDT				1 of 11	

REMARKS: Water Data Drilling Data Personnel Changes	Tool Size	Bore / ROD %	Advance / Recovery	Drill Rate (Min / 6 ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
	13 3/4" Tr Cone					1010	1010.0 - 1070.0' ANDESITE	Dark green to gray, fine grained; hard; very strong; trace ironite. 1010.0 - 1070.0' Slightly porphyritic trace magnetite.
Lost connection						1020		
1030' depth @ 6:25 a.m. 030102						1030		
						1040		
						1050	1050.0 - 1050.0' Epidote, actinolite	
						1060	1060.0 - 1070.0' Trace clear quartz	
						1070	1070.0 - 1090.0' IRON ORE	Dark gray magnetite-hematite; hard, strong; abundant pyrite, minor tremolite.
						1080	1080.0 - 1090.0' Trace andesite.	
						1090	1090.0 - 1195.0' ANDESITE	

	DATE	04/92		BOREHOLE LOG MW-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	FIGURE NO.	
	JOB NO.	G125-19				
	DWG NO.	EM19010/10				
	DRAWN	J HATALA				
	CHECKED	R HARRIS				
APPD	D AFFELDT				1 of 11	


REMARKS: Water Data Drilling Data Personnel Changes	Tool Site	Bore / BOD %	Advance / Recovery	DBI Rate (Min / 8 ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
	13 3/4" Tr Cone					1090		1090.0 - 1195.0' ANDESITE Dark green to black, fine grained; hard, very strong; minor magnetite and pyrite, trace quartz, epidote, tremolite, biotite.
						1100		
	13 1/2" Tr Cone					1110		
						1120		
						1130		
						1140		1140.0 - 1150.0' Medium gray-green; minor quartzite and epidote.
						1150		1150.0 - 1195.0' Dark gray - green.
						1160		1160.0 - 1195.0' Trace magnetite.
						1170		

	DATE	04/92	 The PRA Group, Inc CONSULTING ENGINEERS BOREHOLE LOG MW-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	FIGURE NO.	
	JOB NO.	G125-19			
	DWG NO.	EM19010/11			
	DRAWN	J HATALA			
	CHECKED	R HARRIS			
APPD	D AFFELDT				

REMARKS: Water Data Drilling Data Personnel Changes	Tool Site	Bore / BOD %	Advance / Recovery	DBI Rate (Min / 8 ft)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
	13 1/2" Tr Cone					1170		1090.0 - 1195.0' ANDESITE Dark green to black, fine grained; hard, very strong; minor magnetite and pyrite, trace quartz, epidote, tremolite, biotite.
						1180		
						1190		
						1200		1195.0 - 1235.0' QUARTZITE Light green - gray, very fine grained; very hard, very strong; minor chlorite, trace biotite.
						1210		1210.0 - 1235.0' Minor dark green to black andesite, trace ironite stain.
						1220		1220.0 - 1235.0' Trace magnetite.
						1230		
						1240		1235.0 - 1480.0' ANDESITE Dark green to black, fine grained; hard, very strong; minor magnetite and epidote, trace ironite stain.
						1250		

	DATE	04/92	 The PRA Group, Inc CONSULTING ENGINEERS BOREHOLE LOG MW-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	FIGURE NO.	
	JOB NO.	G125-19			
	DWG NO.	EM19010/12			
	DRAWN	J HATALA			
	CHECKED	R HARRIS			
APPD	D AFFELDT				

REMARKS: Water Cuts Drilling Data Personnel Changes	Tool Site	Bore / ROD %	Address / Flooring	Drill Bits (No. / S. R.)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
1257' depth at 8:00 a.m. on 03/03/92. 1287' depth at 4:00 p.m., on 03/03/92. 1307' depth at 5:54 a.m., on 03/04/92.	13 1/2" To Cone				1250	1250.0 - 1250.0'	1250.0 - 1250.0' ANDESITE Dark green to black, fine grained; hard, very strong; minor magnetite and apatite, trace kyanite.	
					1260	1250.0 - 1260.0'	1250.0 - 1260.0' Minor quartzite, trace crystal calcite	
					1270	1260.0 - 1270.0'	1260.0 - 1270.0' Abundant pink calcite, minor pink with quartz.	
					1280	1270.0 - 1280.0'	1270.0 - 1280.0' Abundant pale green quartzite, minor amphibole, calcite.	
					1290	1280.0 - 1290.0'	1280.0 - 1290.0' 15% magnetite, trace pyrite.	
					1300			
					1310			
					1320			
					1330			



DATE	04/92	The PRA Group, Inc CONSULTING ENGINEERS
JOB NO.	G125-19	
DWG NO.	EM19010/13	BOREHOLE LOG MW-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION
DRAWN	J HATALA	
CHECKED	R HARRIS	
APPRO	D AFFELDT	

REMARKS: Water Cuts Drilling Data Personnel Changes	Tool Site	Bore / ROD %	Address / Flooring	Drill Bits (No. / S. R.)	Elevation (ft)	Depth (ft)	Material Log	Material Classification and Physical Description
	13 1/2" To Cone				1330	1330.0 - 1480.0'	1330.0 - 1480.0' ANDESITE Dark green to black, fine grained; hard, very strong; minor magnetite and apatite, trace kyanite.	
					1340	1340.0 - 1350.0'	1340.0 - 1350.0' Trace pyrite, actinolite.	
					1350			
					1360			
					1370	1370.0 - 1390.0'	1370.0 - 1390.0' Abundant ironite, trace calcite.	
					1380			
					1390			1390.0 - 1400.0' Abundant amphibole.
					1400			1400.0 - 1410.0' Trace pyrite, rare calcite-siderite.
					1410			



DATE	04/92	The PRA Group, Inc CONSULTING ENGINEERS
JOB NO.	G125-19	
DWG NO.	EM19010/14	BOREHOLE LOG MW-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION
DRAWN	J HATALA	
CHECKED	R HARRIS	
APPRO	D AFFELDT	


Project Site / DR# Site WEST END OF EAST PIT	Start Date 04/13/92	Reference Dia 13 3/4"	Ground Elevation 1561.42'	Borehole No. MW-13
Completion / Logging C. I. TRANTHAM	Completion Date 04/17/92	Logged By C. I. TRANTHAM	Bottom of Borehole (Depth) 420'	
Drill Rig Make and Model INGERSOLL RAND T4	Drilling Method Air Hammer	Drilling Fluid Air	Top of Section (Depth) 30'	First Encountered Water Depth 315'
Drilling Contractor TONTON DRILLING SERVICES, INC	Surf Log CDD/Depth 18"OD / 15 1/2"ID / 19'	Total Core Recovery % N/A	Total Number of Core Boxes N/A	Static Water Level Depth

REMARKS: Water Data Drilling Data Personnel Changes	Tool Size	RWD (N)	Fractures / Loss	Percent Core Recovery	Box Number	Section (R)	Depth (Ft)	lithologic log	Material Classification and Physical Description
Night Shift Crew: Driller: Mitch Bronson Helmer: Jason Verce Shannon Samsel	16" Tin Cone						0 - 3.0'	ARTIFICIAL FILL: Gray, dense dry, angular, many 3/4" - 1/4" crushed road surface material.	
Day Shift Crew: Driller: Rick Gustovich Helmer: Chris Fine Dave Cazo							3.0 - 142.0'	QUARTZITE: Gray, fine-grained, scattered veins and veinlets of quartz, tremolite, serpentine, magnetite and white gypsum (?) Scattered thin fracture fillings of white and clear gypsum. Locally breccia present with black FeMg minerals. Barely weathered, very hard, very strong.	
15.0' Bottom of conductor casing.	19" Air Hammer						142.0 - 155.0'	HEMATITE AND QUARTZITE: Red and gray, fine-grained with magnetite, tremolite and mal grains; barely weathered, very hard, very strong.	



DATE	06/92	 The PRA Group, Inc CONSULTING ENGINEERS BOREHOLE LOG MW-13 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY CALIFORNIA MINE RECLAMATION CORPORATION
JOB NO.	G125-19	
DRAWN BY	EM19013/1	
CHECKED BY	J HATALA	
APP'D	R HARRIS	
DATE	06/92	
JOB NO.	G125-19	
DRAWN BY	EM19013/2	
CHECKED BY	J HATALA	
APP'D	D AFFELDT	

REMARKS: Water Data Drilling Data Personnel Changes	Tool Size	RWD (N)	Fractures / Loss	Percent Core Recovery	Box Number	Section (R)	Depth (Ft)	lithologic log	Material Classification and Physical Description
	13 3/4" Air Hammer						70 - 80'		3.0 - 142.0' QUARTZITE: Gray, fine-grained, scattered veins and veinlets of quartz, tremolite, serpentine, magnetite and white gypsum (?) Scattered thin fracture fillings of white and clear gypsum. Locally breccia present with black FeMg minerals. Barely weathered, very hard, very strong.
							80.0 - 110.0'		Dark gray.
							120.0 - 142.0'		Light gray.
							142.0 - 155.0'		HEMATITE AND QUARTZITE: Red and gray, fine-grained with magnetite, tremolite and mal grains; barely weathered, very hard, very strong.



DATE	06/92	 The PRA Group, Inc CONSULTING ENGINEERS BOREHOLE LOG MW-13 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY CALIFORNIA MINE RECLAMATION CORPORATION
JOB NO.	G125-19	
DRAWN BY	EM19013/2	
CHECKED BY	J HATALA	
APP'D	R HARRIS	
DATE	06/92	
JOB NO.	G125-19	
DRAWN BY	EM19013/2	
CHECKED BY	J HATALA	
APP'D	D AFFELDT	

REMARKS Wash Data Drilling Data Personnel Changes	Tool Bits	ROD (ft)	Fractures / foot	Percent Core Recovery	Bore Annular	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
155-210' Cuttings are mainly fine and medium-grained sand sizes.	13 3/4" Air Hammer						150	142.0 - 155.0' HEMATITE QUARTZITE. Red and gray, fine-grained.	
							160	155.0 - 210.0' QUARTZITE. Gray, fine-grained, scattered seams, layers and veins of magnetite, hematite, mica, actinolite, tremolite, white quartz, etc. Slightly weathered, very hard, very strong.	
							170		
							180	180.0 - 190.0' Increased percent of magnetite in cuttings.	
							190	190.0 - 210.0' Approximately 40% of cuttings are magnetite; trace mica and serpentine. Increased percent of magnetite with depth.	
210-225' Cuttings are mostly fine and medium-grained sand sizes.							210	210.0 - 275.0' MAGNETITE, HEMATITE QUARTZITE INTERMIXED. Dark gray, fine-grained, metallic black magnetite, reddish hematite and gray quartzite. Minor veins and fracture fillings of milky quartz, mica, actinolite, and serpentine. Slightly weathered, moderately hard, very strong, brittle. Scattered iron stained fractures.	
							220		
225-227' Cuttings are fine through coarse sand sizes.							230		

REMARKS Wash Data Drilling Data Personnel Changes	Tool Bits	ROD (ft)	Fractures / foot	Percent Core Recovery	Box Number	Direction (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
220' Cuttings predominantly fine and medium sand sizes.	13 3/4" Air Hammer						230	210.0 - 275.0' MAGNETITE, HEMATITE QUARTZITE INTERMIXED. Dark gray, fine-grained, brittle. 220.0 - 275.0' Mostly magnetite. 230.0 - 250.0' Pyrite fragments in cuttings.	
							240		
							250	250.0 - 250.0' Decrease in percent magnetite and increase in percent hematite.	
							260		
							270		
							280	275.0 - 420.0' QUARTZITE. Gray, fine-grained, scattered veins of magnetite. Some fracture filling with gypsum. Few brecciated pieces with quartz, actinolite and mica. Locally conchoidal and cleavage in the quartzite. Slightly weathered, very hard, very strong, chert-like, epoxide, micaite fill.	
							290		
310.0' Depth is end of night shift on 04/15/92. Encountered coarse water at 310'. Saturated sandstone below 247-262'.							300		
							310		



DATE 06/92
JOB NO. G125-19
DWS NO. EM19013/3
DRAWN J. HATALA
CHECKED R. HARRIS
APP'D D. AFFELDT

The PRA Group, Inc.
CONSULTING ENGINEERS
BOREHOLE LOG
MW-13
EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY CALIFORNIA
MINE RECLAMATION CORPORATION



DATE 06/92
JOB NO. G125-19
DWS NO. EM19013/4
DRAWN J. HATALA
CHECKED R. HARRIS
APP'D D. AFFELDT

The PRA Group, Inc.
CONSULTING ENGINEERS
BOREHOLE LOG
MW-13
EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY CALIFORNIA
MINE RECLAMATION CORPORATION

REMARKS Water Data Drilling Data Personnel Changes	Tool Size	RSD (%)	Fractures / Root	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
310' Depth at 7:00 a.m. on 04/17/92	12 1/4" Tr Cone						310		275.0 - 420.0' QUARTZITE: Gray, fine-grained, scattered veins of magnetite. Some fracture filling with gypsum. Few brecciated pieces with quartz, feldspar and mica. Locally banding and lamination in the quartzite. Barely weathered, very hard, very strong, chert, epidote, calcite etc.
315' Begin ejecting some water.							320		320.0 - 333.0' Some brecciation, minor serpentine and magnetite.
320 - 337' Driller reports very tight (as when clay separates in hole).							330		330.0 - 340.0' Banding more noticeable.
337' Depth at 10:03 a.m. on 04/17/92							340		340.0 - 355.0' Increase in percent core feldspar. Scattered oxidized fractures, some filled with clay, some banding and lamination.
350' Depth at 10:50 a.m. on 04/17/92							350		350.0 - 355.0' Brecciated (?), healed, with clay and gouge (?).
350 - 367' Driller reports very tight.							360		355.0 - 375.0' Reddish brown color of outcrops due to scattered magnetite veins. Scattered mica, amphibole-muscovite veins. Scattered iron-stained fractures.
370' End day shift on 04/17/92 and begin night shift on 04/17/92.							370		375.0 - 420.0' Light greenish gray, brecciated with scattered minor veins of hematite/magnetite/serpentine; and veins of amphibole/muscovite in a clayey gouge. Scattered iron-stained fractures.
							380		
							390		
							400		
							410		
							420		420.0' Completed drilling on night shift on 04/17/92.
							430		
							440		
							450		
							460		
							470		
									Bottom of Borehole Total Depth 420.0 feet Elevation: 537.48 feet

REMARKS Water Data Drilling Data Personnel Changes	Tool Size	RSD (%)	Fractures / Root	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
	12 1/4" Tr Cone						350		275.0 - 420.0' QUARTZITE: Gray, fine-grained, scattered veins of magnetite. Some fracture filling with gypsum. Few brecciated pieces with quartz, feldspar and mica. Locally banding and lamination in the quartzite. Barely weathered, very hard, very strong, chert, epidote, calcite etc.
							400		375.0 - 420.0' Light greenish gray.
							420		420.0' Completed drilling on night shift on 04/17/92.
							430		
							440		
							450		
							460		
							470		
									Bottom of Borehole Total Depth 420.0 feet Elevation: 537.48 feet

APPENDIX A

LITHOLOGIC DESCRIPTION

Eagle Mountain Piezometer No. 1

0 - 15ft	<u>ARTIFICIAL FILL</u>
15 - 25ft	<u>QUARTZITE</u>
25 - 45ft	<u>QUARTZITE AND QUARTZ MONZONITE</u>
45 - 65ft	<u>QUARTZITE</u>
65 - 80ft	<u>QUARTZ MONZONITE</u>
80 - 196ft	<u>QUARTZITE</u>
196 - 200ft	<u>QUARTZ MONZONITE WITH SOME QUARTZITE</u>
200 - 205ft	<u>QUARTZITE WITH SOME QUARTZ MONZONITE</u>
205 - 270ft	<u>QUARTZ MONZONITE</u>

APPENDIX A

LITHOLOGIC DESCRIPTION

Eagle Mountain Piezometer No. 11

0- 10ft	<u>POORLY GRADED SAND</u> (SP) : Trace coarse, angular to subrounded gravel; 10% fine, angular to subrounded gravel; 25% coarse, angular to subrounded sand; 60% medium, angular to subrounded sand; 5% fine, subangular to subrounded sand; brown, dry, maximum size = 25mm
10 - 20ft	<u>POORLY GRADED SAND WITH GRAVEL</u> (SP) : 20% coarse, angular to subangular gravel; 15% fine, angular to subangular gravel; 30% coarse, angular to subrounded sand; 35% medium, angular to subrounded sand; trace fine sand; brown, dry, maximum size = 30mm
20 - 75ft	<u>POORLY GRADED SAND WITH GRAVEL</u> (SP) : 5% coarse, angular to subangular gravel; 10% fine, angular to subangular gravel; 40% coarse, angular to subangular sand; 45% medium, angular to subangular sand; trace fine, subangular to subrounded sand; brown, dry, maximum size = 35mm
75 - 135ft	<u>POORLY GRADED GRAVEL WITH SAND</u> (GP) : 25% coarse, angular to subrounded gravel; 35% fine, angular to subrounded gravel; 20% coarse, angular to subrounded sand; 20% medium, angular to subrounded sand; trace fine sand; brown, dry, maximum size = 43mm
135 - 205ft	<u>POORLY GRADED SAND WITH GRAVEL</u> (SP) : 10% coarse, angular to subrounded gravel; 15% fine, angular to subrounded gravel; 30% coarse, angular to subrounded sand; 40% medium, angular to subrounded sand; 5% fine, subangular to subrounded sand; brown, moist (due to injection of water during drilling), maximum size = 37mm
205 - 210ft	<u>POORLY GRADED GRAVEL</u> (GP) : 80% coarse, subangular to subrounded gravel; 20% fine, subangular to subrounded gravel; trace coarse, subangular to subrounded sand; trace medium, subangular to subrounded sand; trace fine, subangular to subrounded sand; trace fines; no dilatancy, medium toughness, medium plasticity, medium dry strength; brown, moist (due to injection of water during drilling), maximum size = 40mm
210- 255ft	<u>POORLY GRADED SAND</u> (SP) : Trace coarse, subangular to subrounded gravel; trace fine, subangular to subrounded gravel; 15% coarse, subangular to subrounded sand; 85% medium, subangular to subrounded sand; trace fine, subangular to subrounded sand; brown, dry, maximum size = 39mm

LITHOLOGIC DESCRIPTION - Piezometer No. 11 (cont.)


255- 270ft	<u>SANDY LEAN CLAY</u> (CL) : Trace fine, angular to subrounded gravel; trace coarse, angular to subrounded sand; 10% medium, angular to subrounded sand; 20% fine, subangular to subrounded sand; 70% fines; no dilatancy, medium toughness, medium plasticity, medium dry strength; brown, moist (due to injection of water during drilling)
270- 310ft	<u>CLAYEY SAND</u> (SC) : Trace fine, angular to subrounded gravel; 5% coarse, angular to subrounded sand; 30% medium, angular to subrounded sand; 35% fine, subangular to subrounded sand; 30% fines; no dilatancy, medium toughness, medium plasticity, medium dry strength; brown, moist (due to injection of water during drilling)
310- 345ft	<u>SANDY LEAN CLAY</u> (CL) : Trace fine, angular to subrounded gravel; trace coarse, angular to subrounded sand; 10% medium, subangular to subrounded sand; 30% fine, subangular to subrounded sand; 60% fines; no dilatancy, medium toughness, medium plasticity, medium dry strength; brown, moist (due to injection of water during drilling)
345- 365ft	<u>CLAYEY SAND</u> (SC) : Trace fine, angular to subangular gravel; 10% coarse, angular to subangular sand; 40% medium, angular to subrounded sand; 30% fine, subangular to subrounded sand; 20% fine; no dilatancy, medium toughness, medium plasticity, medium dry strength; brown, moist (due to injection of water during drilling)
365- 485ft	<u>POORLY GRADED SAND</u> (SP) : 5% fine, angular to subrounded gravel; 40% coarse, angular to subrounded sand; 55% medium, angular to subrounded sand; trace fine, subangular to subrounded sand; trace fines; brown, dry

APPENDIX A


LITHOLOGIC DESCRIPTION

Eagle Mountain Piezometer No. 12

- 0- 10ft POORLY GRADED SAND (SP) : 10% coarse, angular to subrounded gravel; 10% fine, angular to subrounded gravel; 45% coarse, angular to subrounded sand; 35% medium, angular to subrounded sand; trace fine sand; brown, dry, maximum size = 38mm
- 10 - 15ft POORLY GRADED GRAVEL WITH SAND (GP) : 25% coarse, angular to subrounded gravel; 35% fine, angular to subrounded gravel; 25% coarse, angular to subrounded sand; 15% medium, angular to subrounded sand; trace fine sand; brown, dry, maximum size = 40mm
- 15 - 30ft POORLY GRADED SAND WITH GRAVEL (SP) : 5% coarse, angular to subrounded gravel; 20% fine, angular to subrounded gravel; 40% coarse, angular to subrounded sand; 35% medium, angular to subrounded sand; trace fine sand; brown, dry, maximum size = 22mm
- 30 - 60ft POORLY GRADED GRAVEL WITH SAND (GP) : 30% coarse, angular to subrounded gravel; 35% fine, angular to subrounded gravel; 25% coarse, subangular to subrounded sand; 10% medium, subangular to subrounded sand; trace fine sand; brown, dry, maximum size = 31mm
- 60 - 115ft POORLY GRADED SAND WITH GRAVEL (SP) : 10% coarse, angular to subangular gravel; 20% fine, angular to subrounded gravel; 40% coarse, angular to subrounded sand; 30% medium, subangular to subrounded sand; trace fine sand; brown, dry, maximum size = 30mm
- 115 - 130ft ELASTIC SILT (ML) : 10% fine, subangular to subrounded sand; 90% fines; slow dilatancy, medium toughness, low plasticity, low dry strength; brown, dry
- 130- 155ft POORLY GRADED SAND (SP) : Trace coarse, subangular to subrounded gravel; 10% fine, angular to subrounded gravel; 35% coarse, angular to subrounded sand; 50% medium, subangular to subrounded sand; 5% fine, subangular to subrounded sand; brown, dry, maximum size = 32mm
- 155- 370ft POORLY GRADED SAND (SP) : Trace fine, subangular to subrounded gravel; trace coarse, subangular to subrounded sand; 60% medium, subangular to subrounded sand; 40% fine, subangular to subrounded sand; brown, dry
- 370- 500ft POORLY GRADED SAND (SP) : Trace fine, subangular to subrounded gravel; 20% coarse, subangular to subrounded sand; 70% medium, subangular to subrounded sand; 10% fine, subangular to rounded sand; trace to 5% fines; slow dilatancy, medium toughness, medium plasticity, low dry strength; brown, dry



Project Site / Dwg Size		NORTH OF EAST PIT		Start Date	4/22/92	Borehole Dia	3.55"	Ground Elevation	1557.2'	Borehole No.	CH-5
Coordinates / Stationing				Completion Date	4/05/92	Logged By		R. REYNOLDS, J. SUTHARD		Bottom of Borehole (sgt)	
Dwg. Rip Make and Metal		BOYLES 56		Drilling Method	CORE	Drilling Fluid	MUD	Top of Bedrock (sgt)		28'	
Drilling Contractor		TONTON DRILLING SERVICES, INC.		Split Case OD/ID/Depth	4 1/2" / 4" / 26'		Total Core Recovery %	Total Number of Core Boxes		20	
REMARKS		Well Data Drilling Data Personnel Changes		Test Site	ROD (ft)	Fractures / Tool Percut Core Penetration	Box Number	Elevation (ft)	Depth (ft)	Stratigraphic Log	Material Classification and Physical Description
<p>30' depth at 10:10 am, 4/22/92</p> <p>Geologist: R. Reynolds</p> <p>47' depth at 2:00 pm, 4/22/92</p> <p>57' depth at 3:45 pm, 4/22/92</p> <p>67' depth at 7:00 pm, 4/22/92</p> <p>77' depth at 8:45 pm, 4/22/92</p>		5 5/8" TRJ CORE								<p>0' - 28.0' CASING - NO CORE</p> <p>28.0' - 65.0' QUARTZITE</p> <p>Verged light to dark green-gray, fine-grained. Eucalyxene having 15-45 degrees to axis. Slightly to moderately fractured, fractures smooth, slightly open.</p> <p>65.0' - 74.0' QUARTZ SEYENITE</p> <p>Pink-gray, coarse-grained. Mostly K-feldspar, with minor interstitial quartz and pyroxene. Fractures hardy, slightly open, MnO₂ coating. Rock is massive, hard, strong.</p>	
		HQ	0	6	100	8	BO	X	30		
			0	6	100						
		3.85" HOLE	31	3	100	1					
		2.405" CORE	74	1	100	36.5'					
			62	1	100	2	BO	X	40		
			67	1	100	46.5'					
			57	2	100	3	BO	X	50		
			73	<1	100		BO	X	60		
			47	2	100	4					
	72	<1	100		BO	X	70				



DATE	7/92	The PRA Group, Inc CONSULTING ENGINEERS	
JOB NO.	G125-18		
DWG NO.	EM 1500L-1	BOREHOLE LOG	
DRAWN	R. HARRIS	CH-5	
CHECKED	D. MERT	EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY CALIFORNIA	
APP'D	D. AFFELDT	MINE RECLAMATION CORPORATION	

REMARKS Wear Code Drilling Data Personal Charge	Tool Size	ROD (ft)	Fractures per foot	Percent Core Recovery	Box Number	Liters (l)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
77' depth at 9:15 pm, 40492	HQ 3.85" HOLE 2.405" CORE	20	4	100	5	73.0'	70		550' - 74.0' QUARTZ SEVENTITE Pink-gray, coarse-grained. Mostly K-feldspar, with minor mineral quartz and pyroxene. Fractures fairly, slightly open. MnO ₂ coating. Rock is massive, hard, strong.
80' depth at 10:25 pm, 40292		32	3	100	6	82.0'	80		74.0' - 208.0' QUARTZITE Light to dark green, fine-grained, weak mica banding. Hard, strong, slightly to moderately fractured. Fractures mostly 45-50 and 70-90 degrees to axis, smooth, minor calcite fill.
Geologist: J. Suthard		27	6	100	7	90.0'			
90' depth at 3:13 am, 40392		45	2	100	8	99.0'			
100' depth at 6:12 am, 40392 Geologist: R. Reynolds Drilling down for repair		48	2	100	9	100.0'		100' - 107' shales of system to 1" common	
110' depth at 9:30 pm, 40392		25	4	100	10	108.5'			
120' depth at 10:25 am, 40392		46	1	100	11	118.0'			
130' depth at 2:00 am, 40492 Problems retrieving core barrel all night Geologist: R. Reynolds		60	1	100	12	127.0'		115' - 120' minor spindal cleaves	
140' depth at 2:00 pm, 40492		25	2	100	13	136.5'			
150' depth at 3:45 am, 40492		42	2	100	14	145.0'		130' - 135' fault zone, brecciated	
		48	2	100	15	153.0'			
		52	2	100	16	161.0'			
		30	4	100	17	169.0'			
		0	>5	20	18	177.0'			
	23	6	100	19	185.0'				
	98	<1	100	20	193.0'				
	67	1	100	21	201.0'				
				22	209.0'				
				23	217.0'				
				24	225.0'				
				25	233.0'				
				26	241.0'				
				27	249.0'				
				28	257.0'				
				29	265.0'				
				30	273.0'				
				31	281.0'				
				32	289.0'				
				33	297.0'				
				34	305.0'				
				35	313.0'				
				36	321.0'				
				37	329.0'				
				38	337.0'				
				39	345.0'				
				40	353.0'				
				41	361.0'				
				42	369.0'				
				43	377.0'				
				44	385.0'				
				45	393.0'				
				46	401.0'				
				47	409.0'				
				48	417.0'				
				49	425.0'				
				50	433.0'				
				51	441.0'				
				52	449.0'				
				53	457.0'				
				54	465.0'				
				55	473.0'				
				56	481.0'				
				57	489.0'				
				58	497.0'				
				59	505.0'				
				60	513.0'				
				61	521.0'				
				62	529.0'				
				63	537.0'				
				64	545.0'				
				65	553.0'				
				66	561.0'				
				67	569.0'				
				68	577.0'				
				69	585.0'				
				70	593.0'				
				71	601.0'				
				72	609.0'				
				73	617.0'				
				74	625.0'				
				75	633.0'				
				76	641.0'				
				77	649.0'				
				78	657.0'				
				79	665.0'				
				80	673.0'				
				81	681.0'				
				82	689.0'				
				83	697.0'				
				84	705.0'				
				85	713.0'				
				86	721.0'				
				87	729.0'				
				88	737.0'				
				89	745.0'				
				90	753.0'				
				91	761.0'				
				92	769.0'				
				93	777.0'				
				94	785.0'				
				95	793.0'				
				96	801.0'				
				97	809.0'				
				98	817.0'				
				99	825.0'				
				100	833.0'				
				101	841.0'				
				102	849.0'				
				103	857.0'				
				104	865.0'				
				105	873.0'				
				106	881.0'				
				107	889.0'				
				108	897.0'				
				109	905.0'				
				110	913.0'				
				111	921.0'				
				112	929.0'				
				113	937.0'				
				114	945.0'				
				115	953.0'				
				116	961.0'				
				117	969.0'				
				118	977.0'				
				119	985.0'				
				120	993.0'				
				121	1001.0'				
				122	1009.0'				
				123	1017.0'				
				124	1025.0'				
				125	1033.0'				
				126	1041.0'				
				127	1049.0'				
				128	1057.0'				
				129	1065.0'				
				130	1073.0'				
				131	1081.0'				
				132	1089.0'				
				133	1097.0'				
				134	1105.0'				
				135	1113.0'				
				136	1121.0'				
				137	1129.0'				
				138	1137.0'				
				139	1145.0'				
				140	1153.0'				
				141	1161.0'				
				142	1169.0'				
				143	1177.0'				
				144	1185.0'				
				145	1193.0'				
				146	1201.0'				
				147	1209.0'				
				148	1217.0'				
				149	1225.0'				
				150	1233.0'				
				151	1241.0'				
				152	1249.0'				
				153	1257.0'				
				154	1265.0'				
				155	1273.0'				
				156	1281.0'				
				157	1289.0'				
				158	1297.0'				
				159	1305.0'				
				160	1313.0'				
				161	1321.0'				
				162	1329.0'				
				163	1337.0'				
				164	1345.0'				
				165	1353.0'				
				166	1361.0'				
				167	1369.0'				
				168	1377.0'				
				169	1385.0'				
				170	1393.0'				
				171	1401.0'				
				172	1409.0'				
				173	1417.0'				
				174	1425.0'				
				175	1433.0'				
				176	1441.0'				
				177	1449.0'				
				178	1457.0'				
				179	1465.0'				
				180	1473.0'				
				181	1481.0'				
				182	1489.0'				
				183	1497.0'				
				184	1505.0'				
				185	1513.0'				
				186	1521.0'				
				187	1529.0'				
				188	1537.0'				
				189	1545.0'				
				190	1553.0'				
				191	1561.0'				

Project Site / Dwell Site	NORTH OF EAST PT	Spore Date	04/03/92	Borehole Dia	3.25"	Ground Elevation	1657.20'	Borehole No	CH-5A
Coordinates / Stationing		Completion Date	04/28/92	Logged By	R. REYNOLDS, J. SUTKARD	Bottom of Borehole (Depth)	900'		
Drill Rig Make and Model	BOYLES 56	Drilling Method	CORE	Drilling Fluid	MUD	Top of Borehole (Depth)	14'	First Encounter	825'
Drilling Contractor	TANTO DRILLING SERVICES, INC.	Start Csg Coring Depth	4 1/2" / 1' / 13'	Total Core Recovery %		Total Number of Core Boxes	25	Static Water Level (Depth)	

REMARKS: Hole Data Drilling Data Personal Changes	Test Site	REID (%)	Fractures / foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Stratigraphic Log	Material Classification and Physical Description
	5.55" Tin Core							0' - 13.0' CASING NO CORE	
27' depth at 2:20 a.m. on 04/05/92.	HQ 3.25" Hole 2,406' Core	75	<1	100	X O B	75.5'	27'	13.0' - 34.5' QUARTZ MONZONITE. Porphyritic, pink gray, medium to coarse grained. K-feldspar phenocrysts to 3 mm, abundant biotite. Mostly hard, strong; slightly to highly fractured. Fractures variable.	
30' depth at 3:11 a.m. on 04/05/92.		38	3	100	1	22.0'	30'	15.0' - 25.5' fractures 10 and 20 degrees to axis. Slightly open, minor calcite fill.	
30' depth at 3:11 a.m. on 04/05/92.		77	1	100	X O B	22.0'	30'	25.5' - 60.5' fractures 30, 60, and 90 degrees to axis. Slightly open, very minor calcite.	
40' depth at 4:17 a.m. on 04/05/92.		23	3	92	2	31.5'	40'		
40' depth at 4:17 a.m. on 04/05/92.		80	1	100	X O B	31.5'	40'		
50' depth at 5:24 a.m. on 04/05/92.		72	1	100	3	40.5'	50'		
50' depth at 5:24 a.m. on 04/05/92.		73	1	100	X O B	40.5'	50'		
50' depth at 5:24 a.m. on 04/05/92.		68	3	88	4	51.2'	50'		
50' depth at 5:24 a.m. on 04/05/92.		12	4	100	X O B	51.2'	50'		
50' depth at 5:24 a.m. on 04/05/92.		55	<1	100	5	61.5'	50'		
50' depth at 5:24 a.m. on 04/05/92.		0	>5	48	X O B	61.5'	50'		
50' depth at 5:24 a.m. on 04/05/92.		0	>5	28	6	61.5'	50'		
70' depth at 10:02 a.m. on 04/05/92.					6		70'	80.5' - 73.2' fractures horizontal, clay coating.	

	DATE	06/92	
	JOB NO.	G125-19	
	DRAWN	N TOOR	BOREHOLE LOG CH-5A EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION
	CHECKED	R HARRIS	
	APPROVED	D AFFELDT	

REMARKS Hole Data Drilling Data Personal Changes	Test Site	REID (%)	Fractures / foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Stratigraphic Log	Material Classification and Physical Description
80.0' depth at 11:35 a.m. on 04/05/92.	HQ 3.25" Hole 2,406' Core	10	>5	42	X O B	75.5'	70'	13.0' - 34.5' QUARTZ MONZONITE. Porphyritic, pink gray, medium to coarse grained. K-feldspar phenocrysts to 3 mm, abundant biotite. Mostly hard, strong; slightly to highly fractured. Fractures variable.	
80.0' depth at 11:35 a.m. on 04/05/92.		82	<1	100	75.5'	80'	73.2' - 140.0' few fractures, 60 - 70 degrees to axis, weak chrome coating.		
80.0' depth at 11:35 a.m. on 04/05/92.		72	5	100	X O B	75.5'	80'		
80.0' depth at 11:35 a.m. on 04/05/92.		92	<1	60	7	85.0'	80'		
80.0' depth at 11:35 a.m. on 04/05/92.		88	<1	100	X O B	85.0'	80'		
80.0' depth at 11:35 a.m. on 04/05/92.		74	<1	80	8	85.5'	80'		
80.0' depth at 11:35 a.m. on 04/05/92.		71	1	100	X O B	85.5'	80'		
100.0' depth at 5:15 p.m. on 04/05/92.		100	0	87	9	105.0'	100'		
100.0' depth at 5:15 p.m. on 04/05/92.		72	1	100	X O B	105.0'	100'		
110.0' depth at 6:45 p.m. on 04/05/92.		65	<1	100	10	115.0'	110'		
110.0' depth at 6:45 p.m. on 04/05/92.		87	<1	100	X O B	115.0'	110'		
110.0' depth at 6:45 p.m. on 04/05/92.		66	1	100	11	124.0'	110'		
120.0' depth at 6:40 p.m. on 04/05/92.		80	<1	100	X O B	124.0'	120'		
120.0' depth at 6:40 p.m. on 04/05/92.		87	<1	100	12	132.5'	120'		
120.0' depth at 6:40 p.m. on 04/05/92.		85	<1	100	X O B	132.5'	120'		
120.0' depth at 6:40 p.m. on 04/05/92.		57	2	100	13	141.0'	120'		
120.0' depth at 6:40 p.m. on 04/05/92.		52	2	100	X O B	141.0'	120'		
140.0' depth at 12:25 a.m. on 04/10/92.					14		140'	140.0' - 155.0' slightly fractured, 10, 60, and 80 degrees to axis, calcite coatings.	
150.0' depth at 04/10/92.					15		150'		

	DATE	07/92	
	JOB NO.	G125-19	
	DRAWN	N TOOR	BOREHOLE LOG CH-5A EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION
	CHECKED	R HARRIS	
	APPROVED	D AFFELDT	

REMARKS Hole Data Passive Charge	Tool Size	RQD (%)	Fractures / Foot	Percent Core Recovery	Bar Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
160.0' depth at 1:00 p.m. on 04/10/92.	HC 3.85" Hole 2.405" Core	85	1	100	X O B	150	150	13.0' - 349.5' QUARTZ MONZONITE	Porphyratic, pink gray, medium to coarse grained. K-feldspar phenocrysts to 3 cm, abundant biotite. Mostly hard, strong; slightly to highly fractured, fractures variable.
		0	—	0	X O B	15	150	160.0' - 170.0' highly fractured, MnO ₂ -stained sandy fracture filling, fractures 10 degrees to axis.	
		20	4	25	X O B	154.5'	150		
		73	<1	100	X O B	15	170	170.0' - 194.5' moderately to highly fractured, fractures 70 - 90 degrees to axis, calcite fill.	
		27	1	90	X O B	174.0'	170		
		33	2	75	X O B	17	180		
		83	5	75	X O B	17	180		
		35	3	100	X O B	17	185.0'		
		31	3	85	X O B	18	190		
		9	3	75	X O B	18	195.5'		
		47	2	90	X O B	19	200	194.5' - 234.5' fractures 10-45, 60, and 80 degrees to axis, minor calcite, rare gypsum fill	
		28	5	92	X O B	19	204.5'		
22	4	55	X O B	20	210				
27	>5	92	X O B	20	212.5'				
0	4	68	X O B	21	220				
22	4	100	X O B	21	223.0'				
20	5	100	X O B	22	230				



DATE 07/92
JOB NO. G125-19
DWS NO. EM19005-3
DRAWN N TOOR
CHECKED R HARRIS
APPROVED D AFFELDT

The PRA Group, Inc
CONSULTING ENGINEERS
BOREHOLE LOG
CH-5A
EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
MINE RECLAMATION CORPORATION

2 of 12

REMARKS Hole Data Passive Charge	Tool Size	RQD (%)	Fractures / Foot	Percent Core Recovery	Bar Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
240.0' depth at 12:30 p.m. on 04/11/92.	HC 3.55" Hole 2.405" Core	41	3	100	X O B	241.5'	230	13.0' - 349.5' QUARTZ MONZONITE	Porphyratic, pink gray, medium to coarse grained. K-feldspar phenocrysts to 3 cm, abundant biotite. Mostly hard, strong; slightly to highly fractured, fractures variable.
		10	4	100	X O B	23	240	234.5' - 243.0' fractures 10 - 40 degrees to axis; clay, calcite coating; weak discontinuities at 238'.	
		0	4	100	X O B	23	240	243.0' - 250.0' fractures 40 and 70-90 degrees to axis, slightly open, no fill	
		0	10	60	X O B	24	250		
		0	10	50	X O B	24	250		
		30	2	100	X O B	25	251.0'		
		0	—	0	X O B	25	251.0'		
		57	3	100	X O B	25	259.5'		
		0	>5	100	X O B	25	260	250.0' - 260.5' fractures 10-30 and 70-90 degrees to axis, irregular, clay and calcite fill	
		17	3	100	X O B	25	270		
		9	3	48	X O B	25	270		
		11	>5	62	X O B	26	274.0'		
0	>5	80	X O B	26	274.0'				
11	3	100	X O B	27	280				
56	2	100	X O B	27	283.0'				
50	3	100	X O B	28	290				
37	3	100	X O B	28	293.0'				
38	2	100	X O B	28	300				
38	2	100	X O B	28	301.5'				
52	1	100	X O B	29	310				



DATE 07/92
JOB NO. G125-19
DWS NO. EM19005-4
DRAWN N TOOR
CHECKED R HARRIS
APPROVED D AFFELDT

The PRA Group, Inc
CONSULTING ENGINEERS
BOREHOLE LOG
CH-5A
EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
MINE RECLAMATION CORPORATION

PAGE NO
2 of 12


REMARKS Hour Date Drilling Date Pressure Changes	Tool Size	RQD (%)	Fractures / Foot	Percent Core Recovery	Box Number	Elevation (F)	Depth (F)	Lithologic Log	Material Classification and Physical Description
320.0' depth at 5:50 p.m. on 04/15/92 330.0' depth at 9:50 p.m. on 04/15/92 340.0' depth at 12:20 a.m. on 04/15/92 350.0' depth at 4:00 a.m. on 04/15/92 360.0' depth at 2:00 p.m. on 04/15/92 370.0' depth at 3:30 a.m. on 04/15/92 380.0' depth at 6:10 a.m. on 04/15/92 390.0' depth at 8:30 a.m. on 04/15/92	HD 3.25" Hole 2.405" Core	42	2	100	X O m	310.5'	310	315.0' - 349.5' QUARTZ MONZONITE Porphyritic, pink gray, medium to coarse grained K-feldspar phenocrysts to 3 cm, abundant biotite. Massy hard, strong, slightly to highly fractured, orientation variable. 309.5' - 324.5' fractures 40 and 70 degrees to axis, semi-smooth to hacky, slightly open. 324.5' - 368.0' fractures 10, 40, and 70 degrees to axis, smooth to hacky, minor calca 10. 349.5' - 368.0' HORNfels Medium gray, fine grained, equigranular, alternating bands of biotite-amphibole-muscovite and quartz-feldspar. Hard, strong. 368.0' - 395.0' QUARTZITE White to medium gray, zones and slots of K-feldspar and epidote-diopside. Fractures 15-40 and 50-90 degrees to axis, calca 11. Very hard, strong.	
	30	2	100	X O m	311.5'	311			
	48	2	100	X O m	319.5'	319			
	21	2	75	X O m	329.0'	329			
	8	>5	75	X O m	329.0'	329			
	0	>5	80	X O m	335	335			
	22	4	60	X O m	339.5'	339			
	70	2	100	X O m	343.5'	343			
	52	2	100	X O m	349.5'	349			
	23	4	100	B O X	357.5'	357			
	13	>10	95	B O X	357.5'	357			
	0	>10	75	B O X	363.0'	363			
	0	>10	80	B O X	363.0'	363			
	53	<1	100	B O X	377.5'	377			
	95	<1	100	B O X	377.5'	377			
	91	<1	100	B O X	385.5'	385			
	88	<1	100	BOX	385.5'	385			

	DATE 07/92	The PRA Group, Inc CONSULTING ENGINEERS BOREHOLE LOG CH-5A EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	PAGE NO 5 of 12
	JOB NO. G125-19		
	DRAWN BY EM19005-S		
	CHECKED BY N TCOR		
	APP'D BY R HARRIS		
DATE 07/92	DATE 07/92		
JOB NO. G125-19	JOB NO. G125-19		
DRAWN BY EM19005-S	DRAWN BY EM19005-S		
CHECKED BY N TCOR	CHECKED BY N TCOR		
APP'D BY R HARRIS	APP'D BY R HARRIS		
DATE 07/92	DATE 07/92		
JOB NO. G125-19	JOB NO. G125-19		
DRAWN BY EM19005-S	DRAWN BY EM19005-S		
CHECKED BY N TCOR	CHECKED BY N TCOR		
APP'D BY R HARRIS	APP'D BY R HARRIS		

REMARKS Hour Date Drilling Date Pressure Changes	Tool Size	RQD (%)	Fractures / Foot	Percent Core Recovery	Box Number	Elevation (F)	Depth (F)	Lithologic Log	Material Classification and Physical Description
400.0' depth at 12:01 p.m. on 04/15/92 410.0' depth at 12:10 a.m. on 04/15/92 420.0' depth at 4:20 a.m. on 04/15/92 430.0' depth at 7:52 a.m. on 04/15/92 440.0' depth at 1:10 p.m. on 04/15/92 450.0' depth at 4:40 p.m. on 04/15/92 460.0' depth at 1:22 a.m. on 04/15/92 470.0' depth at 8:30 a.m. on 04/15/92	HD 3.25" Hole 2.405" Core	27	3	100	33	390	368.0' - 395.0' QUARTZITE White to medium gray, zones and slots of K-feldspar and epidote-diopside. Fractures 15-40 and 50-90 degrees to axis, calca 11. Very hard, strong. 395.0' - 434.0' HORNfels Gray to green gray, fine grained, bands of biotite and feldspar. Fractures variable orientation, semi-smooth, slightly open, minor calca 11. 434.0' - 632.0' GRANOFELS / GRANULITE Medium gray, medium to coarse grained, equigranular. Appears to be a plastic mixture of quartz monzonite and recrystallized metasediments. Hard, medium strong. Common quartz-feldspar cleavages to 0'. 434.0' - 470.0' fractures variable, slightly open semi-smooth, minor calca 11.		
	27	3	100	33	390				
	27	2	100	X O m	395.0'	395			
	13	>10	80	X O m	404.5'	404			
	30	2	100	X O m	404.5'	404			
	20	5	100	X O m	413.0'	413			
	33	4	100	X O m	413.0'	413			
	62	2	96	X O m	421.0'	421			
	50	3	92	B O X	421.0'	421			
	0	>5	75	B O X	431.0'	431			
	0	5	100	B O X	439.5'	439			
	23	75	100	B O X	439.5'	439			
	36	3	100	B O X	447.5'	447			
	0	>10	100	B O X	447.5'	447			
	37	>10	100	B O X	457.0'	457			
	50	1	100	B O X	457.0'	457			
	8	2	65	B O X	466.0'	466			
	0	>5	75	B O X	466.0'	466			
37	3	90	BOX	466.0'	466				
21	3	65	BOX	466.0'	466				

	DATE 07/92	The PRA Group, Inc CONSULTING ENGINEERS BOREHOLE LOG CH-5A EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	PAGE NO 5 of 12
	JOB NO. G125-19		
	DRAWN BY EM19005-S		
	CHECKED BY N TCOR		
	APP'D BY R HARRIS		
DATE 07/92	DATE 07/92		
JOB NO. G125-19	JOB NO. G125-19		
DRAWN BY EM19005-S	DRAWN BY EM19005-S		
CHECKED BY N TCOR	CHECKED BY N TCOR		
APP'D BY R HARRIS	APP'D BY R HARRIS		

REMARKS Weather Data Drilling Data Personnel Changes	Tool Size	RQD (%)	Fractures / Foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
480' depth at 12:50 p.m. on 04/16/92. Broken catch housing on drill rig. 480' depth at 12:20 a.m. on 04/17/92. 500' depth at 3:50 a.m. on 04/17/92. 510' depth at 5:40 a.m. on 04/17/92. 520' depth at 6:30 p.m. on 04/17/92. 530' depth at 10:30 p.m. on 04/17/92. 540' depth at 12:55 a.m. on 04/18/92. 550' depth at 2:00 a.m. on 04/18/92.	HQ 3.85" Hole 2.406" Core	21	3	100	BOX 48	470	634.0'	632.5' GRANOFELS / GRANULITE	Medium gray, medium to coarse grained, equigranular. Appears to be a plastic mixture of quartz, microcline and recrystallized metasediments. Hard, medium strong. Common quartz-feldspar cleaves to 6". 470' - 530' fractures variable orientation, semi-smooth to hacky, slightly open, minor calcite fill.
		28	>10	100	1475.5'		480		
		50	<1	100	X-Box				
		100	0	100	48				
		22	>10	50	484.5'				
		28	3	100	X-Box				
		8	3	100	50				
		32	3	100	493.5'				
		0	3	100	51				
		15	2	100	502.5'				
		18	6	100	52				
		39	1	100	511.0'				
		57	<1	100	512.5'				
		8	>10	60	54				
		0	>10	80	529.0'				
		0	>5	35	55				
		22	>5	70	539.5'				
0	>5	40	56						
0	4	90	56						
17	>5	100	548.0'						



The PRA Group, Inc.
 CONSULTING ENGINEERS
BOREHOLE LOG
CH-5A
 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
 MINE RECLAMATION CORPORATION

REMARKS Weather Data Drilling Data Personnel Changes	Tool Size	RQD (%)	Fractures / Foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
560' depth at 9:45 a.m. on 04/18/92. 570' depth at 9:30 p.m. on 04/18/92. Rig down for catch adjustment. 580' depth at 1:22 p.m. on 04/19/92. Rig down for catch repair. 590' depth at 4:46 a.m. on 04/22/92. 600' depth at 9:30 a.m. on 04/22/92. 605' drilling stopped to run packer tests on HQ hole; reduced to NQ hole, resumed 5:17 a.m. 4/25/92. 610' depth at 11:50 a.m. on 04/25/92. 620' depth at 12:55 p.m. on 04/25/92. 630' depth at 2:10 p.m. on 04/25/92.	HQ 3.85" Hole 2.406" Core	12	>5	90	BOX 57	550	634.0'	632.5' GRANOFELS / GRANULITE	Medium gray, medium to coarse grained, equigranular. Appears to be a plastic mixture of quartz, microcline and recrystallized metasediments. Hard, medium strong. Common quartz-feldspar cleaves to 6". 530' - 580' fractures pattern random, fractures slightly open, semi-smooth, with minor clay, FeOx, and calcite fill. 605' - 630.5' fractures 10-20 and 40-70 degrees to axis, semi-smooth to hacky, slightly open, clay and calcite fill.
		0	>5	100	57		550		
		0	>5	100	57.0'				
		100	4	100	BOX 58				
		26	2	100	565.5'				
		15	2	54	BOX 59				
		6	4	100	575.5'				
		7	4	88	BOX 60				
		7	>5	78	60				
		17	>5	62	585.0'				
		0	>5	45	61				
		0	>5	100	597.5'				
		0	>10	100	BOX 62				
		0	>10	100	605.0'				
		0	—	37	BOX 63				
		0	5	100	63				
		0	6	100	63				
		11	6	65	616.5'				
		23	8	100	BOX 64				
		13	4	100	525.5'				
7	6	100	BOX 65						



The PRA Group, Inc.
 CONSULTING ENGINEERS
BOREHOLE LOG
CH-5A
 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
 MINE RECLAMATION CORPORATION

REMARKS Water Gas Drilling Gas Pressure Changes	Tool Size	RWD (%)	Fractures / lost Percent Core Recovery	Box Number	Elevation (F)	Depth (F)	Lithologic Log	Material Classification and Physical Description
790.0' depth at 2:10 p.m. on 04/27/92	NO 2.56" Hole 1.775" Core	0	5	95	81	790	<p>867.0' - 843.0' QUARTZITE Medium to dark gray, fine to medium grained, weakly bedded. Common quartz monzonite cleaves. Mostly hard, strong, highly fractured. Fractures variable orientation, slightly open, weak clay and calcite cement.</p> <p>827.0' - 838.0' abundant quartz monzonite, strongly stained to clay, with siderite 10 segments to test</p> <p>843.0' - 864.0' QUARTZ MONZONITE Strongly clay-stained and bleached, abundant beams (>20%). Moderately hard, moderately strong, highly fractured. Clay and calcite fracturing slight.</p> <p>864.0' - 870.0' HORNFELS Medium to dark gray, fine grained, equigranular. Siderite 30-40%, weakly bedded. Fractures 10-10 degrees to axis, irregular, weak clay ss, weak FeOx stain.</p>	
800.0' depth at 8:00 p.m. on 04/27/92		10	>10	100	X O B	82		
810.0' depth at 12:58 a.m. on 04/28/92		0	>10	80	X O B	83		
820.0' depth at 2:29 a.m. on 04/28/92		14	5	90	X O B	84		
830.0' depth at 5:09 a.m. on 04/28/92		27	3	100	X O B	85		
840.0' depth at 8:35 a.m. on 04/28/92		30	>5	92	X O B	86		
850.0' depth at 5:25 a.m. on 04/28/92		0	>5	50	X O B	87		
860.0' depth at 11:20 a.m. on 04/28/92		0	5	96	B X O X	88		
870.0' depth at 12:55 p.m. on 04/28/92		42	2	100	X O B	89		
880.0' depth at 2:30 p.m. on 04/28/92		10	>10	100	X O B	90		
890.0' depth at 4:05 p.m. on 04/28/92		11	>10	75	B X O X	91		
900.0' total depth at 5:50 p.m. on 04/28/92		13	4	100	B X O X	92		
	28	4	100	B X O X	93			
	31	1	100	B X O B	94			
	48	5	100	B X O B	95			
	7	>10	100	B X O B	96			
	13	>10	100	B X O B	97			
	52	2	95	B X O B	98			




DATE	07/92
JOB NO.	G125-19
DWG NO.	EM19005/11
EXAMINER	K. HOCHSTATTER
CLIENT	R. HARRIS
APPROVED	D. AFFELDT

The PRA Group, Inc
CONSULTING ENGINEERS

BOREHOLE LOG
CH-5A
EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
MINE RECLAMATION CORPORATION

REMARKS Water Gas Drilling Gas Pressure Changes	Tool Size	RWD (%)	Fractures / lost Percent Core Recovery	Box Number	Elevation (F)	Depth (F)	Lithologic Log	Material Classification and Physical Description
870.0' depth at 12:55 p.m. on 04/28/92	NO 2.56" Hole 1.775" Core	52	2	95	81	870	<p>870.0' - 900.0' QUARTZ MONZONITE Intensely clay-stained, weakly to strongly bleached. Abundant hornfels inclusions. Moderately hard, moderately strong, highly fractured to brecciated. Fractures variable, clay and calcite ss.</p> <p>880.0' - 883.0' fault breccia: quartzite and quartz monzonite clasts in matrix of calcite-dominated clay</p> <p>885.0' - 890.0' fault breccia, strong calcite cement</p> <p>895.0' - 900.0' fault breccia, clay-rich matrix</p> <p>TOTAL DEPTH 900'</p>	
880.0' depth at 2:30 p.m. on 04/28/92		32	6	100	X O B	880		
890.0' depth at 4:05 p.m. on 04/28/92		7	>10	100	X O B	885		
900.0' total depth at 5:50 p.m. on 04/28/92		58	4	100	B X O X	890		
		22	>10	100	B X O X	895		
		0	>10	100	B X O X	900		
					B X O X	905		
					B X O X	910		
					B X O X	915		
					B X O X	920		
					B X O X	925		
					B X O X	930		



DATE	07/92
JOB NO.	G125-19
DWG NO.	EM19005/12
EXAMINER	K. HOCHSTATTER
CLIENT	R. HARRIS
APPROVED	D. AFFELDT

The PRA Group, Inc
CONSULTING ENGINEERS

BOREHOLE LOG
CH-5A
EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
MINE RECLAMATION CORPORATION

REMARKS Water Data Drilling Data Rebar Changes	Tool Size	RQD (%)	Fractures / foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
530.0' depth at 2:10 p.m. on 04/25/92.	NC 2.58" Hole 1.775" Core	7	6	100	63X 65	630.0'	630		634.0' - 632.5' GRANITE / GRANULITE Medium gray, medium to coarse grained, equigranular. Appears to be a plastic mixture of quartz monzonite and recrystallized metabasalts. Hard, medium strong.
		0	5	100	X O X				
640.0' depth at 3:30 p.m. on 04/25/92.		0	6	100	66	640.0'	640		632.5' - 644.0' HORNFELS Light to medium gray, fine grained, equigranular. Biotite 20%, weakly lobate, sheets of quartz. Bedrock. Hard, strong, highly fractured. Fractures 20, 40, and 70 degrees to axis, slightly open, minor calcite.
		0	5	100	64Z O'				
550.0' depth at 4:57 p.m. on 04/25/92.		13	6	80	67	650.0'	650		644.0' - 653.5' QUARTZITE Pinkish gray, fine to medium gray, weakly lobate. Abundant bedrock, minor biotite. Hard, strong, highly fractured. Fractures 40 and 70 degrees to axis, slightly open, weak clay and minor calcite.
		33	4	100	B X O X				
660.0' depth at 6:20 p.m. on 04/25/92.		0	6	100	68	660.0'	660		653.5' - 667.0' HORNFELS Pinkish gray, fine grained, lobate. Strongly cemented with pink quartz monzonite. Hard, strong, highly fractured. Fractures 20 and 50-70 degrees to axis, slightly open, weak clay and calcite cement.
		15	>5	100	B X O X				
670.0' depth at 8:55 p.m. on 04/25/92.		0	>10	80	69	670.0'	670		667.0' - 667.0' HORNFELS Pinkish gray, fine grained, lobate. Strongly cemented with pink quartz monzonite. Hard, strong, highly fractured. Fractures 20 and 50-70 degrees to axis, slightly open, weak clay and calcite cement.
		25	>10	100	B X O X				
680.0' depth at 11:30 p.m. on 04/25/92.		0	>10	80	70	680.0'	680		667.0' - 642' QUARTZITE Medium to dark gray, fine to medium grained, weakly bedded. Common quartz monzonite clasts. Mostly hard, strong, highly fractured. Fractures variable orientation, slightly open, weak clay and calcite cement.
		13	6	100	B X O X				
690.0' depth at 1:30 p.m. on 04/25/92.		0	>10	100	71	690.0'	690		
		0	5	80	B X O X				
690.0' depth at 6:30 a.m. on 04/25/92.		40	1	67	72	700.0'	700		
		0	>5	100	B X O X				
700.0' depth at 12:01 p.m. on 04/25/92.		28	4	100	72	710.0'	710		
		25	>5	100	B X O X				
710.0' depth at 3:15 p.m. on 04/25/92.		24	>2	65	73				
		13	5	100	B X O X				

	DATE 07/92		The PRA Group, Inc CONSULTING ENGINEERS
	JOB NO. G125-19		
	DRAWN NO. EM19005/9		The PRA Group, Inc CONSULTING ENGINEERS
	DRAWN K HOCHSTATTER		
	CHECKED R HARRIS		The PRA Group, Inc CONSULTING ENGINEERS
	APPROVED D AFFELDT		

REMARKS Water Data Drilling Data Rebar Changes	Tool Size	RQD (%)	Fractures / foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
710.0' depth at 3:15 p.m. on 04/25/92.	NC 2.58" Hole 1.775" Core	13	5	100	74	710.0'	710		667.0' - 842' QUARTZITE Medium to dark gray, fine to medium grained, weakly bedded. Common quartz monzonite clasts. Mostly hard, strong, highly fractured. Fractures variable orientation, slightly open, weak clay and calcite cement.
		0	>10	100	X O X				
720.0' depth at 5:05 p.m. on 04/25/92.		27	1	50	74	720.0'	720		718.0' - 719.0' bent gouge, light gray clay with fragments of quartzite.
		0	1	85	74				
730.0' depth at 10:30 p.m. on 04/25/92.		13	>10	65	75	730.0'	730		
		0	>10	50	B O X				
740.0' depth at 1:05 a.m. on 04/27/92.		17	>5	100	75	740.0'	740		
		0	5	80	B O X				
750.0' depth at 3:00 a.m. on 04/27/92.		28	5	84	76	750.0'	750		
		27	5	92	B O X				
760.0' depth at 5:40 a.m. on 04/27/92.		0	6	66	77	760.0'	760		
		13	6	60	B O X				
770.0' depth at 7:30 a.m. on 04/27/92.		23	5	94	78	770.0'	770		
		8	5	90	B O X				
780.0' depth at 12:05 p.m. on 04/27/92.		33	3	100	79	780.0'	780		
		0	>10	100	B O X				
790.0' depth at 3:15 p.m. on 04/27/92.		0	>10	100	80	790.0'	790		
		0	>10	100	B O X				
		0	>10	100	81				
		0	>10	85	B O X				
		0	>10	100	82				
		0	>10	100	B O X				

	DATE 07/92		The PRA Group, Inc CONSULTING ENGINEERS
	JOB NO. G125-19		
	DRAWN NO. EM19005/10		The PRA Group, Inc CONSULTING ENGINEERS
	DRAWN K HOCHSTATTER		
	CHECKED R HARRIS		The PRA Group, Inc CONSULTING ENGINEERS
	APPROVED D AFFELDT		

Project Site / Grid Site		SECT	SECT DATE	SECTANCE C/D	GROUND ELEVATION	SECTANCE NO.
CENTRAL PIT		02/13/92	02/13/92	185 INCHES	2307.76 FEET	CH-10
Coordinates / Stationing		Completion Date	Logged By	Bottom of Section (top)		
		02/26/92	R. HARRIS, R. USREY J. SUTHARD, D. VOLTURNO	1389 feet		
Drill Rig Make and Model		Drilling Method	Drilling Fluid	First Encountered Water Log		
BOYLES 56-6		CORE	MUD	SURFACE		
Drilling Contractor		SECT C/D	Total Core Recovery %	Total Number of Core Boxes	Static Water Level (top)	
TANTO DRILLING SERVICES, INC.		6" / 5.5" / 17"	>50%	161	1309 feet	

REMARKS: Water Core Drilling Data Personnel Changes	Test Size	ROD (N)	Feet per Log	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
FOREMAN: WAYNE BEAUPRE DRILL CREW: (7am-7am) Driver: Shawn Arzani Helmer: Eric Owens John Cross DRILL CREW: (7pm-7am) Driver: Jeff Foley Helmer: Ed Karson Brad Williams Geologist: D. Volturno Casing set at 7.0 feet Began coring at 4:30 pm on 02/13/92 Geologist: R. Harris Stopped drilling at 17' - problems receiving core. Replaced casing to 17' 21.5' depth at 11:40 am, 2/13/92 Driver noted that hole made minor amount of wash	5.25"	17"	1	1	1				0.0 - 7.0' SET CASING No sample taken
	3.35"	HQ	1	>10	43		10		7.0' - 15.4' QUARTZITE Light gray, fine-grained, sandy weathered
	2.40"	2.40"	1	>10	90		20		15.4' - 59.0' IRON ORE Dark brown, highly fractured very hard. Minor mica.
			1	1	1		20		23.5' Ore with irregular inclusions of light colored minerals (not calcite)
			90	1	98		27.8'		
			90	1	100		30		
			47	1	74		30		
			82	>10	80		40		
			39	4	65		50		
			0	5	80		50		
			0	>10	1		50		
			19	>10	65		56.0'		
			19	>10	75		60		
			13	4	84		60		59.0' - 66.3' IRON ORE BRECCIA Light rust colored fragments (20%) in ore matrix (70%). Fragments up to 1" Fractures dipping 20-60 degrees
			46	3	86		65.0'		66.3' - 67.8' DORITE ORE Medium green, medium coarse-grained with orthoclase phenocrysts. Fractures with slickensides Contact highly altered to chlorite
			43	3	96		70		

DATE: 3/92	FIGURE NO.
JOB NO.: Q125-19	
DWG NO.: EM 10005-1	
DRAWN: R. HARRIS	
CHECKED: D. MERIT	
APPROVED: D. AFFELDT	

The PRA Group, Inc CONSULTING ENGINEERS	
BOREHOLE LOG CH-10	
EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA	
MINE RECLAMATION CORPORATION	

REMARKS: Water Core Drilling Data Personnel Changes	Tool Size	ROD (N)	Feet per Log	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
Geologic D. Volturno 120' depth at 4:55 pm, 2/14/92 130' depth at 5:55 pm, 2/14/92 147' depth at 6:43 pm, 2/14/92	HQ	40	3	96		70		59.5' - 73.5' ORE BRECCIA Light rust colored fragments in ore, with weathered chunks of iron-stained quartz 76.0' to 76.5' highly fractured, with clay gouge	
	2.40"	47	2	84		80		73.5' - 92.5' DORITE Gray, fine-grained matrix. Hard, strong, healed fractures	
		85	<1	100		83.0'	80		Weak zone with healed fractures
		92	2	100			90		
		17	3	100		92.5'	90		
		50	4	100			100		92.5' - 119.5' PORPHYRY ORE Green, aphanitic. Fine-grained subophitic phenocrysts. 2 - 5% silting to chlorite. Limonite stain in fractures. Hard. Most fractures dipping 20 - 50 degrees.
		0	>10	100		10	100		
		25	5	100		102.0'	100		
		50	3	100			110		highly altered zone - dark green epidote and chlorite
		47	4	100		110.5'	110		brecciated, traces of calcite in veins
		13	6	100		12	120		
		46	3	100			130		119.5' - 129.2' ORE BRECCIA Tan to light green angular fragments, 45-50% fragments 1-6mm in black ore matrix. Fractures dip 20-60 degrees. Very hard, very strong. Apertures light, some limonite staining
		69	3	100		13	130		129.2' - 133.0' SQUARN ZONE Increasing green alteration. Fractures with iron to moderate hard fill.
		54	4	100			140		133.0' - 138.0' DORITE PORPHYRY ORE Gray, with limonite phenocrysts (60%). Fractures do not silt. Healed fractures with ore filling
		25	4	100		137.8'	140		138.0' - 142.7' SQUARN ZONE Green alteration, iron to moderate hard
		37	5	100		15	140		142.7' - 155.0' ORE BRECCIA Tan to light gray angular fragments 40-50% fragments 1-6mm in black ore matrix Magnesian hematite matrix, with weathered green alteration zones. Fractures light, dipping 20-60 degrees Slightly hard, moderately strong
	46	3	95		16	150			

DATE: 3/92	FIGURE NO.
JOB NO.: Q125-19	
DWG NO.: EM 10005-2	
DRAWN: R. HARRIS	
CHECKED: D. MERIT	
APPROVED: D. AFFELDT	

The PRA Group, Inc CONSULTING ENGINEERS	
BOREHOLE LOG CH-10	
EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA	
MINE RECLAMATION CORPORATION	

REMARKS Hole Dia Drilling Date Proximal Charge	Tool Size	ROD [ft]	Feet/rod per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
155' depth at 10:00 pm, 2/15/92 Geologist J. Sutherland 170' depth at 11:30 pm, 2/14/92 187' depth at 1:00 am, 2/15/92 197' depth at 2:07 am, 2/15/92 207' depth at 4:16 am, 2/15/92 217' depth at 5:18 am, 2/15/92 227' depth at 6:27 am, 2/15/92	HQ	32	5	100	BOX 16	155.2	150		140.2' - 155.0' IRON ORE BRECCIA: Tan to light green, angular fragments. 40-50 to fragments 1-6 cm in black ore matrix. Fragments dip 20-60 degrees. Slightly hard, moderate strength.
	3.850" HOLE	18	8	100	BOX 17	156.2	160		155.0' - 157.0' IRON ORE: Rust black, highly fractured, nearly vertical to horizontal stained sil. not iron-bearing.
	2.400" CORE	42	6	100	BOX 17	157.7	160		157.0' - 164.9' QUARTZITE: Light green, very fine-grained. Steeply dipping banding. Highly fractured.
		12	<3	100	BOX 18	171.0	170		164.9' - 173.0' SCHISTOSE META-ARKOSE: Light green with bands of black, pink, green. Bands dip 60 degrees. Fractures mostly parallel to bands. Moderately hard, moderately strong.
		53	1	90	BOX 18	171.0	170		173.0' - 176.0' IRON ORE: Rusty black, highly fractured. Magnetite rich.
		77	2	100	BOX 19	180.0	180		176.0' - 178.0' ORE BRECCIA: Fragments of meta-arkose in magnetite ore.
		85	2	100	BOX 19	180.0	180		178.0' - 185.9' IRON ORE: Magnetite-rich. Light to dark green alteration zones. Steeply dipping veins of calcite, abundant calcite.
		63	2	100	BOX 20	185.2	190		185.9' - 187.0' QUARTZITE: Greenish white, very fine-grained. Very hard, very strong.
		96	<1	100	BOX 20	185.2	190		187.0' - 229.5' IRON ORE: Magnetite-rich, massive with white calc-silicates or calcite to 190.8'.
		85	1	100	BOX 21	187.5	200		190.8' - 214.5' ore with veins of white calc-silicates, 25-30 degrees from vertical. Magnetite with pyrite, sericite, minor clinopyroxene. Moderately hard, moderately strong. Very fractured, brecciated, numerous healed fractures.
		82	1	100	BOX 22	208.0	210		
		66	1	100	BOX 22	208.0	210		
		58	3	100	BOX 23	214.5	220		
		71	1	100	BOX 24	229.5	220		
		83	<1	100	BOX 24	229.5	230		229.5' - 237.0' QUARTZITE:
	37	5	100	BOX 25	237.0	230			

	DATE: 3/92		The PRA Group, Inc CONSULTING ENGINEERS BOREHOLE LOG CH-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	3 of 13
	JOB NO. G125-19 DWS NO. EM 19006-3 DRAWN R. HARRIS CHECKED D. MERT APP'D D. AFFINITY			

REMARKS Hole Dia Drilling Date Proximal Charge	Tool Size	ROD	Feet/rod per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
247' depth at 8:00 pm, 2/15/92 Geologist J. Sutherland 257' depth at 9:30 pm, 2/15/92 267' depth at 5:47 am, 2/16/92 Deviation survey = 0.75 degrees Geologist D. Volturo	HQ	0	6	100	BOX 25	237.0	230		229' - 237.0' QUARTZITE: Light grey, fine-grained. Very hard, very strong, black. Highly fractured, fractures dipping 30-90 degrees. Light with hematite-stained stain.
	3.850" HOLE	18	2	100	BOX 25	237.0	240		237.0' - 245.5' QUARTZ MONZONITE DIKE: Light pink-brown, fine-grained. Moderately hard, moderately strong.
	2.400" CORE	0	8	100	BOX 26	241.5	240		245.5' - 275.5' IRON ORE: Magnetite rich, rusty black, slightly waxy. Moderately hard, slightly weakened. Scattered zones and veins of skarn minerals.
		0	>10	50	BOX 27	250.0	250		247.2' - 247.5' Green alteration zone (skarn, calc-silicate minerals)
		28	1	80	BOX 27	250.0	250		258.0' - 275.5' Skarn: dark green to yellow-green, some steeply dipping banding.
		14	2	52	BOX 28	258.0	250		258.0' - 275.5' Skarn: dark green to yellow-green, some steeply dipping banding.
		65	1	88	BOX 28	258.0	250		nearby vertical veins of calcite
		28	3	100	BOX 29	267.0	270		266.0' - 267.0' magnetite vein, slightly waxy
		22	3	92	BOX 29	267.0	270		
		32	2	58	BOX 30	275.5	280		275.5' - 284.0' QUARTZ MONZONITE DIKE: Fine-grained, pink-brown. Highly fractured, fractures slightly open, with hematite-stained stain. Very hard, very strong, fresh.
		24	3	98	BOX 30	275.5	280		282.0' increasing alteration, veins of ore
		0	5	81	BOX 31	283.0	290		
		33	2	62	BOX 32	292.5	290		291.0' - 294.0' Gauge light to dark green, crumbly
		42	2	100	BOX 32	292.5	290		294.0' - 319.7' IRON ORE: Black, fresh, hard, very strong. Abundant fresh pyrite. Minor fractures. Hard veins to 1/2" of zirconium and calcite.
		46	2	98	BOX 33	301.2	300		
	100	<1	100	BOX 34	301.2	310			
	92	<1	100	BOX 34	301.2	310			
	100	<1	100	BOX 34	301.2	310			

	DATE: 3/92		The PRA Group, Inc CONSULTING ENGINEERS BOREHOLE LOG CH-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	4 of 13
	JOB NO. G125-19 DWS NO. EM 19006-4 DRAWN R. HARRIS CHECKED D. MERT APP'D D. AFFINITY			

REMARKS Wear Data Drilling Data Personnel Changes	Tool Site	ROD (ft)	Fractures per foot	Percent Core Recovery	Bar Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description	
Geologist R. Harris	HO	100	<1	100	X-03	310			<u>304.0' - 319.7' IRON ORE</u> Black, fresh, hard, very strong. Abundant pyrite. Minor fracturing, hard veins of silica and traverse to > 1/2".	
	3.66" HOLE	93	<1	100	35	311.7				
	2.425" CORE		33	4	100	X-03	320			<u>319.7' - 341.0' QUARTZ MONZONITE</u> Pink-brown, fine grained, highly fractured. Fractures variable dip, mostly steep, minor iron-stain. Veins and fractures chloritized. Very hard, very strong.
			0	1	100	X-03				
			0	6	100	X-03				
			0	10	100	X-03				
			0	7	100	X-03				
			67	3	100	37				
			33	2	100	X-03				
			0	6	100	X-03				
			23	3	100	X-03				
			44	2	100	X-03				
	Geologist J. Schardt Electric generator failure, 9:03 pm, 2/15/92. Resumed drilling 11:40 pm, 2/15/92.		0	4	100	X-03	340			<u>341.0' - 389.5' SCHISTOSE META-ARKOSE</u> Banded pink-brown, dark green, light green, yellow-green. Moderately fractured, veins healed; fractures wide to 1/8" to bedding. Slightly weathered, decreasing with depth.
			33	5	100	X-03	350			
			50	3	100	X-03				
			23	8	100	X-03	360			
			25	10	100	41				
			1	1	1	X-03	370			
			18	4	100	42				
			8	5	100	X-03				
		11	4	100	X-03	380				
		0	8	100	X-03					
Geologist D. Affeldt		0	9	100	44	390			<u>382' - 385' highly fractured, highly stained. Iron-stain in fractures</u>	
									<u>389.5' - 395.0' QUARTZITE</u>	
397 depth at 11:42 am on 2/16/92										
365.5' increasing chroma-oxidation alteration, increasing fracture density, fractures open, 30-40 degrees to axis										

REGISTERED GEOLOGIST
 RYAN DEAN AFFELDT
 No. 1108
 STATE OF CALIFORNIA

The PRA Group, Inc
 CONSULTING ENGINEERS
**BOREHOLE LOG
 CH-10**
 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
 MINE RECLAMATION CORPORATION

REMARKS Wear Data Drilling Data Personnel Changes	Tool Site	ROD (ft)	Fractures per foot	Percent Core Recovery	Bar Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description		
400' depth at 1:00 pm on 2/17/92. Deviation survey = 0.75 degrees	HO	46	5	100	X-04	390			<u>389' - 395.0' QUARTZITE</u> Mass yellow to red hematite stain, moderately weathered, moderately hard, moderately fractured, fractures variable orientation. Zones of pyrite-chroma-oxidation alteration.		
	3.66" HOLE	47	4	100	45	390.0			<u>395.0' - 420.5' SILICIFIED</u> Fine grained, mottled with K-feldspar-quartzite- quartz-pyrite-stain. Hard, strong.		
	2.425" CORE		53	1	100	X-03	400			<u>420.5' - 428.0' IRON ORE</u> Abundant fresh pyrite zones up to 2" Moderately fractured; fractures tight, dipping up to 60 degrees. Hard, strong, slightly weathered iron-stained.	
			60	1	100	46					
			60	1	100	X-03	410			<u>412.5' - 415.7' moderately weathered iron, abundant iron-stain. Veils of hematite pyrite stain with quartz.</u>	
			30	<1	100	47					
			60	<1	100	48					
			87	<1	100	X-03	430			<u>428.0' - 436.2' QUARTZ MONZONITE</u> Pink-brown, coarse-grained. Abundant K-feldspar alteration and pyrite in healed fractures. Fractures, minor iron-stain, shallow dip.	
			47	1	100	49					
			63	3	100	X-03	440			<u>436.2' - 452.0' IRON ORE</u> Abundant pyrite. Very hard, very strong, fresh. Numerous vertical fractures with pyrite filling.	
			58	2	100	50					
			43	4	100	X-03	450			<u>452.0' - 457.6' ANDESITE DKE</u> Greenish gray, fine-grained. Moderately altered, hard strong to 456.4, becoming brecciated, softer more altered.	
	Geologist R. Harris		38	4	100	52				<u>457.6' - 610.0' QUARTZITE</u> Light gray, fine-grained, very hard, very strong. Many re-healed fractures with iron-stain up to 5 mm, dipping 0 - 10 degrees. Fractures tight, with pyrite, dipping 30 - 45 degrees. Irregular veins to 10 mm.	
			32	4	100	X-03	460				
			100	0	100	53					
			100	0	100	54					
			63	1	100	54					
470' depth at 9:21 am on 2/16/92											

REGISTERED GEOLOGIST
 RYAN DEAN AFFELDT
 No. 1108
 STATE OF CALIFORNIA

The PRA Group, Inc
 CONSULTING ENGINEERS
**BOREHOLE LOG
 CH-10**
 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
 MINE RECLAMATION CORPORATION

REMARKS Hole Data Drilling Data Personal Charge	Test Site	RQD (%)	Fractures per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description			
487' depth at 4:13 am, 2/18/92	2.40' CORE	63	1	100	X O B	477.0'	470		457.5' - 610.0' QUARTZITE Light gray, fine-grained. Very hard, very strong. Many re-healed fractures with iron-stain, up to 5 mm, dipping 0 - 10 degrees. Fractures with pyrite, dip to 20 - 45 degrees. Irregular quartz veins to 10 mm.			
		13	4	80	54	477.0'	480					
		75	2	100	X O B	477.0'						
		44	3	100	55	477.0'						
		13	4	100	55	477.0'						
		RQD and fractures per foot averaged for box 56 (7 core runs). 487' depth at 8:10 am, 2/18/92	(62)	(1)	100	B O X				487.5'	490	483.0' - 484.5' gray siliceous, with green epidote or chlorite, and pyrite. Unconformable fractures.
			(50)	(1)	100	X O B				500.0'	500	
		RQD and fractures per foot averaged for box 57 (6 core runs). 507' depth at 1:42 pm, 2/18/92 Deviation survey = 1.5 degrees	63	<1	100	B O X				500.0'	500	500.0' - 547.0' light green, with zones of banding dipping about 60 degrees. Fractures nearly vertical. Slightly less hard and strong. banding steepens with depth.
			100	<1	100	56				500.0'		
		517' depth at 4:40 pm, 2/18/92	100	0	100	56.5'				510		
			100	0	100	57.0'				510		
81	1		100	59								
527' depth at 7:35 pm, 2/18/92	42	4	100	517.8'	520							
	37	4	100	59								
	60	3	100	60								
537' depth at 12:00 am, 2/18/92	42	1	100	527.0'	530							
	94	1	100	61								
	70	0	100	61								
547' depth at 2:36 am, 2/18/92	88	<1	100	536.0'	540							
	83	1	100	62								
	100	<1	100	62								
557' depth at 4:26 am, 2/18/92	86	<1	100	545.0'	550	547.0' - 550.0' Gray, banding nearly absent. Very hard, very strong. Dark green alteration zones.						

	DATE 3/92		BOREHOLE LOG CH-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	FIGURE NO. 7 of 16
	JOB NO. 0125-18			

REMARKS Hole Data Drilling Data Personal Charge	Test Site	RQD (%)	Fractures per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description		
Geologist D. Volturno 567' depth at 9:00 am, 2/18/92 577' depth at 10:55 am, 2/18/92 587' depth at 2:15 pm, 2/18/92 597' depth at 3:25 pm, 2/18/92 Geologist J. Schardt 598' depth at 4:00 pm, 2/18/92 Deviation survey = 0.75 degrees 617' depth at 6:10 pm, 2/18/92 627' depth at 6:56 pm, 2/18/92 637' depth at 8:26 pm, 2/18/92	2.40' CORE	HQ	69	1	100	BCX 63	550		457.5' - 610.0' QUARTZITE Light gray, fine-grained. Very hard, very strong. Many re-healed fractures with iron-stain, up to 5 mm, dipping 0 - 10 degrees. Tight fractures with pyrite, dip to 20 - 45 degrees. Irregular quartz veins to 10 mm.		
		3.15' HOLE	67	1	100	64	554.0'			560	
		58	2	100	X O B	554.0'					
		53	2	100	64	562.0'					
		53	2	100	X O B	65					
		56	2	100	X O B	65.8'					
		40	3	100	66	571.8'					
		40	4	100	66	582.0'					
		80	<1	100	67	582.0'					
		49	3	58	B O X	582.0'	580				575.0' - 578.5' abundant light healed fractures with calcite. Orientation varies. 578.5' one vein, one inch, 90 degrees to core axis.
		52	3	100	68	587.0'					
		598' depth at 4:00 pm, 2/18/92 Deviation survey = 0.75 degrees	63	2	100	B O X	590				583.0' - 610.0' scattered quartz monzonite dikes, 2 - 8 inches, 30 - 45 degrees to axis. Green alteration in quartzite.
52	2		100	68	598.0'						
52	2		100	68	598.0'						
617' depth at 6:10 pm, 2/18/92	67	3	100	B O X	600	610.0' - 660.0' ANDRUSITE OXIDE Dark gray with sodio-chlorite-pyrite-pyrite alteration. Argonite groundmass with felsic phenocrysts to 1/4". Moderately fractured, hard, strong, slightly weathered. Fractures light, with quartz epidote, minor calcite, serphentine, iron-stain.					
	37	1	100	70	615.0'						
	38	1	100	71	621.0'						
627' depth at 6:56 pm, 2/18/92	38	1	100	71	627.0'	630					
	56	2	100	72	627.0'						


	DATE 4/92		BOREHOLE LOG CH-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	FIGURE NO. 8 of 17
	JOB NO. 0125-18			

REMARKS Wear Data Drilling Data Reameral Change	Test Site	ROD (ft)	Fractures per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
647 depth at 10:45 pm, 2/25/92 Geologist: R. Usry	HO	50	1	100	BO X	634.0'	500		610.0' - 656.0' ANDESITE DYKE Light gray, fine-grained. Very hard, very strong. Many re-healed fractures with ironite stain, up to 5 mm, dipping 0 - 10 degrees. Tight fractures with pyrite, dipping 20 - 45 degrees. Irregular quartz veins to 10 mm. 634.0' - 645.0' minor ironite stain, calcite in veins. Slightly weathered.
		50	2	100	BO X	641.5'	640		
650 depth at 2:29 am, 2/25/92	HO	67	2	100	BO X	641.5'	640		
		55	2	100	BO X	641.5'	650		
660 depth at 4:55 am, 2/25/92	HO	74	1	100	BO X	641.5'	650		655.0' - 662.0' highly fractured. Apertures slightly open. Ironite stain, calcite, dipping 0 - 30 degrees.
		0	3	100	BO X	654.0'	660		
660 depth at 4:55 am, 2/25/92	HO	0	5	100	BO X	654.0'	660		662.0' - 666.0' shear zone with slickensides, calcite in fractures.
		15	3	100	BO X	654.0'	660		
670 depth at 5:40 am, 2/25/92	HO	22	4	100	BO X	654.0'	670		666.0' - 671.0' SKELTON Dark green azaroon in andesine (?) with iron ore and calcite veins. Moderately hard, moderately strong, moderately weathered.
		18	2	100	BO X	654.0'	670		
680 depth at 7:15 am, 2/25/92	HO	30	2	100	BO X	654.0'	680		
		8	4	100	BO X	654.0'	680		
690 depth at 8:00 am, 2/25/92 Geologist: D. Volume	HO	13	3	100	BO X	654.0'	690		
		33	5	100	BO X	654.0'	690		
700 depth at 9:20 am, 2/25/92 Deviator survey = 1 degree	HO	27	2	100	BO X	654.0'	700		691.0' - 696.0' QUARTZITE Dark gray, very fine-grained. Hard, strong, fresh to slightly weathered. Moderately fractured, apertures slightly open, dipping mostly 0 - 50 degrees, minor ironite stain, minor calcite.
		0	>10	20	BO X	654.0'	700		
710 depth at 11:15 am, 2/25/92	HO	0	4	100	BO X	654.0'	710		
		17	6	100	BO X	654.0'	710		
		0	1	100	BO X	654.0'	710		
		22	4	100	BO X	654.0'	710		



DATE: 4/92	The PRA Group, Inc CONSULTING ENGINEERS	FIGURE NO.
JOB NO. G125-18		
DWG NO. EM 19028-9	BOREHOLE LOG CH-10	9 of 18
DRAWN: R. HARRIS		
CHECKED: D. MERTZ		
APP'D: D. AFFELDT	EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	

REMARKS Wear Data Drilling Data Reameral Change	Test Site	ROD (ft)	Fractures per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
710' depth at 2:10 am, 2/25/92	HO	25	4	100	BO X	710.0'	710		691.0' - 696.0' QUARTZITE Dark gray, very fine grained. Hard, strong, fresh to slightly weathered. Moderately fractured, apertures slightly open, dipping mostly 0 - 30 degrees, minor ironite stain, minor calcite.
		20	4	100	BO X	710.0'	710		
720' depth at 2:45 pm, 2/25/92 Geologist: J. Subard	HO	67	2	100	BO X	710.0'	720		
		75	2	100	BO X	710.0'	720		
730' depth at 4:45 pm, 2/25/92	HO	69	2	100	BO X	710.0'	730		
		73	1	100	BO X	710.0'	730		
740' depth at 5:47 pm, 2/25/92	HO	32	2	100	BO X	710.0'	740		
		52	1	100	BO X	710.0'	740		
750' depth at 6:50 pm, 2/25/92	HO	60	2	100	BO X	710.0'	750		
		68	2	100	BO X	710.0'	750		
760' depth at 8:25 pm, 2/25/92	HO	31	1	100	BO X	710.0'	760		759.0' - 779.0' sand zone: brecciated, minor bleaching, minor gouge, moderately strong
		0	>10	100	BO X	710.0'	760		
770' depth at 8:46 pm, 2/25/92 Geologist: R. Usry	HO	0	>10	100	BO X	710.0'	770		
		0	>10	100	BO X	710.0'	770		
780' depth at 11:23 pm, 2/25/92	HO	25	>10	100	BO X	710.0'	780		
		23	4	100	BO X	710.0'	780		
790' depth at 11:45 pm, 2/25/92	HO	17	3	100	BO X	710.0'	790		
		28	3	100	BO X	710.0'	790		



DATE: 4/92	The PRA Group, Inc CONSULTING ENGINEERS	FIGURE NO.
JOB NO. G125-18		
DWG NO. EM 19028-10	BOREHOLE LOG CH-10	10 of 18
DRAWN: R. HARRIS		
CHECKED: D. MERTZ		
APP'D: D. AFFELDT	EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	

REMARKS Hole Data Drilling Data Personnel Changes	Test Site	RHD (ft)	Fracture per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
627 depth at 4:21 am, 2/21/92 Demarcation survey = 1 degree	HQ 1.85' HOLE 2.40' CORE	28	2	100	91	790		<u>811.0' - 829.0' QUARTZITE</u> Dark gray, very fine-grained. Hard, strong, fresh to slightly weathered. Moderately fractured, apertures slightly open, dipping mostly 0 - 30 degrees, minor limonite stain, minor calcite.	
		60	1	100	91	800			
817 depth at 5:14 am, 2/21/92	HQ 1.85' HOLE 2.40' CORE	47	1	100	92	810		<u>806.0' - 822.0' META-ARKOSE</u> Light gray, generally quartz-rich, minor dolomite zones. Moderately hard to hard, moderately strong to strong, moderately weathered. Moderately fractured with dark green alteration along fractures. Apertures slight, veins 20 - 30 degrees.	
		43	2	100	92	820			
827 depth at 5:28 am, 2/21/92	HQ 1.85' HOLE 2.40' CORE	48	1	100	93	830		<u>839.0' - 848.5' brecciated zones, highly altered</u> Massive fractures with massive pink-brown quartz veins, minor calcite veins.	
		60	1	100	94	840			
837 depth at 7:28 am, 2/21/92 Geologist: D. Volturno	HQ 1.85' HOLE 2.40' CORE	18	2	100	94	850		<u>863.0' - 869.0' brecciated zone with purple silicification, hematite stain</u>	
		33	2	100	95	860			
847 depth at 8:28 am, 2/21/92	HQ 1.85' HOLE 2.40' CORE	50	2	100	95	870			
		50	2	100	96				
857 depth at 9:45 am, 2/21/92	HQ 1.85' HOLE 2.40' CORE	40	2	100	97				
		60	1	100	97				
867 depth at 10:58 am, 2/21/92	HQ 1.85' HOLE 2.40' CORE	27	3	100	98				
		40	2	100	98				
877 depth at 11:45 am, 2/21/92	HQ 1.85' HOLE 2.40' CORE	40	2	100	99				
		27	>10	100	99				

	DATE: 4/92		PROJECT NO.
	JOB NO. 0125-19		
	DWG NO. EM 19006-11		
	DRAWN R. HARRIS		
	CHECKED D. MERTZ		
APP'D D. AFFELDT		The PRA Group, Inc. BOREHOLE LOG CH-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	11 of 18

REMARKS Hole Data Drilling Data Personnel Changes	Test Site	RHD (ft)	Fracture per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
877 depth at 11:40 am, 2/21/92	HQ 3.55' HOLE 2.40' CORE	53	<1	100	100	870		<u>806.0' - 852.0' META-ARKOSE</u> Light gray, generally quartz-rich, minor dolomite zones. Hard, strong, moderately weathered. Moderately fractured, with dark green alteration along fractures. Apertures slight, veins up 20-30 degrees.	
		47	2	100	100	880			
887 depth at 1:48 pm, 2/21/92 Geologist: J. Scharf	HQ 3.55' HOLE 2.40' CORE	11	3	100	101	890		<u>892.0' - 904.5' QUARTZ MONZONITE</u> Light gray, coarse grained, K-feldspar phenocrysts. Epoxide in fractures, granitic epoxide 1-2 %. 892' - 897' green andesite dikes	
		72	1	100	101	900			
897 depth at 6:27 pm, 2/21/92	HQ 3.55' HOLE 2.40' CORE	35	1	100	102	910		<u>904.4' - 921.0' SKARN:</u> Dark green, fine grained, vertical flow texture Pyroxene-rich, with epoxide in veins. Hard, strong, slightly weathered. Moderately fractured with iron oxide, hematite stain, fractures 60-845 degrees.	
		27	3	100	102	920			
907 depth at 10:00 pm, 2/21/92 Demarcation survey = 1.0 degree Geologist: R. Ustry	HQ 3.55' HOLE 2.40' CORE	68	1	100	103	930		<u>921.0' - 924.0' QUARTZ MONZONITE</u> Green-gray, medium grained. Epoxide-like veins 1-3 mm, pyroxene-rich zones. Hard, strong, slightly fractured.	
		19	2	100	103	940			
917 depth at 3:10 am, 2/22/92	HQ 3.55' HOLE 2.40' CORE	100	<1	100	104	950		<u>924.0' - 950.0' QUARTZITE</u> Light gray, fine grained, shattered appearance, with dark green alteration along shatter lines. Veins of pink-brown massive quartz to 1 cm. Very hard, very strong, unweathered, slightly fractured, with minor calcite.	
		23	2	100	104	960			
927 depth at 4:15 am, 2/22/92	HQ 3.55' HOLE 2.40' CORE	70	1	100	105	970		<u>957' - 946'</u> scattered ore veins to 2 cm.	
		57	2	100	105	980			
937 depth at 5:40 am, 2/22/92	HQ 3.55' HOLE 2.40' CORE	42	1	100	106	990		<u>957' - 946'</u> scattered ore veins to 2 cm.	
		65	1	100	107	1000			
947 depth at 7:50 am, 2/22/92 Geologist: D. Volturno	HQ 3.55' HOLE 2.40' CORE	83	1	100	107	1010		<u>957' - 946'</u> scattered ore veins to 2 cm.	
		100	<1	100	107	1020			
957 depth at 9:22 am, 2/22/92	HQ 3.55' HOLE 2.40' CORE	60	1	100	108	1030		<u>957' - 946'</u> scattered ore veins to 2 cm.	
		27	3	100	108	1040			

	DATE: 4/92		PROJECT NO.
	JOB NO. 0125-19		
	DWG NO. EM 19006-12		
	DRAWN R. HARRIS		
	CHECKED D. MERTZ		
APP'D D. AFFELDT		The PRA Group, Inc. BOREHOLE LOG CH-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION	12 of 18

REMARKS Hour Date Drilling Data Personnel Changes	Tool Size	RFD (N)	Fractures per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
967' depth at 10:25 am, 2/22/92	2.406" CORE	53	3	100	109	950.0'	950		951.0' - 952.0' IRON ORE Black, magnetite-rich, abundant massive pyrite- hematite-siderite, minor ironite stain. Calcite abundant in fractures to 1 cm.
		60	1	100	110				
977' depth at 11:45 am, 2/22/92		56	2	100	111	950	950		952.0' - 955.0' QUARTZ MONZONITE Greenish, highly altered. Calcite abundant in horizontal fractures. Moderately to very fractured. Hard, strong, slightly weathered.
		87	<1	100	110				
987' depth at 1:55 pm, 2/22/92 Geologist J. Sutherland		47	1	100	111	970	970		955.0' - 970.5' IRON ORE / SKARN Dark green to black, highly altered. Abundant magnetite, pyrite, dark massive quartz veins. Slightly fractured with calcite veins to 1 cm. Mostly hard to very hard, strong to very strong unweathered.
		87	<1	100	112				
987' depth at 1:55 pm, 2/22/92 Geologist J. Sutherland		17	2	100	112	980	980		970.5' - 977.1' ANDESITE DIKE Dark gray, slightly porphyritic, aphanitic groundmass. Slightly to moderately fractured, epidote and calcite lining Apertures slightly open, minor ironite stain. Hard, strong unweathered.
		0	>10	100	113				
997' depth at 4:00 pm, 2/22/92		0	5	100	113	980	980		977.1' - 981.1' IRON ORE Red, brown, black, hematite, minor magnetite. Highly weathered, soft, crumbly, lumpy.
		67	1	100	113				
1000' depth at 5:32 pm, 2/22/92 Deviation survey = 1 degree		0	3	85	114	980	980		981.1' - 1027.5' SKARN Green chlorite, epidote, tremolite, with ore veins (magnetite + pyrite) to 2 inches. Stained quartz zones. Moderately fractured, with calcite fill, ironite stain. Hard, strong, slightly weathered.
		52	2	100	114				
1000' depth at 5:32 pm, 2/22/92 Deviation survey = 1 degree		22	4	100	114	1000	1000		
		50	3	100	115				
1010' depth at 9:35 pm, 2/22/92		75	3	100	115	1010	1010		
		42	2	100	116				
1020' depth at 10:25 pm, 2/22/92 Geologist R. Harty		73	1	100	116	1020	1020		
		40	2	100	117				
1020' depth at 10:25 pm, 2/22/92 Geologist R. Harty		85	<1	100	117	1030	1030		
		87	<1	100	118				
1030' depth at 11:50 pm, 2/22/92		62	1	100	118	1030	1030		1027.5' - 1054.5' IRON ORE Black, magnetite-rich. Moderately fractured, apertures slight- ly open, dip steep to vertical, with ironite stain. Hard, strong, very slightly weathered.




The PRA Group, Inc
 CONSULTING ENGINEERS
BOREHOLE LOG
CH-10
 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
 MINE RECLAMATION CORPORATION

DATE: 4/92
 JOB NO.: G125-19
 DWD NO.: EM 18006-13
 DRAWN: R. HARTZ
 CHECKED: D. MERIT
 APPD: D. AFFELT

FIGURE NO. 10 OF 11

REMARKS Hour Date Drilling Data Personnel Changes	Tool Size	RFD (N)	Fractures per foot	Percent Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
1040' depth at 1:15 am, 2/23/92	2.406" CORE	62	1	100	119	1030	1030		1027.5' - 1054.5' IRON ORE Black, magnetite-rich. Moderately fractured, apertures slightly open, dip steep to vertical, with ironite stain. Hard, strong, very slightly weathered.
		17	2	100	119				
1050' depth at 2:25 am, 2/23/92		80	2	100	120	1040	1040		
		57	1	100	120				
1057' depth at 2:25 am, 2/23/92		25	1	100	121	1050	1050		
		25	2	100	121				
1067' depth at 4:00 am, 2/23/92 Geologist D. Yokumo		27	3	100	122	1060	1060		1045.5' - 1067.4' SKARN Massive, ironite-stained, iron ore zone. Moderately weathered.
		25	2	100	122				
1070' depth at 5:50 am, 2/23/92		0	>10	100	123	1070	1070		1067.4' - 1081.5' ANDESITE DIKE Green-gray, highly altered, abundant ironite stain. Massive highly fractured to scattered. Slightly hard, slightly strong, highly weathered.
		0	>10	100	123				
1080' depth at 8:47 am, 2/23/92		17	3	100	124	1080	1080		
		29	3	100	124				
1090' depth at 2:37 pm, 2/23/92		17	5	100	125	1090	1090		1081.5' - 1109.0' QUARTZITE Pinkish tan, green, gray. Pervasive chlorite-epidote alteration. Calcite in veins 1-5 mm, minor ironite stain. Hard to very hard, very strong, slightly to moderately fractured, apertures slightly open.
		53	2	100	125				
1100' depth at 3:00 pm, 2/23/92 Geologist J. Sutherland Deviation survey = 1.5 degrees		67	1	100	125	1100	1100		
		67	1	100	125				
1107' depth at 5:40 pm, 2/23/92		67	1	100	126	1100	1100		
		53	2	100	126				
1110' depth at 5:40 pm, 2/23/92		72	2	100	127	1110	1110		
		78	1	100	127				
1110' depth at 5:40 pm, 2/23/92		78	1	100	128	1110	1110		1109.0' - 1127.5' ANDESITE DIKE



The PRA Group, Inc
 CONSULTING ENGINEERS
BOREHOLE LOG
CH-10
 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA
 MINE RECLAMATION CORPORATION

DATE: 4/92
 JOB NO.: G125-19
 DWD NO.: EM 18006-14
 DRAWN: R. HARTZ
 CHECKED: D. MERIT
 APPD: D. AFFELT

FIGURE NO. 11 OF 11

REMARKS Water Data Drilling Data Personnel Changes	Tool Site	ROD (ft)	Fluores per foot	Fluores Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Elevation Log	Material Classification and Physical Description
1137' depth at 8:15 pm, 2/24/92	HO 3.85' HOLE 2.406' CORE	77	<1	100	BOX 128 1114.5'	1110			1137' - 1112' ANDESITE DIKE Green, highly stained, highly calcified. Moderately to slightly hard, moderately to slightly strong.
		0	5	66	XOB 1114.5'				
1137' depth at 10:00 pm, 2/23/92		32	3	100	XOB 1122.1'	1120			1112' - 1116.5' FAULT GOUGE Green to yellow, minor ironstone stain; slickensided.
		42	3	100	XOB 1122.1'				
1137' depth at 12:25 am, 2/24/92 Geologist: R. Urley		40	3	100	XOB 1130.5'	1130			1116.5' - 1164.8' QUARTZITE Green/gray/tan. Slightly weathered, moderately fractured. Fractures slightly healed, mostly 5-20 degrees from axis, with calcite-like fill, ironstone stain.
		47	2	100	XOB 1130.5'				
1157' depth at 2:25 am, 2/24/92 Geologist: D. Volturo		65	1	100	XOB 1137.2'	1140			
		52	3	100	XOB 1148.0'				
1167' depth at 4:55 am, 2/24/92		72	2	100	XOB 1154.0'	1150			
		57	2	100	XOB 1164.0'				
1177' depth at 8:01 am, 2/24/92		62	2	100	XOB 1164.1'	1160			1164.8' - 1178.9' QUARTZ MONZONITE Gray to pinkish green; enclaves of green stained quartzite. Hard to very hard, strong, slightly weathered. Moderate ironite-epidote-pyrite alteration. Calcite veins, hairline to 1 cm.
		67	1	100	XOB 1172.0'				
1187' depth at 9:40 am, 2/24/92		52	1	100	XOB 1172.0'	1170			
		33	2	100	XOB 1181.0'				
1197' depth at 11:12 am, 2/24/92		50	2	100	XOB 1181.0'	1180			1178.9' - 1195.0' QUARTZITE Medium pink-gray. Highly fractured, healed with dark green chlorite-epidote-pyrite, hairline to 3 cm, 10-30 degrees from axis. Very hard, very strong, slightly weathered.
		63	<1	100	XOB 1191.0'				

REGISTERED GEOLOGIST
IRVING DEAN AFFELDT
No. 1108
ENGINEERING
GEOLOGIST

DATE 4/92	The PRA Group, Inc CONSULTING ENGINEERS	FIGURE NO.
JOB NO. G125-19	EDITED BOREHOLE LOG	
DWG NO. EM 18006-15	CH-10	
DRAWN R. HARRIS	EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA	
CHECKED C. MERIT	MINE RECLAMATION CORPORATION	
APPROVED D. AFFELDT		15 of 18

REMARKS Water Data Drilling Data Personnel Changes	Tool Site	ROD (ft)	Fluores per foot	Fluores Core Recovery	Box Number	Elevation (ft)	Depth (ft)	Elevation Log	Material Classification and Physical Description
1197' depth at 11:12 am, 2/24/92	HO 2.85' HOLE 2.406' CORE	60	1	100	XOB 1184.5'	1190			1178.9' - 1195.0' QUARTZITE Medium pink-gray, highly fractured, mostly healed with dark green chlorite-epidote-pyrite, hairline to 3 cm, 10-30 degrees from axis. Very hard, very strong, slightly weathered.
		13	>10	100	XOB 1184.5'				
1207' depth at 12:00 pm, 2/24/92 Deviation survey = <1.5 degrees Geologist: J. Scharf		28	3	100	XOB 1192.0'	1200			1195.0' - 1198.5' SKARN Very dark green to black, highly stained, ore veins with pyrite. Moderately hard, moderately strong, moderately weathered, highly fractured, apertures moderately open.
		0	2	100	XOB 1192.0'				
1217' depth at 4:40 pm, 2/24/92		61	1	100	XOB 1202.0'	1210			1198.5' - 1203.5' ANDESITE Dark gray, porphyritic. Moderately to highly fractured. Minor epidote-calcite fill.
		52	2	100	XOB 1202.0'				
1227' depth at 6:30 pm, 2/24/92		0	3	100	XOB 1202.0'	1220			1203.5' - 1223.5' DIORITE Medium gray to green, fine to medium grained. Green alteration (pyroxene- amphibole-iron-sulfide-epidote-pyrite). Moderately fractured, light to moderately open, veins of epidote-calcite, ironstone stain. Hard, strong.
		50	5	100	XOB 1202.0'				
1237' depth at 9:55 pm, 2/24/92		16	4	65	XOB 1202.0'	1230			1223.5' - 1236.0' ANDESITE Dark gray, aphanitic, slightly porphyritic. Moderately to highly fractured, apertures light to slightly open with epidote-pyrite fill, ironstone stain. Hard, strong, slightly weathered.
		11	4	92	XOB 1202.0'				
1247' depth at 3:40 am, 2/25/92 Geologist: R. Urley		52	2	100	XOB 1214.0'	1240			1236.0' - 1238.5' QUARTZ MONZONITE Pink to brown, medium grained. Fractures mostly healed hairline to 3 mm, 10-30 degrees from axis, with calcite fill, ironstone stain. Very hard, very strong, slightly weathered.
		36	2	100	XOB 1214.0'				
1257' depth at 9:50 am, 2/25/92		42	2	100	XOB 1214.0'	1250			1238.5' - 1262.0' QUARTZITE Gray, tan, pink mottled zones. Older fractures healed, with black to green alteration zones. Younger fractures healed, with abundant calcite, apertures slightly to moderately open, mostly non-veined. Hard, strong.
		0	4	100	XOB 1214.0'				
1267' depth at 12:05 pm, 2/25/92		33	3	100	XOB 1214.0'	1260			1262.0' - 1275.5' QUARTZ MONZONITE Gray-brown, coarse-grained. Hard, strong. Moderately fractured, with calcite fill, slightly open. Scattered small masses of quartzite.
		44	2	100	XOB 1214.0'				
1277' depth at 4:30 pm, 2/25/92		14	>10	100	XOB 1214.0'	1270			
		13	2	100	XOB 1214.0'				
		53	1	100	XOB 1214.0'				
		47	1	100	XOB 1214.0'				
		47	2	100	XOB 1214.0'				

REGISTERED GEOLOGIST
IRVING DEAN AFFELDT
No. 1108
ENGINEERING
GEOLOGIST


DATE 3/92	The PRA Group, Inc CONSULTING ENGINEERS	FIGURE NO.
JOB NO. G125-19	BOREHOLE LOG	
DWG NO. EM 18006-16	CH-10	
DRAWN R. HARRIS	EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA	
CHECKED C. MERIT	MINE RECLAMATION CORPORATION	
APPROVED D. AFFELDT		16 of 18

REMARKS Wear Date Drilling Date Personnel Changes	Tool Size	ROD (ft)	Fractures per foot	Percent Core Recovery	Box Number	Character (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
1270' depth at 2:00 pm, 2/25/92	3.15" 7/16	47	2	100	142	X O B	1270		1265' - 1275' QUARTZ MONZONITE Gray-brown, coarse-grained. Hard, strong. Moderately fractured, with calcite fill. Apertures slightly open. Scattered small masses of quartzite.
		63	2	100	148	X O B	1275		
1280' depth at 4:06 pm, 2/25/92 Geologist: J. Sutherland	2.40" CORE	74	1	100	148	X O B	1280		1275' - 1285' LIVINGSTONE Gray-green, with abundant calcite veins and fracture tracings with black (ore?) fill. Hard, strong, moderately fractured, apertures slightly open. Increasing silicification with depth.
		50	3	100	149	X O B	1285		
		83	<1	100	150	X O B	1290		
		40	2	100	143	X O B	1295		
1290' depth at 11:57 am, 2/25/92 Geologist: R. Ustev		50	2	100	143	X O B	1290		1285' - 1295' QUARTZ MONZONITE Green and gray, mixed with minor green-hercynite quartzite. Hard, strong, slightly weathered, moderately fractured, with epidote-calcite fill, iron-stain.
		22	3	100	150	X O B	1295		
1300' depth at 11:52 am, 2/25/92 Deviation survey = 1.5 degrees Geologist: D. Vahama		57	3	100	150	X O B	1300		1295' - 1299' QUARTZITE Dark gray, with 3-5 mm ore veins. Hard, strong. Moderately fractured, apertures slightly open with minor epidote-calcite fill.
		57	2	100	151	X O B	1305		
1310' depth at 3:10 pm, 2/25/92 Geologist: J. Sutherland		44	2	100	151	X O B	1310		1299' - 1300' SKARN Gray, black green, orange, with mixed zones of quartzite and ore. Up to 25% ore, with abundant pyrite. Hard, strong, slightly weathered. Moderately fractured, apertures moderately open, calcite in veins.
		13	3	100	152	X O B	1315		
1320' depth at 5:15 pm, 2/25/92 Broken drive chain - rig down until 12:42 am, 2/28/92 Geologist: R. Ustev		25	3	100	152	X O B	1320		1307' - 1327' dissolution of calcite veins
		63	<1	100	153	X O B	1325		
1330' depth at 1:27 am, 2/27/92 Geologist: D. Vahama		100	0	100	153	X O B	1330		1327' - 1335' QUARTZITE Light green to medium dark gray, fine-grained to medium. Very hard, very strong, unweathered. Moderately fractured, fractures healed to slightly open. Calcite-epidote veins, hercynite to 5 mm, 0-50 degrees to axis.
		56	<1	100	154	X O B	1335		
1340' depth at 4:00 am, 2/25/92 Geologist: D. Vahama		100	<1	100	154	X O B	1340		
		0	>10	100	155	X O B	1345		
1350' depth at 1:24 am, 2/28/92		0	>10	60	155	X O B	1350		
		47	5	100	156	X O B	1350		
		17	5	100	157	X O B	1350		

	DATE: 4/92	<p>The PRA Group, Inc CONSULTING ENGINEERS</p> <p>BOREHOLE LOG CH-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION</p>	FIGURE NO:
	JOB NO. G125-12		17 of 15
	DWG NO. EM 19005-17		
	DRAWN: R. HARRIS		
	CHECKED: D. MERT		
APP'D: D. AFFELDT			

REMARKS Wear Date Drilling Date Personnel Changes	Tool Size	ROD (ft)	Fractures per foot	Percent Core Recovery	Box Number	Character (ft)	Depth (ft)	Lithologic Log	Material Classification and Physical Description
1350' depth at 12:26 am, 2/28/92	3.50" HOLE	11	>10	100	157	X O B	1350		1300' - 1335' QUARTZITE Light green to medium dark gray, fine-grained to medium. Very hard, very strong, unweathered. Moderately fractured, fractures healed to slightly open. Calcite-epidote veins, hercynite to 5 mm, 0-50 degrees to axis.
		19	5	100	156	X O B	1355		
1360' depth at 12:00 pm, 2/28/92	2.40" CORE	29	5	100	156	X O B	1360		
		33	1	100	158	X O B	1365		
1370' depth at 2:17 pm, 2/28/92		13	5	100	159	X O B	1370		
		17	3	100	159	X O B	1375		
1380' depth at 5:10 pm, 2/28/92 Geologist: J. Sutherland		79	1	100	160	X O B	1380		
		81	<1	100	160	X O B	1385		
Total depth 1389' at 7:30 pm, 2/28/92		72	<1	100	160	X O B	1385		
		87	<1	100	151	X O B	1390		
							1390		TOTAL DEPTH 1389 FEET
							1400		
							1410		
							1420		
							1430		

	DATE: 4/92	<p>The PRA Group, Inc CONSULTING ENGINEERS</p> <p>BOREHOLE LOG CH-10 EAGLE MOUNTAIN LANDFILL, RIVERSIDE COUNTY, CALIFORNIA MINE RECLAMATION CORPORATION</p>	FIGURE NO:
	JOB NO. G125-13		18 of 15
	DWG NO. EM 19005-18		
	DRAWN: R. HARRIS		
	CHECKED: D. MERT		
APP'D: D. AFFELDT			






Table E.1 Summary of Soil Laboratory Testing


Boring	Sample Information		In-situ Water Content, %	In-situ Dry Unit Weight, pcf	Atterberg Limits		Sieve/Hydrometer			USCS Group Symbol	Hydraulic Conductivity (cm/s)
	Sample No	Depth (ft)			LL	PI	#4 (%)	#200 (%)	(< 5µm) (%)		
C-1	3	17	1.7	112.4	-	-	91	8.3	-	SP-SM	
	7	58	1.1	111.1	-	-	97.3	9.3	-	SP-SM	
	12	101	2.8	111.6	NP	NP	98.3	14.6	8	SM	
	13	110	-	-	-	-	99.8	11.7	4	SP-SM	
	14	120-123*	-	-	-	-	81.6	8.7	3	(SP-SM)g	
	15	141	-	-	-	-	99.4	25.4	19	SM-SC	
	16	160	-	-	-	-	92.5	16.5	10	SM-SC	
	17	177	-	-	-	-	85.4	13.1	-	(SM)g	
	18	199	-	-	-	-	99.7	27.9	16	SC	
	19	201	5.3	109.9	31	9	94.1	18.8	11	SC	
	21	210-220*	-	-	NP	NP	-	-	-	-	
	24	240-250*	-	-	-	-	97.9	23.3	13	SM-SC	
	24	262	7.7	104.8	24	4	-	-	-	SC-SM	
	27	263-272*	-	-	-	-	96.7	19	8	SM	
	28	285-275*	-	-	-	-	77.9	14.9	7	(SM)g	
	30	280-295*	-	-	-	-	98.3	16.4	-	SM	
	32	322	5.6	116.1	-	-	98.7	26.1	13	SM	
	34-2	380	-	-	21	3	-	-	-	SM	
	37	400-420*	-	-	40	26	-	-	-	CL	
	38	420-426*	-	-	-	-	99.9	8.1	-	-	
	42-2	460	15.3	113.1	23	3	-	-	-	SC-SM	
	42-3	460	-	-	22	6	-	-	-	SC-SM	
C-5	1	n/a	-	-	-	-	97.6	19	13	SC-SM	
	2	n/a	-	-	-	-	92.4	14.4	11	-	
	4-2	20	2.6	124.2	-	-	74.6	13.3	7	(SM)g	
	8	n/a	-	-	-	-	99.7	16	13	SM	
	9	59	-	-	-	-	58.6	2.8	-	(SW)g	
	10-3	62	2.9	112.4	-	-	98.9	22	16	SC-SM	2.70E-07
	11	n/a	-	-	-	-	83.6	14.5	9	(SM)g	
	12-3	81	2	113.3	-	-	45	9.8	-	(CP-GM)s	
	13	101	-	-	-	-	94.3	4.8	-	SP-SM	
	14	121	-	-	-	-	52.7	6.7	-	(CP-GM)s	
	16	142	23.5	93.2	58	35	100	91.2	70	CH	9.20E-10
	18	n/a	-	-	-	-	100	96.2	53	M/ACI	
	23	206	15.3	109.1	36	10	100	75.6	17	(ML)s	
	25	241	-	-	-	-	99.7	42.3	18	SM	
	28	276	-	-	-	-	100	33.4	-	SM	
	29	280	-	-	-	-	100	8.2	7.4	SP-SM	
	30	300	-	-	-	-	100	41.5	18	SM-SC	
	MC-1	344**	31.4	92	100	58	-	98.7	-	CH	
C-9	3	17	6.4	102.4	-	-	90.4	9.2	-	SW-SM	
	6	35-45*	-	-	-	-	96.6	16.6	-	SM	
	11	59-77*	-	-	49	32	-	-	-	CI	
	13	82	23.6	90.5	41	24	100	68.6	30	(CL)	
	15	87-94*	-	-	-	-	86.8	12.7	6	SM	
	17	95-105*	-	-	-	-	87.1	10.2	4	SP-SM	
	MC-1	145	5.9	107.9	-	-	94.6	23	-	SM	3.50E-05
C-10	1	0-15.5*	-	-	-	-	93.5	7.9	5	SP-SM	
	2	16	1.9	115.6	-	-	93.2	7.8	-	SP-SM	
	2	17-30	-	-	-	-	97.5	10.8	7	SP-SM	
	4	30-63*	-	-	-	-	97.1	5.8	-	SP-SM	
	5	63-93*	-	-	-	-	91.2	5.7	3	SP	
	9	95	-	-	-	-	98.4	12.4	8	SP-SM	
	10	100	2.1	115.8	-	-	91.3	9.5	-	SP-SM	
	12	104-121*	-	-	-	-	98	16.2	11	SM	
	13	122-139*	-	-	-	-	78.4	7	5	(SP-SM)g	
	34	175-191*	-	-	-	-	99.6	8.4	7	SP-SM	
	17	191-198*	-	-	-	-	73.4	8	6	(SP-SM)g	
	18	198	2.8	100.5	-	-	66.9	5.6	-	(SP-SM)g	
	20	207-240*	-	-	-	-	94.5	15.7	8	SM	
	21	240-260*	-	-	-	-	93.7	12.1	6	SP-SM	
	22	260-280*	-	-	-	-	99	10.5	-	SP-SM	
	29	339	0.4	110.3	47	24	100	63.6	53	(CL)s	
	34	428-442*	-	-	61	31	100	91.3	50	CH	
	35	442-453*	-	-	59	32	100	48.3	35	CH	
	37	469-470*	-	-	59	37	99.6	86.7	70	CH	
	39	500-520	-	-	51	29	98.2	80.4	59	(CI)s	

*grab sample

**Shelby Tube sample

Principles of **Geotechnical Engineering**

Fifth Edition



Braja M. Das

ity
 have been pro-
 efficient), Hazen
 y in the form

(6.23)

ose, clean, filter
 soil, may change
 ductivity for fine-

(6.24)

timating the hy-
 n equation. The
 s are referred to
 plication of the

(6.25)

ation can be re-

(6.26)

w conditions may
 be valid for these
 onditions usually
 on granular soils
 to 25.4 mm. The
 o 12. All perme-
 ese tests showed

(6.27)





Figure 6.8
 Results of permeability tests on which
 Eq. (6.27) is based: (a) results for $C_u = 1-3$;
 (b) results for $C_u > 3$ (after Kenney, Lau, and
 Ofoegbu, 1984)

where D_5 = diameter (mm) through which 5% of soil passes. Figures 6.8a and 6.8b show the results on which Eq. (6.27) is based.

On the basis of laboratory experiments, the U.S. Department of Navy (1971) provided an empirical correlation between k (ft/min) and D_{10} (mm) for granular soils with the uniformity coefficient varying between 2 and 12 and $D_{10}/D_5 < 1.4$. This correlation is shown in Figure 6.9.




Figure 6.9 Permeability of granular soils (after U.S. Department of Navy, 1971)

According to their experimental observations, Samarasinghe, Huang, and Drnevich (1982) suggested that the hydraulic conductivity of normally consolidated clays (see Chapter 10 for definition) can be given by

$$k = C_3 \left(\frac{e^n}{1 + e} \right) \quad (6.28)$$

where C_3 and n are constants to be determined experimentally. This equation can be rewritten as

$$\log[k(1 + e)] = \log C_3 + n \log e \quad (6.29)$$

Hence, for any given clayey soil, if the variation of k with the void ratio is known, a log-log graph can be plotted with $k(1 + e)$ against e to determine the values of C_3 and n .

Some other empirical relationships for estimating the hydraulic conductivity in sand and clayey soils are given in Table 6.3. One should keep in mind, however, that any empirical relationship of this type is for estimation only, because the magnitude of k is a highly variable parameter and depends on several factors.

Tavenas et al. (1983) also gave a correlation between the void ratio and the hydraulic conductivity of clayey soil. This correlation is shown in Figure 6.10. An important point to note, however, is that in Figure 6.10, PI , the plasticity index, and CF , the clay-size fraction in the soil, are in *fraction* (decimal) form.

Table 6.3 Empirical Relationships for Estimating Hydraulic Conductivity

Type of Soil	Source	Relationship ^a	Comments
Sand	Amer and Awad (1974)	$k = C_2 D_{10}^{2.32} C_u^{0.6} \frac{e^3}{1 + e}$	
	Shahabi, Das, Tarquin (1984)	$k = 1.2 C_2^{0.735} D_{10}^{0.89} \frac{e^3}{1 + e}$	Medium to fine sand
Clay	Mesri and Olson (1971)	$\log k = A' \log e + B'$	
	Taylor (1948)	$\log k = \log k_0 - \frac{e_0 - e}{C_k}$ $C_k \approx 0.5e_0$	For $e < 2.5$,

^a D_{10} = effective size
 C_u = uniformity coefficient
 C_2 = a constant
 k_0 = *in situ* hydraulic conductivity at void ratio e_0
 k = hydraulic conductivity at void ratio e
 C_k = permeability change index




Figure 6.10 Variation of void ratio with hydraulic conductivity of clayey soils (based on Tavenas et al., 1983)

Eagle Mountain Pumped Storage Project Seepage Recovery Assessment

Prepared by: Richard Shatz [C.E.G. 1514], David Fairman, Donghai Wang, Ph.D., P.E.,
GEI Consultants, Inc.

May 13, 2009, Revised November 24, 2009, February 2012.

Introduction

Eagle Crest Energy Company (ECEC) is in the licensing stages of a two reservoir hydroelectric project known as the Eagle Mountain Pumped Storage Project (Project). The Colorado River Aqueduct (CRA) passes within about one mile east of the Lower Reservoir, and is located between the reservoir and the proposed location of the groundwater supply wells, near Desert Center, that will be used to draw water for the initial fill and annual makeup water for the reservoirs. The potential effects of Project operations on groundwater elevations beneath the CRA are of particular interest, since significant changes in the subsurface saturated conditions could result in land subsidence and impact the integrity and function of the CRA.

Two particular groundwater-related issues associated with the Project are: 1) the potential effects of groundwater extraction in the Desert Center area as water supply for the initial filling and replacement of annual losses from evaporation and seepage; and 2) the potential effects of seepage from the reservoirs. The first issue is addressed in a separate memorandum titled *Groundwater Supply Pumping Effects*, dated April 20, 2009. This memorandum describes the approach and results to address the second issue, the potential impacts of seepage from the reservoirs on groundwater levels.

Approach

This technical memorandum provides an assessment of the groundwater impacts due to seepage, and seepage recovery schemes to address the Lower and Upper reservoirs separately. Different approaches are required to address the Lower and Upper reservoirs since subsurface conditions are dramatically different. The Lower Reservoir is partially situated on unconsolidated alluvium and is evaluated using a groundwater flow model to develop a seepage recovery system design. The Upper Reservoir sits atop fractured bedrock, and a seepage recovery system is defined by performing a review of known faults that intersect the reservoir footprint.

For the Lower Reservoir, the model set-up, analysis results, and proposed seepage recovery design are discussed. For the Upper Reservoir, this memo includes a description of the geology beneath the reservoir and the proposed seepage recovery system. A groundwater model was not developed for the Upper Reservoir as application of the model would require data that does not currently exist.

Lower Reservoir Seepage Assessment

Portions of the Lower Reservoir overlie saturated alluvium, while the remainder sits atop fractured bedrock. A groundwater model was developed to assess the effects of seepage

from the reservoir on local groundwater conditions for the portion overlying saturated alluvium. Because of the close proximity of the bedrock to the saturated alluvium it was assumed that the faults and fractures would be hydraulically connected to the alluvium.

Upon review of the geologic conditions at the Project site, it was decided that a numerical model built in MODFLOW would be the most cost-effective and beneficial approach to evaluating groundwater conditions in the vicinity of the CRA. The model was developed using MODFLOW-2000 (version 1.18.00, released on 8/23/2007).

Modeling Goals and Objectives

Upon filling of the Lower Reservoir, some seepage from the reservoir is expected. That seepage needs to be controlled to prevent adverse changes in water elevations beneath the CRA that could cause subsidence and hydrocompaction.

The model objectives are to:

- Create a model that can accurately simulate current groundwater conditions in the vicinity of the Lower Reservoir and the CRA based on the available data.
- Evaluate the impacts of seepage from the Lower Reservoir into the saturated alluvium.
- Simulate the effects of seepage recovery wells to capture the seepage lost from the Lower Reservoir.
- Prepare a plan for the seepage recovery array to adequately capture Lower Reservoir seepage, but not significantly raise or depress the groundwater elevations beneath the CRA.

This analysis defines an optimum number and spacing of the recovery wells, and presents hydrographs at hypothetical observation wells located adjacent to the CRA to document the effects of seepage/pumping on the CRA. The potential impacts of seepage from the Lower Reservoir and extraction from the seepage recovery wells were determined by comparing the baseline model results with those of the different scenarios.

Final design of the monitoring and recovery well system will be based upon a refined modeling effort during final engineering design based upon measured aquifer hydraulic characteristics. The model developed for this evaluation can be re-applied to support the final design phase.

Hydrogeology

Figure 1 shows the general project area. The regional hydrogeology and the basis for model development are based on:

- Descriptions of geologic conditions in the Lower Reservoir (CH2MHill, 1996).
- Water elevations obtained from monitoring wells constructed for the Eagle Mountain Landfill and Recycling Center Project.
- Subsurface logs from coring performed for the Eagle Mountain Mine.
- Well drillers' logs from Eagle Mountain Mine water supply wells.
- Cross-sections developed by ECEC, shown on Figures 2 and 3.

- Cross-sections developed by GeoPentech for a groundwater banking project in the area, shown on Figures 4 and 5.
- Geophysical survey (gravity survey) from GeoPentech shown on Figure 6.

The regional hydrogeology is characterized by fractured bedrock at the surface, with recent and older alluvium overlapping onto the sloping surface of the bedrock. The alluvium is part of the Chuckwalla Groundwater Basin. The alluvium in the upper portions of the Chuckwalla Groundwater Basin can be grouped into three units with similar sediments and hydraulic parameters. Figures 2 through 5 show the geologic layering of the alluvial sediments in the vicinity of the Lower Reservoir.

The first alluvial layer is about 300 feet thick and consists of sand and gravel with a few discontinuous layers of silt and clay. Approximately 150 feet of the alluvium is saturated. Exposures of the alluvium in the eastern face of the Lower Reservoir were described as a coarse fanglomerate (CH2MHill, 1996). Underlying the first layer are lake deposits consisting primarily of clay. The lakebed thickness varies and may be thinner near the margins of the basin and thicker towards the central portions of the basin based on geophysical surveys (gravity). However, no wells have fully penetrated the lakebeds to determine their actual thickness. One well (CW-1) penetrated over 900 feet of clayey lakebed deposits before being terminated. The lakebed deposits are potentially underlain by coarser sediments, based on geophysical surveys, but there are no wells to confirm the presence of this layer (GeoPentech, 2003). The sediments are likely to have a lower permeability than the first alluvial layer because of compaction and development of clay due to weathering.

The alluvial sediments were deposited on an irregular bedrock surface. Geophysical surveys suggest the bedrock surface is a large bowl opposite the reservoirs (GeoPentech, 2003). The southern edge of the bowl aligns with a narrow bedrock ridge that juts easterly into the basin. The upper coarse-grained sediments were deposited above the bowl rim, whereas the lakebed sediments are below the rim. This configuration would create confining conditions in the underlying coarse sediment and prevent outflow from these sediments. The northern edge of the bowl connects to the Pinto Groundwater Basin where inflow into the Chuckwalla Groundwater Basin occurs. A basalt flow and several faults are present, as shown on Figure 4, but their effects on groundwater levels are not defined.

The bedrock beneath the Lower Reservoir is broken by the inactive East Pit Fault. The East Pit Fault appears to offset the bedrock by about 300 feet, which creates a near vertical bedrock contact on the western side of the valley starting near the reservoirs and extending to the south. Figure 2 shows the difference in the bedrock surface. West of the fault the alluvium is thin and unsaturated. Portions of the CRA, south of hypothetical monitoring well OW03 (Figure 1), rests on this unsaturated alluvium. The East Pit fault consists of about a 30-foot zone of broken rock and is in hydraulic continuity with the alluvial deposits.

Groundwater level measurements near the reservoirs are available for a two-year period between 1992 and 1994, after the time when significant pumping for the Eagle Mountain Mine and jojoba agricultural activities occurred in the 1960's through the 1980s. The measurements occurred during a period when there were no quantifiable or significant stresses applied to the aquifer that could be used for calibration. There was some pumping in the Desert Center area for domestic uses and limited agricultural uses during this period.

Groundwater occurs in the sediments above the lakebeds at a depth of about 25 feet below the lowest point in the East Pit, in the west bowl. The west bowl of the East Pit is the western portion of the East Pit, and is outside and to the west of, the portion of the East Pit proposed

to be used for the project's lower reservoir. The groundwater surface generally is deeper, progressing easterly into the valley. The nature of the sediments infer – and groundwater levels show – that the aquifer is unconfined.

Only one groundwater level measurement is available for the lakebed deposits at groundwater monitoring well (C-10) located near the eastern edge of the model area. It showed the groundwater level was about 60 feet below the top of the clay surface and over 200 feet below the water surface in the overlying sediments as shown on Figure 4. There is great uncertainty regarding this single data point due to this significant difference.

No groundwater levels are available for the coarse-grained sediments underlying the lakebeds. If present, this aquifer would be confined.

The groundwater flow direction in the alluvium is relatively uniform while flow in the bedrock is variable. Figure 1 shows the groundwater flow directions. The flow direction in the saturated alluvium above the lakebeds is generally to the southeast (CH2MHill, 1996). Groundwater flow in the bedrock is towards the Eagle Creek Canyon, from both the northwest and southwest.

Hydraulic characteristics of the sediments overlying the lakebeds were estimated during the investigation for the landfill. The hydraulic conductivities were estimated to be between 0.02 and 7.1 feet per day as shown in Table 1. Descriptions of the fan conglomerate from monitoring well construction describe the sediments as ranging from boulders to coarse sand, and therefore the estimated K appear to be too low. Typical K values for well-sorted sand and gravel are from 3 to 180 feet/day (Fetter, 1988). Because the fan conglomerate are part of older continental deposits and could be weathered and compacted, a conservative K of 25 feet per day and an S of 0.05 were used in the model.

Conceptual Model

The model area was defined to include both the Upper and Lower Reservoirs, but is centered on the Lower Reservoir and the closest portion of the CRA as shown in Figure 1. The area modeled is the alluvial aquifers, which will extend from the alluvium–bedrock contact at the Lower Reservoir to about 2 miles east of the CRA. As described above, the model is only set up to simulate groundwater conditions for the portion of the model area overlying saturated alluvium, with the portion of the model overlying bedrock, including the Upper Reservoir, designated as *inactive*. The following assumptions were made in development of the model:

1. A 3-layer model simulates the geologic conditions present in the vicinity of the reservoir. Layer 1 represents the saturated alluvium above the lakebeds, Layer 2 represents the lakebeds, and Layer 3 represents the underlying coarse-grained sediments.
2. The model is run under steady-state conditions because of the short period of available groundwater level measurements, and those data obtained during a period when there was little to no stress on the aquifer to calibrate the model.
3. The model boundaries are generally oriented to be parallel and perpendicular with the regional groundwater flow direction in the alluvial basin.
4. Layer 3, the confined aquifer, has no outflow, either naturally or by pumping wells. The aquifer is full and water is neither flowing into nor out of the aquifer. Therefore, assigning very small hydraulic conductivities is appropriate to both Layers 2 and 3,

essentially making the model a 1-layer model at this time. The deeper layers are built into the model for use during final engineering design.

5. The upgradient and downgradient boundaries are specified to keep the system in balance under current conditions so the seepage from the Lower Reservoir can be added after the model performance is verified.
6. Seepage from the reservoir instantaneously percolates through the unsaturated sediments and reaches the groundwater surface.
7. There are no other sources or outflows of water such as wells, streams, evaporation, or precipitation.

Model Development

The groundwater flow model was developed as follows.

Model Grid

The model cells are square, with a two-step nodal spacing. The node spacing in the central portion of the model area, which is in the vicinity of the Lower Reservoir and the closest stretch of CRA, is 200 feet by 200 feet. The node spacing expands to 400 feet by 400 feet for the extremities of the model area. Figure 7 shows the model grid.

Layers

The model was constructed with three layers to simulate the hydrogeologic conditions in the Upper Chuckwalla Groundwater Basin. Layer 1 is the saturated sands and gravels above the lakebeds. Layer 2 is the lakebed deposits. Layer 3 is the coarse sediments that may underlie the lakebeds.

The top of Layer 1 is the groundwater surface and was determined from the general gradient in the area and extrapolated as a uniform planar surface to best fit actual groundwater elevations, particularly in those areas close to the reservoir and aqueduct as shown on Figure 8. Given the limited measurements available, Layer 1 has been assigned a uniform thickness of 150 feet over the entire modeled area. This assumed thickness resulted in a reasonable fit to the few clay surface elevations shown on Figure 9. Layer 1 slopes to the southeast with edges partially controlled by the bedrock contact and partially by no flow and constant head boundaries as discussed in the Boundary Conditions section of this memo.

The lakebed deposits extent is poorly defined and may have a variable thickness as shown on Figures 4 and 5. Because of the limited data points available an average and uniform thickness of 400 feet was used to create Layer 2. Definition of Layer 3 is also limited, so an average and uniform thickness of 850 feet was used. Both Layer 2 and Layer 3 surfaces were assumed to be parallel to the top of Layer 1. Both layers were created to extend throughout the modeled area.

Seepage Infiltration

The average seepage from the Lower Reservoir assuming a 0.5 foot thick seepage blanket is constructed would have seepage losses of about 890 acre-feet per year (AFY), or about 550 gpm (GEI, *Seepage Analyses for Upper and Lower Reservoirs*, dated January 5, 2009). The maximum seepage would be about 1,600 AFY if only limited seepage control improvements were made. For the current analysis, the average seepage was distributed evenly over the eastern portion of the reservoir overlying alluvium, even though it is possible that some of the seepage could migrate through the bedrock via the crushed zone of the East Pit Fault.

Based on this interpretation of the subsurface conditions, it appears the fault intersects the alluvium near the Lower Reservoir. To simplify the modeling approach and provide a reasonable worst-case scenario, all seepage is assumed to be entering the system through the alluvial sediments.

Aquifer Parameters

Layer 1 was assigned a hydraulic conductivity (K) of 25 feet per day (ft/day) and a storativity (S) of 0.05. Layers 2 and 3 were assigned a $K = 3 \times 10^{-6}$ ft/day (1×10^{-9} centimeters per second) and $S = 0.0001$, which creates an essentially impermeable lower boundary for Layer 1. The aquifer characteristics of these deeper layers may be adjusted based upon measurements made to support final engineering design.

Initial and Boundary Conditions

The model is oriented such that the east and west boundaries are parallel to the direction of groundwater flow and therefore are no-flow boundaries. The upgradient and downgradient boundaries are general head boundaries assuming a total volumetric flow of 6,625 AFY (estimated outflow through the southern edge of the modeled area) through the system (790,120 ft³/day), and an aquifer thickness of 150 feet. The flow was distributed across an up gradient length of 20,600 feet and across a down gradient length of 14,600 feet. The down gradient length is shorter due to the model area coinciding with a bedrock ridge that juts easterly into the valley.

The initial heads for Layer 1 were based on groundwater levels measured in monitoring wells constructed for the landfill. A uniform planar surface was developed that provided a best fit near the Lower Reservoir. Because Layers 2 and 3 have no hydraulic head measurements the heads were assumed to be at the top of Layer 2.

Modeling Runs

The overall approach to simulating the groundwater conditions in the vicinity of the Lower Reservoir and CRA was performed using the model runs outlined below. All runs are steady-state simulations.

Run 1 – Simulate current groundwater conditions and compare results of model analysis with current groundwater elevations interpolated by observation wells to evaluate the model performance.

Run 2 – Add seepage from the Lower Reservoir to Run 1 and observe changes in water elevations around the reservoir and at simulated observation wells along the CRA.

Run 3 – Add seepage recovery wells to Run 2 and observe changes in water elevations around the reservoir and at simulated observation wells along the CRA.

Transient simulations were performed for both Runs 2 and 3 to develop hydrographs showing the projected changes in groundwater levels beneath the CRA and when steady state conditions are reached. This allows the timing of groundwater changes in response to seepage, and seepage mitigation, to be evaluated. Water balance results for each modeling run are also provided.

Run 1 - Model Performance

The model performance was evaluated by observing the model's ability to replicate the current groundwater conditions using the given aquifer parameters, boundary conditions, and initial conditions. General agreement was observed between the initial groundwater gradient and the steady-state elevations simulated by the model after Run 1. As shown on Figure 10,

the up gradient and down gradient elevations were accurately estimated and the model reasonably matched the uniform initial gradient.

It was expected that the uniform gradient projected over the entire alluvial portion of the model would not be as accurately replicated near the encroaching bedrock contact along the southwestern portion of the model since the extrapolated gradient does not take into account the no-flow boundary effects. It would appear that the model better approximated the groundwater elevations in this area. Overall, the model appears to reasonably replicate the current groundwater conditions in the alluvial area.

Run 2 – Seepage

Run 2 was performed following verification of the model's ability to replicate the current groundwater conditions. The purpose of Run 2 was to assess the impacts of seeping 890 AFY from the Lower Reservoir on groundwater elevations and did not include seepage recovery wells. The estimated seepage is based on the analysis found in the Technical Memorandum on Seepage (Section 12.5). Run 2 is based on an assumed placement of a 5-foot thick liner consisting of grouting, seepage blanket, and RCC or soil cement treatment over alluvium.

As shown in Figure 11, Run 2 showed that a groundwater mound is created in the vicinity of the Lower Reservoir and a rise in groundwater elevations occur across the model. Groundwater levels rose about 8 feet beneath the reservoir, far less than the 25 feet of unsaturated alluvium. A series of hypothetical observation wells were placed along the CRA as monitoring points to evaluate groundwater elevation changes. As shown on Figures 12 through 14, groundwater elevations at the closest observation well, OW05, rose 1.88 feet in response to seepage from the Lower Reservoir. Down gradient observation well OW03.2 rose about 2.65 feet.

A transient analysis was performed to evaluate the change of groundwater elevations over time. Figure 12 showed that groundwater elevations at OW05 rose 1.64 feet (87 percent of elevation change at steady state) after three years in response to seepage from the Lower Reservoir, and reached 1.87 feet (99 percent) after 10 years.

Run 3 – Seepage Recovery and Alternatives Evaluation

Run 3 consisted of multiple runs varying the number, pumping rates, and preliminary locations of the seepage recovery wells. In all runs the seepage from the reservoirs was captured, using 5 to 7 wells, but the drawdown beneath the CRA varied from about 1 to 4 feet. Consideration was given to placement of the wells away from the reservoir to effectively capture the seepage. Model Run 2 showed that a saturated mound would not rise high enough to connect to the reservoir bottom. Therefore, the seepage will migrate mostly vertically through unsaturated alluvium before reaching the water surface. To allow the seeped water to reach the groundwater surface the recovery wells' array design consisted of six wells distributed about 1500 to 2000 feet from the eastern and southern edges of the Lower Reservoir at a spacing of about 1000 feet, each pumping 92 gpm. The locations of the wells are shown on Figure 15. Figure 16 shows the results of Run 3. Groundwater elevations in the vicinity of the CRA were maintained between 0 and 3 feet below the initial groundwater conditions. Pumping the seepage recovery wells would result in less than 6 feet of drawdown in these wells.

A transient analysis was performed to evaluate the change of groundwater elevations over time. Figures 12 through 14 show that the seepage recovery wells reduced the water elevations at OW05 to 1.86 feet (89 percent of elevation change at steady state) below the

initial groundwater elevations after three years, and reached 2.08 feet (greater than 99 percent) after 10 years. The other observation wells reached steady state conditions in a similar time frame.

Water Balances

Figure 17 shows the mass balance for all three runs. The inflow and outflow values are within a fraction of a percent of each other, indicating that model parameters are being accounted for and the model is valid.

Landfill Compatibility

The water surface elevation in the Lower Reservoir will range from elevation 925 and 1,092 feet msl. The landfill is proposed to be constructed in four phases. Phases 1 through 3 will be constructed at elevations above the lower reservoir's maximum water surface elevation and therefore cannot be affected by the seepage from the lower reservoir. Phase 4 is located to the north of the lower reservoir and its foundation finish grade at its lowest point is about 1,040 feet msl (about 800 feet from the reservoir), below the maximum reservoir water surface. This portion of the landfill is being built at least in part over the older alluvium exposed in the eastern portion of the Lower Reservoir, however the area is currently covered by tailing piles so the exact extent of the alluvium is unknown.

The groundwater model covered this area and can approximate the change in the groundwater level beneath this portion of the landfill. Groundwater levels directly beneath the reservoir, if not controlled by seepage recovery wells, would be expected to rise a maximum of 8 feet. Existing monitoring well MW-1 is the closest monitoring well in the alluvium to Phase 4. The groundwater elevation in well MW-1 was 706 feet msl in 1992. The water surface elevation with uncontrolled recharge mounding, projects to be about 714 feet elevation, far below the landfill foundation. With seepage control wells, as shown on Figure 16, groundwater levels are expected to change by about one to four feet.

Upper Reservoir Seepage Assessment

The Upper Reservoir is entirely underlain by bedrock. The bedrock is fractured and seepage from the Upper Reservoir will likely be through these fractures. These groundwater conditions do not readily lend themselves to modeling. Therefore, a geologic assessment of the major faulting pattern was prepared to develop a preliminary seepage recovery well network to capture all of the seepage from the Upper Reservoir.

Hydrogeology

Bedrock geologic units present at the site can be generally classified as igneous or meta-sedimentary (including the iron ore) with little to no primary permeability. The meta-sediments have been folded into an anticline with the Upper Reservoir on the north limb. Subsequent to the folding and fracturing volcanic dikes intruded the rock in a northeast-southwest trend.

Fracturing and faulting of the rock created secondary permeability that can convey water from the reservoir. Geologic mapping of the Upper Reservoir was performed prior to the excavation of the pit by the Eagle Mountain Mine and shows the location of the major faults. Figure 18 shows the location of these major faults (digitized from Proctor, 1992). For purposes of this analysis, it was assumed that the fractures would be connected to these major faults. The faults near and beneath the Upper Reservoir (Fault "A") have a similar northwest-southeast trend to the East Pit Fault, which crosses through the Lower Reservoir. Although no dips are provided for faults in the Upper Reservoir it is believed they would be similar to the East Pit Fault, which is nearly vertical (dips about 80 degrees to the east).

Two borings were completed in the Upper Reservoir site vicinity (MW-10 and CH-10). Rock core obtained from boring CH-10 provides insights on the hydrogeologic character of the bedrock. The boring was drilled to a total depth of 1,389 feet. Water was first observed at a depth of 1,309 feet. Rock in the upper 350 feet of the boring was found to be moderately fractured, interbedded igneous and meta-sedimentary rock. Monitoring well MW-10 was drilled to a total depth of 1,214 feet. Water was first encountered at a depth of 506 feet. The water surface subsequently dropped and later stabilized at a depth of 1,018 feet. The observations suggest that water may be present in joints and fractures at various depths and that lower fractures are either dry or at lower heads.

The groundwater flow direction in the bedrock is regionally towards the southeast, in the direction of Eagle Creek Canyon as shown on Figure 1 (CH2MHill, 1996). It is possible there are either faults or fractures in the rock that are concealed beneath the thin alluvium in the canyon. Faults and fractures typically create weak zones where erosion can create canyons. The orientation of the canyon would suggest a fault or fracture could convey water to the east into the saturated alluvium where it could be captured by the Lower Reservoir seepage recovery wells.

The depth to groundwater in the bedrock beneath portions of the CRA is about 450 feet below ground surface, as shown on Figure 2. Groundwater levels in the bedrock would have to rise by about 180 feet before saturating the alluvium overlying bedrock.

Hydraulic Characteristics

Hydraulic characteristics of the bedrock joint and fractures were estimated during the investigation for the landfill. The hydraulic conductivities were estimated to be between 0.02 and 5.1 feet per day as shown in Table 1.

Few wells in the area obtain water from the fractured bedrock. The former Eagle Mountain school well (School Well) was drilled to a depth of about 750 feet before encountering adequate flow to support a small well. The well could be pumped at a rate of about 75 gpm.

Seepage

The Upper Reservoir may seep an average of 738 acre-feet of water annually or about 460 gallons per minute (GEI, *Seepage Analyses for Upper and Lower Reservoirs*, dated January 5, 2009). Raising and lowering of water levels in the reservoir during normal operations would allow some of the seepage, especially in the sidewalls, to drain back into the reservoir during low water level periods.

Seepage Recovery Wells

A preliminary seepage recovery network was designed assuming that the average well would be capable of pumping only 70 gallons per minute, similar to the School Well. About seven seepage recovery wells may be needed. Five of the seven seepage recovery wells were positioned around the Upper Reservoir outside of the landfill perimeter at currently known locations of faults that extend beneath the reservoir. Figure 18 shows the location of the proposed seepage recovery well system.

In addition to the seepage recovery well system near the Upper Reservoir, additional seepage recovery wells will be constructed along the axis of the Eagle Creek Canyon at the intersections of the faults that cross beneath the Upper Reservoir. These wells in conjunction with the wells near the Upper Reservoir will be used to maintain the water levels below the elevation of the liner for the proposed landfill operations in this area and to prevent a rise in groundwater levels in the bedrock beneath the CRA.

Conclusions

The results of the MODFLOW model for the Lower Reservoir indicate that groundwater levels in the vicinity of the CRA would increase by up to three feet by seepage from the Lower Reservoir if not controlled through seepage recovery wells. A preliminary seepage recovery well array design consists of six wells, each pumping 92 gpm, and resulted in capture of all of the seepage, with groundwater elevations only being reduced beneath the CRA by about three feet. The absolute elevations are reflected in Figure 13 with the elevation increasing from about 629 feet msl to about 632 feet msl without the network and decreasing from about 629 to 626 with the network. Although the seeped water could be allowed to flow unimpeded to offset drawdown related to water supply pumping, this does not allow for unanticipated conditions. Therefore, seepage recovery wells will be installed and equipped. Once the reservoirs are at full capacity and the actual operating conditions are observed, groundwater management alternatives will be employed to minimize groundwater level changes beneath the CRA.

The maximum seepage from the Lower Reservoir with limited seepage control improvements is estimated to be about 1,600 AFY, about double the average seepage that was analyzed in this assessment. Therefore, worst case projections would suggest the seepage, if not controlled by pumping, would raise groundwater levels by about 6 feet beneath the CRA. The seepage could be controlled by pumping wells.

Seepage from the Upper Reservoir will be along joints, fractures, and faults that cross beneath the reservoir. About seven seepage control wells will be needed to control the seepage losses, assuming they will each pump about 70 gpm. Since the faults are near-vertical angle drilling may be an effective method. Additional seepage recovery wells will be constructed along the axis of the Eagle Creek Canyon to provide secondary control to prevent groundwater levels from rising beneath this area of the proposed landfill.

Mitigation Measures

Mitigation SR-1:

Aquifer tests will be performed during final engineering design to confirm the seepage recovery well pumping rates and aquifer characteristics. The tests will be performed by constructing one of the seepage recovery wells and pumping the well while observing the drawdown in at least two seepage recovery or monitoring wells. If available, additional observation wells will be monitored. Upon completion of this testing the model will be re-run and the optimal locations of the remainder of the seepage recovery wells will be determined to effectively capture water from the Lower Reservoir and maintain groundwater level rises and drawdown at less than significant levels beneath the CRA.

Mitigation SR-2:

A testing program will also be employed for seepage recovery wells for the Upper Reservoir. However, the purpose of these tests is to assess the interconnectedness of the joints and fractures and the pumping extraction rate. Drawdown observations will be made in nearby observation wells to support final engineering design.

Mitigation SR-3:

A groundwater level monitoring network will be developed to confirm that seepage recovery well pumping is effective at managing groundwater levels beneath the CRA and in the Eagle Creek Canyon portion of the proposed landfill. The monitoring network will consist of both existing and new monitoring wells to assess changes in groundwater levels beneath the landfill and the CRA. In addition to the proposed monitoring wells, groundwater levels, water quality, and production will be recorded at the Project seepage recovery wells.

Mitigation SR-4:

Seepage from the upper reservoir will be maintained below the bottom elevation of the landfill liner. Seepage from the Lower Reservoir will be maintained to prevent significant rise in water levels beneath the CRA.

Alternative Mitigation Measure:

As shown in the analyses for the Project water supply well pumping assessment, the cumulative change in groundwater levels beneath the CRA (near OW03) over the 50-year life of the Project are projected to be drawn down by about 14 feet as a result of pumping for the proposed projects – pumped-storage project, landfill project, and solar projects – and other existing uses in the basin (GEI, 2009). The Project water supply pumping will result in about 6 feet of drawdown. Project pumping drawdown could be mitigated by managing seepage from the reservoirs, which, if left unimpeded, could raise groundwater levels by up to 3 feet. Implementation of this option would require confirmation of groundwater level rises and water quality of the resulting seepage.

Mitigation SR-5:

Groundwater monitoring will be performed on a quarterly basis for the first four years of Project pumping and thereafter may be extended to bi-annually or annually depending on the findings. Annual reports will be prepared and distributed to interested parties.

References

CH2M Hill, 1996. Eagle Mountain Landfill and Recycling Center Project, Produced for Riverside County and Bureau of Land Management.

GEI, January 5, 2009. Eagle Mountain Pumped Storage Project: Seepage Analyses for the Upper and Lower Reservoirs.


GEI, April 20, 2009. Groundwater Supply Pumping Effects.

GeoPentech, 2003. Upper Chuckwalla Groundwater Basin Storage, Draft Report (not for public release). Produced for Metropolitan Water District.

Greystone, 1994. Eagle Mountain Pumped Storage License Application. Produced for Eagle Crest Energy Company.

Proctor, Richard J., July 31, 1992. Largest Faults and General Geologic Units at Eagle Mtn. Landfill Site, Plate 1.

Figures



SEEPAGE RECOVERY MODEL AREA

Pumped Storage Project
Eagle Mountain, California



MARCH 2009


Eagle Crest Energy Company

FIGURE 1

EAGLE MOUNTAIN CROSS-SECTION C-C'

DIRECTION
S

DIRECTION
N




EAGLE MOUNTAIN PUMPED STORAGE
EAGLE MOUNTAIN, CALIFORNIA
EAGLE CREST ENERGY COMPANY

CROSS-SECTION C - C'

MARCH 2009

FIGURE 3

DRAFT



GeoPentech
 Groundwater Storage & Dry Year Supply
 Project Upper Chuckwalla Valley

- LEGEND**
- Granitics
 - Volcanics
 - ▽ Water Level Observed during drilling
 - ▽ Static Water Level Observed in Piezometers
- Geotechnical Boring**
- Predominantly Sand and Silty Sand Deposits
 - Sand with Gravel, Cobbles and Boulders
 - Predominantly Clay Deposits


File: SectionBRev2.grt

GEOPENTECH CROSS SECTION C-C'


MARCH 2009

Pumped Storage Project
 Eagle Mountain, California
 Eagle Crest Energy Company

FIGURE 4



Composite Basement Elevations



Source: GeoPentech 2003.

Pumped Storage Project
Eagle Mountain, California




Eagle Crest Energy Company

BEDROCK ELEVATION MAP
BASED ON BOUGOUR ANOMALIES

MARCH 2009

FIGURE 6



Pumped Storage Project
Eagle Mountain, California


Eagle Crest Energy Company



MARCH 2009

MODEL GRID

FIGURE 7




- Water Level Well or Boring
- Layer 1 Top (feet msl)
- Colorado River Aqueduct
- Fault (Proctor 1992)**
- Certain
- Approximately located
- Concealed
- Concealed, queried
- Inferred
- Inferred, queried
- Seepage Recovery Model Area
- Reservoir
- Groundwater Basin Boundary

Axis of Buried Ridge



S:\GIS\Projects\083850_EagleMtn_gwmodeling\Layer1_top.mxd DLF 30-Mar-2009



- Clay Elevations
- Layer 1 Bottom (feet msl)
- Colorado River Aqueduct
- Fault (Proctor 1992)**
- Certain
- - - Approximately located
- - - ? Approximately located, queried
- Concealed
- ? Concealed, queried
- - - Inferred
- - - ? Inferred, queried
- ▭ Seepage Recovery Model Area
- ▨ Reservoir
- ▭ Groundwater Basin Boundary



Axis of Buried Ridge

S:\GIS\Projects\083850_EagleMtn_gwmodeling\Layer1_bottom.mxd DLF 30-Mar-2009

Pumped Storage Project
Eagle Mountain, California




BOTTOM OF LAYER 1

MARCH 2009

FIGURE 9

Eagle Crest Energy Company

30-Mar-2009 S:\GIS\Projects\083850_EagleMtn_gy modeling\ModelRun1.mxd DLF



— Layer 1 Top (feet msl)
- - Run 1

Pumped Storage Project
Eagle Mountain, California


Eagle Crest Energy Company



LAYER 1 INPUT AND
MODEL RESULTS RUN 1

MARCH 2009

FIGURE 10



Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy Company



MODEL RESULTS RUNS 1 AND 2

MARCH 2009

FIGURE 11

FIGURE 12
GROUNDWATER LEVEL CHANGE OVER TIME AT OW03.2




FIGURE 13
GROUNDWATER LEVEL CHANGE OVER TIME AT OW04







FIGURE 14
GROUNDWATER LEVEL CHANGE OVER TIME AT OW05





SOURCE: Background image is INAIP 2005.




Pumped Storage Project
Eagle Mountain, California
Eagle Crest Energy Company



LOCATION OF SEEPAGE RECOVERY WELLS

MARCH 2009

FIGURE 15



— Run 1
— Run 3
○ Seepage Recovery Well

Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy Company




MODEL RESULTS RUNS 1 AND 3


MARCH 2009

FIGURE 16


Figure 17 Mass Balance for Three Model Runs





Unit for the flow rate is ft³/day



* = 890 AFY



- ▲ Existing Well
- ◆ Existing Well to be used for monitoring
- ▲ Proposed New Monitoring Well
- Seepage Recovery Well
- Proposed New Extensimeter
- Colorado River Aqueduct



Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy Company



MITIGATION AND MONITORING NETWORK

APRIL 2009

FIGURE 18

09-Apr-2009 S:\GIS\Projects\083850_Eagle\Mn_gwmodeling\SeepRecovNetwork.mxd

Tables

Table 1
Aquifer Characteristics Near Project Site

Well No./Name	Aquifer Material	Screen Interval (feet bgs)	Flow Rate (gpm)	Drawdown (feet)	Saturated Aquifer Thickness (feet)	Hydraulic Conductivity (ft/day)	Transmissivity (gpd/ft)
MW-1	Alluvium	325 - 385			51	7.1	2,700
MW-2	Alluvium	394-455	33	37	65	0.02	10
MW-2					65	0.37	180
MW-3	Bedrock	289 - 350	3.3	33			200
MW-4	Bedrock	60 - 140	3.5	47	40	0.02	6
MW-4					40	0.50	150
MW-5	Alluvium	180 - 240	20	25	30	2.0	450
MW-5					30	2.2	500
MW-5					30	7.1	1,600
MW-6	Bedrock	560 - 620	5	12	65	0.1	50
					65	1.4	680
					65	1.8	870
School Well	Bedrock	475-740	75	11	265	0.5	1,000
					265	5.1	10,105

Source: CH2MHill, 1996

TABLE 2

Proposed Mitigation Well Network and Maximum Allowable Changes From Seepage Recovery Pumping¹

Existing Monitoring Wells or Piezometer

Well No./Name	Aquifer Material	Monitoring Purpose	Total Borehole Depth (feet)	Borehole Diameter (inches)	Casing Diameter (inches)	Screen Interval (feet bgs)		Maximum Allowable Drawdown (feet)	Maximum Allowable Water Elevation (feet msl)
						Top	Bottom		
P-2	Bedrock	Water Level Beneath Landfill	960	6.5	2	905	955		1,620
P-3	Bedrock	Brine Pond Downgradient	675	6.0	Unknown	613	663		
P-4	Bedrock	Brine Pond Upgradient	625	5.5	Unknown	575	625		
P-5	Bedrock	Brine Pond Upgradient	625	5.5	Unknown	575	625		
P-9	Bedrock	Lower Reservoir Seepage	525	5.6	Unknown	470	520		
P-10	Bedrock	Upper Reservoir Seepage	675	5.6	Unknown	625	675		
P-11	Alluvium	Lower Reservoir Seepage	485	5.5	Unknown	350	470	2	
MW-7	Bedrock	Water Level Beneath Landfill	785	10.6	4	666	726		1,560
MW-8	Bedrock	Water Level Beneath Landfill	871	13.5	Unknown	792	844		1,880
MW-9	Bedrock	Water Level Beneath Landfill	1,544	6.5	Unknown	Unknown	Unknown		2,350
MW-11	Bedrock	Water Level Beneath Landfill	1,130	13.5	Unknown	663	917		1,940
Kaiser MW	Alluvium	CRA	Unknown	Unknown	Unknown	Unknown	Unknown	3	

Existing Monitoring Wells to be Replaced

P-1R	Alluvium	Lower Reservoir Pumping Contol	550	10	4	490	540	6	
MW-4R	Bedrock	Background Lower Reservoir	774	10	4	704	764		
MW-5R	Alluvium	Lower Reservoir Pumping Contol	418	10	4	348	408	6	
MW-10R	Bedrock	Background Upper Reservoir	1,672	10	4	1,558	1,662		1,464

New Monitoring Wells to be Constructed

MW-101A	Alluvium	Brine Pond Downgradient	110	10	4	60	100	dry	
MW-101B	Bedrock	Brine Pond Downgradient	599	10	4	549	589		
MW-102A	Alluvium	Brine Pond Downgradient	110	10	4	60	100	dry	
MW-102B	Bedrock	Brine Pond Downgradient	658	10	4	608	648		
MW-103A	Alluvium	Brine Pond Downgradient	200	10	4	150	190	dry	
MW-103B	Bedrock	Brine Pond Downgradient	658	10	4	608	648		
MW-104	Alluvium	Lower Reservoir Pumping Contol	575	10	4	525	565	6	
MW-105	Alluvium	Lower Reservoir Seepage	552	10	4	502	542	4	
MW-106	Alluvium	Lower Reservoir Seepage	383	10	4	333	373	4	
MW-107	Alluvium	Lower Reservoir Seepage	353	10	4	303	343	4	
MW-108	Alluvium	CRA	318	10	4	268	308	2	
MW-109	Alluvium	CRA	497	10	4	447	487	3	

Seepage Recovery Wells to be Constructed

Well No./Name	Aquifer Material	Purpose	Total Borehole Depth (feet)	Borehole Diameter (inches)	Casing Diameter (inches)	Screen Interval (feet bgs)		Maximum Allowable Drawdown (feet)	Maximum Allowable Water Elevation (feet msl)
						Top	Bottom		
SRW-01	Bedrock	Upper Reservoir Seepage Recovery	1,477	10	6	1,353	1,467		2,540
SRW-02	Bedrock	Upper Reservoir Seepage Recovery	1,421	10	6	1,297	1,411		586
SRW-03	Bedrock	Upper Reservoir Seepage Recovery	1,359	10	6	1,235	1,349		586
SRW-04	Bedrock	Upper Reservoir Seepage Recovery	1,297	10	6	1,173	1,287		586
SRW-05	Bedrock	Upper Reservoir Seepage Recovery	1,522	10	6	1,398	1,512		586
SRW-06	Bedrock	Upper Reservoir Seepage Recovery	696	10	6	614	686		940
SRW-07	Bedrock	Upper Reservoir Seepage Recovery	1,043	10	6	969	1,033		2,060
SRW-08	Alluvium	Lower Reservoir Seepage Recovery	650	18	12	493	640	7	
SRW-09	Alluvium	Lower Reservoir Seepage Recovery	495	18	12	328	485	7	
SRW-10	Alluvium	Lower Reservoir Seepage Recovery	645	18	12	463	635	7	1,560
SRW-11	Alluvium	Lower Reservoir Seepage Recovery	575	18	12	385	565	7	
SRW-12	Alluvium	Lower Reservoir Seepage Recovery	640	18	12	453	630	7	
SRW-13	Alluvium	Lower Reservoir Seepage Recovery	695	18	12	513	685	7	

Footnote: ¹ Drawdown projections solely due to Seepage Recovery Pumping

12.7 Schedule, Manpower, and Equipment Utilization During Construction of the Eagle Mountain Pumped Storage Project

Eagle Mountain Pumped Storage Project – Schedule, Manpower and Equipment Utilization During Construction

Prepared by: Richard Westmore, P.E., GEI Consultants, Inc.

April 9, 2009

Preparation of an environmental evaluation of the Eagle Mountain Pumped Storage Project under the National Environmental Policy Act (NEPA) and the California Environmental Quality Act (CEQA) includes an assessment of construction-related impacts associated with the project. These impacts typically include: air quality (fugitive dust and carbon emissions from construction equipment operation); noise generated during construction; night-time light “pollution”; water quality concerns (erosion and sedimentation entering surface water bodies, as well as hazardous spills that might affect surface and ground water supplies); and socio-economic impacts on the region. Assessment of these construction-related impacts requires an evaluation of the probable construction schedule and the estimated quantities of work (excavation, fill placement, concrete production and placement, tunneling by boring machine and conventional methods, etc.) to identify the types and numbers of equipment pieces that are likely to be used over time, as well as the required labor force.

At this early stage in project design and given the complexity of the Eagle Mountain Project, it is difficult to develop an overall schedule of equipment and man-power that will closely follow what actually will occur during construction. However, the estimates provided in Attachment 1 represent a reasonable estimate of the type, schedule and monthly use of construction equipment, as well as the monthly man-power utilization during construction of the project. These estimates are based on an overall construction period of about 4 years and engineering judgment and experience relative to construction methods and procedures.

The estimated construction schedule is provided on Figure 1. Key features of the estimated schedule are summarized below:

First Year of Construction

General:

- Mobilize and construct temporary office, storage, maintenance and staging facilities.
- Construct and improve permanent and construction access roads.

Water Conduits:

- Proceed and erect Tunnel Boring Machine and start excavation of tailrace tunnel.

Power Plant:

- Construct access tunnel portal and start excavation of access tunnel.

Upper Reservoir:

- Excavation of approach channel to inlet/outlet works.

Production Wells:

- Begin Construction

Lower Reservoir:

- Start moving unstable tailings pile.
- Start to line lower reservoir.

Monitoring Wells:

- Begin Construction

Switchyard:

- Start switchyard construction.

Transmission Line:

- Start construction of transmission line foundations.

Second Year of Construction

Upper Reservoir:

- Complete excavation of approach tunnel.
- Complete construction of the south and west dams.
- Start Construction of inlet/outlet structures.
- Start lining of Reservoir.

Production Wells:

- Complete Construction

Lower Reservoir:

- Complete moving unstable tailings pile.
- Seepage control liner blanketing.
- Construct inlet/outlet works.

- Install water pipeline from wells, pumping plant, and reverse osmosis system.
- Begin to fill lower reservoir.

Monitoring Wells:

- Complete Construction

Water Conduits:

- Complete tailrace tunnel, manifold and draft tube tunnels.
- Move and erect Tunnel Boring Machine and excavate upper pressure tunnel.
- Excavate lower pressure tunnel, manifold and penstock tunnels.
- Start to excavate pressure shaft.
- Start Installation of steel tunnel linings.

Power Plant:

- Complete majority of underground power plant access.
- Finish excavation of access tunnel.
- Excavate powerhouse cavern.
- Excavate transformer gallery caverns.
- Embed spiral cases and draft tube liners.
- Start to install pump/turbines and generators.
- Start first stage and second stage concrete.
- Start to install electrical and mechanical equipment.

Transmission Line:

- Build foundations and towers.
- String high voltage transmission wires.

Switchyard:

- Complete switchyard and install equipment.

Third Year of Construction

Upper Reservoir:

- Seepage Control by blanketing with fines and grouting.
- Complete inlet/outlet works.

Lower Reservoir:

- Continue filling lower reservoir.

Water Conduits:

- Finish excavation of pressure shaft.
- Construct downstream surge chambers.
- Concrete line penstock and draft tube manifolds.
- Install steel linings in penstocks and concrete linings in draft tube tunnels.

Power Plant:

- Complete excavation of transformer gallery caverns.
- Construct cable tunnel and shaft.
- Complete first stage concrete.
- Start and complete superstructure concrete.
- Continue installation of pump/turbines.

- Continue installation of motor/generators.
- Continue installation of other mechanical and electrical equipment.
- Install water delivery pipeline, pump, and reverse osmosis system.
- Installation of mechanical and electrical equipment.

Fourth Year of Construction

Power Plant:

- Finish installation of pump/turbines.
- Finish installation of motor/generators.
- Continue and Finish installation of other mechanical and electrical equipment.
- Start architectural construction.
- Start startup and testing of units.
- Commission unit 1.
- Commission units 2, 3 and 4 at three month intervals ending the beginning of April.
- Complete architectural work.

Transmission Line:

- Test and energize high voltage transmission line.


Commercial Operation:

- June 2016.

Attachment 1 is organized as follows:

- Bar chart showing the major features of the project construction and the estimated duration in months for construction.
- The schedule bar chart with an overlay graph showing the total number of persons working on the project per month. The peak work force is estimated to be 209 laborers. The total work force is estimated to be 4,674 person months over the duration of construction.
- The schedule bar chart with an overlay graph showing the total number of on-site equipment items, daily concrete trucks (on-site), and daily heavy trucks (on-site) required for the project per month. The peak monthly on-site equipment items are estimated to be 150 items. The peak daily concrete trucks (on-site) are estimated to be 210 trucks. This estimate assumes the trucks are traveling to and from an on-site batch plant. The peak daily heavy trucks (on-site) are estimated to be 258 trucks. This estimate assumes the trucks are hauling materials to and from locations on-site.
- The schedule bar chart with an overlay graph showing the total number of off-site trucks working on the project per month. The peak monthly off-site truck volume is estimated to be 75 trucks. The total off-site truck volume is estimated to be 925 trucks for the duration of construction. This estimate assumes the off-site trucks are importing the necessary construction materials to the site such as steel linings, steel reinforcement, electrical components, etc.

- The schedule bar chart with an overlay graph showing the total labor cost for staff working on the project per month. The peak monthly labor cost is estimated to be \$2.51 million.
- The schedule bar chart with an overlay graph showing the cumulative total labor cost for staff working on the project. The cumulative labor cost for the project is estimated to be \$58 million.
- A summary table showing the average crew size for each major feature of the project construction, the associated average duration in months, and the total number of person months for each item and for the complete project.
- A summary table showing the type and total number of equipment required for each major feature of the project construction.
- A summary table showing estimates of construction crew member's basic hourly wages and hourly wages including the contractor's overhead and profit.
- A summary table showing a typical pumped-storage project operations crew, and their associated annual salaries. Also shown is a table presenting the annual operations and maintenance costs expected to occur over the project duration.
- A table showing the typical equipment and task production rates used in calculations for the duration and quantity of equipment required for each major feature of the project construction.
- A list of major construction activities and items required for the pumped-storage project.
- Equipment and crew size calculation spreadsheets for each major feature of the project construction. Only project features with construction durations are presented.
- Tunnel excavation advancement rate calculation spreadsheet. The spreadsheet includes advancement rates for Tunnel Boring Machine (TBM) and Drill and Blast (D&B) excavation methods.
- Project features and cost estimate spreadsheet. Includes quantities and unit prices for major project features.
- Project reservoir filling calculations and associated charts.



Task	Progress	Summary	External Tasks	Deadline
Split	Milestone	Project Summary	External Milestone	



Eagle Mountain Pumped Storage Project
Eagle Mountain, California

Eagle Crest Energy

Project 080472



ESTIMATED PROJECT
CONSTRUCTION SCHEDULE

February 2009

Figure 1



ATTACHMENT 1


EAGLE MOUNTAIN PUMPED STORAGE PROJECT

SCHEDULE, EQUIPMENT, AND MAN POWER ESTIMATES


ESTIMATED CONSTRUCTION SCHEDULE EAGLE MOUNTAIN

Duration Months

0.0 6.0 12.0 18.0 24.0 30.0 36.0 42.0 48.0 54.0 60.0 66.0 72.0




ESTIMATED CONSTRUCTION SCHEDULE & MAN POWER EAGLE MOUNTAIN




ESTIMATED CONSTRUCTION SCHEDULE & EQUIPMENT EAGLE MOUNTAIN

Duration Months


0.0 6.0 12.0 18.0 24.0 30.0 36.0 42.0 48.0 54.0 60.0 66.0 72.0




ESTIMATED CONSTRUCTION SCHEDULE & OFFSITE TRUCKS PER MONTH EAGLE MOUNTAIN



ESTIMATED CONSTRUCTION SCHEDULE & MONTHLY LABOR COSTS EAGLE MOUNTAIN



ESTIMATED CONSTRUCTION SCHEDULE & CUMMULATIVE LABOR COSTS EAGLE MOUNTAIN



**ESTIMATED CONSTRUCTION WORK FORCE
EAGLE MOUNTAIN PUMPED-STORAGE PROJECT**

CONSTRUCTION SEGMENT	AVERAGE CREW SIZE (1)	AVERAGE DURATION (MONTHS) (2)	SHIFTS (3)		PERSON MONTHS (4)
			NUMBER	LENGTH (HRS)	
CIVIL CONTRACTOR MOBILIZATION	15	4	1	8	60
CONSTRUCT ACCESS ROADS	18	4	1	8	67
EXCAVATE POWER HOUSE ACCESS TUNNEL	23	12	1	8	268
EXCAVATE TAILRACE TUNNEL	26	8	1	8	199
EXCAVATE LOWER PRESSURE TUNNEL	16	6	1	8	101
EXCAVATE UPPER PRESSURE TUNNEL	29	6	1	8	166
EXCAVATE PRESSURE SHAFT	20	9	1	8	188
EXCAVATE TOP HEADING	27	4	1	8	100
ROOF ANCHORAGE AND LINING	6	3	1	8	17
EXCAVATE REMAINDER OF CAVERN	27	2	1	8	44
EXCAVATE TRANSFORMER GALLERY	18	3	1	8	49
EXCAVATE TAILRACE SURGE CHAMBER	16	6	1	8	103
EXCAVATE CABLE TUNNEL SHAFT	11	6	1	8	65
LINE AND PAVE CABLE TUNNEL	6	10	1	8	61
LINE PENSTOCKS AND DRAFT TUBE MANIFOLD	36	5	1	8	187
INSTALL STEEL TUNNEL LININGS	22	8	1	8	175
FIRST STAGE CONCRETE	19	6	1	8	105
INSTALL SPIRAL CASES AND DRAFT TUBE LINE	8	8	1	8	65
INSTALL PUMP TURBINES AND GENERATORS	8	11	1	8	89
EMBED SPIRAL CASES AND DRAFT LINERS	7	9	1	8	61
INSTALL MECHANICAL EQUIPMENT	9	6	1	8	54
INSTALL ELECTRICAL EQUIPMENT	8	6	1	8	48
COMPLETE CONCRETE WORK	15	9	1	8	140
STRUCTURAL AND ARCHITECTURAL CONSTRUCTION	30	13	1	8	394
ELECTRICAL AND MECHANICAL MOBILIZATION	15	3	1	8	46
COMPLETE ELECTRICAL CONSTRUCTION	8	13	1	8	107
EXCAVATE APPROACH CHANNEL - UPPER RESERVOIR	23	10	1	8	222
CONSTRUCT UPPER RESERVOIR DAM	38	8	1	8	320
MOVE UNSTABLE SOIL - LOWER RESERVOIR	19	13	1	8	242
LINE UPPER RESERVOIR	23	4	1	8	85
LINE LOWER RESERVOIR	18	5	1	8	95
CONSTRUCT I/O STRUCTURE - LOWER RESERVOIR	26	4	1	8	107
CONSTRUCT I/O STRUCTURE - UPPER RESERVOIR	27	4	1	8	105
SWITCHYARD EXCAVATION	10	3	1	8	31
SWITCHYARD FOUNDATIONS	11	4	1	8	45
SWITCHYARD STRUCTURES	9	1	1	8	13
TRANSMISSION LINE FOUNDATIONS	10	5	1	8	46
TRANSMISSION LINE STRINGING	7	4	1	8	28
TRANSMISSION LINE STRUCTURES	12	6	1	8	69
INSTALL WATER SUPPLY PIPELINE AND RO S	19	7	1	8	128
RESERVOIR FILLING	3	24	1	8	72
U-1 START-UP	7	3	1	8	22
U-2 START-UP	7	3	1	8	19
U-3 START-UP	7	3	1	8	19
U-4 START-UP	7	3	1	8	19
FINISH PROJECT	10	3	1	8	28
				TOTAL	4674

- (1) Average number of people on site during a construction activity, rounded to the nearest person.
(2) Estimated time to complete a construction activity if completed independent of other construction activities and without consideration of other construction and schedule constraints, rounded to the nearest month.
(3) Number and length of daily shifts.
(4) Rounded to nearest person month. One person month is equal to 173 hours. Calculated prior to rounding crew sizes and durations.

ESTIMATED CONSTRUCTION EQUIPMENT
EAGLE MOUNTAIN

TYPE OF EQUIPMENT	CIVIL CONTRACTOR MOBILIZATION	ACCESS ROADS	POWER HOUSE ACCESS TUNNEL	EXCAVATE TAILRACE TUNNEL	EXCAVATE LOWER PRESSURE TUNNEL	EXCAVATE UPPER PRESSURE TUNNEL	EXCAVATE PRESSURE SHAFT	EXCAVATE TOP HEADING	ROOF ANCHORAGE AND LINING	EXCAVATE REMAINDER OF CABIN	
	DURATION ⁽⁵⁾	4	4	12	8	6	6	9	4	3	2
On-site											
Air Compressor	0.0	1.3	0.0	0.0	0.0	0.0	1.3	3.8	1.3	1.3	
Backhoe / Front End Loader, Wheeled	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Backhoe, Tracked	0.0	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Compactor, Sheepsfoot, Self-Propelled	0.0	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Compactor, Vibratory, Self-Propelled	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Concrete Pump	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Crane - 40 Ton	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Crane - 70 Ton	0.0	0.0	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	
Dozer, D5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Dozer, D6	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Dozer, D8	0.0	1.3	0.0	0.0	0.0	0.0	1.3	2.5	0.0	2.5	
Drill, Tracked	0.0	1.3	2.5	1.3	1.3	0.0	1.3	3.8	1.3	3.8	
Dump Truck, End Dump, 15 Ton	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Dump Truck, Off-Highway, 34 Ton	0.0	3.8	5.0	6.3	2.5	6.3	2.5	5.0	0.0	5.0	
Excavator, 325	0.0	1.3	1.3	1.3	1.3	0.0	1.3	2.5	0.0	2.5	
Forklift, Rough Terrain	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Front End Loader, Wheeled	0.0	1.3	2.5	2.5	2.5	1.3	2.5	5.0	0.0	5.0	
Fuel Truck / Support Truck	1.3	1.3	0.0	0.0	0.0	1.3	1.3	1.3	1.3	1.3	
Generator - Diesel	1.3	1.3	1.3	1.3	1.3	1.3	1.3	2.5	1.3	2.5	
Grout Pump	0.0	0.0	1.3	1.3	1.3	0.0	1.3	0.0	1.3	0.0	
Motor Grader	1.3	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Pump truck - Concrete	0.0	0.0	1.3	2.5	2.5	0.0	2.5	0.0	0.0	0.0	
Truck, Flatbed	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1.3	0.0	
Tunnel Rig	0.0	0.0	1.3	1.3	1.3	1.3	0.0	0.0	0.0	0.0	
Water Pump, Diesel	1.3	0.0	1.3	1.3	1.3	1.3	1.3	0.0	0.0	0.0	
Water Truck	0.0	1.3	0.0	0.0	0.0	0.0	0.0	1.3	0.0	1.3	
Welder and Generator Set	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
TOTAL	10.0	17.5	17.5	18.8	15.0	12.5	18.8	27.5	7.5	25.0	
Daily Vehicles⁽³⁾											
Daily Concrete Mixer Truck - 8 CY	0.0	0.0	16.3	31.3	31.3	62.5	31.3	0.0	3.8	0.0	
Daily Semi Trailer Truck	0.0	0.0	71.3	97.5	76.3	81.3	30.0	75.0	0.0	50.0	
Off-Site Vehicles											
Total Offsite Flatbed/Semi Trucks	1.3	0.0	11.3	6.3	16.3	32.5	8.8	0.0	2.5	0.0	

(1) Rounded to nearest unit of equipment.
(2) Sum of estimated pieces of equipment times duration of construction activity. Calculated prior to rounding duration and equipment quantities. One equipment month is equal to 173 hours of operation.

(3) Number of daily vehicles on site.
(4) Pieces of equipment not equal to a whole number represent equipment not being utilized for entire duration of the activity.

(5) Rounded to the nearest month.

ESTIMATED CONSTRUCTION EQUIPMENT
EAGLE MOUNTAIN

TYPE OF EQUIPMENT	DURATION ⁽⁵⁾									
	EXCAVATE TRANSFORMER GALLERY	EXCAVATE TAILRACE SURGE CHANBER	EXCAVATE CABLE TUNNEL SHAFT	LINE AND PAVE CABLE TUNNEL	LINE PENSTKS DRAFT TUBE MAN.	INSTALL STEEL TUNNEL LINES	FIRST STAGE CONCRETE	INSTALL CASES DRAFT TUBE LINE.	INSTALL PUMP TURBIN. AND GEN.	EMBED CASES AND DRAFT LINERS
	3	6	6	10	5	8	6	8	11	9
On-site										
Air Compressor	1.3	1.3	1.3	1.3	2.5	1.3	0.0	0.0	1.3	0.0
Backhoe / Front End Loader, Wheeled	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Backhoe, Tracked	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Compactor, Sheepsfoot, Self-Propelled	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Compactor, Vibratory, Self-Propelled	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Concrete Pump	0.0	0.0	0.0	1.3	0.0	0.0	0.0	1.3	0.0	0.0
Crane - 40 Ton	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1.3	0.0	0.0
Crane - 70 Ton	0.0	0.0	0.0	1.3	0.0	0.0	1.3	0.0	1.3	0.0
Dozer, D5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Dozer, D6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Dozer, D8	1.3	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0
Drill, Tracked	2.5	1.3	1.3	1.3	0.0	1.3	0.0	0.0	0.0	0.0
Dump Truck, End Dump, 15 Ton	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Dump Truck, Off-Highway, 34 Ton	3.8	1.3	1.3	0.0	3.8	2.5	0.0	0.0	0.0	0.0
Excavator, 325	1.3	1.3	1.3	0.0	1.3	1.3	0.0	0.0	0.0	0.0
Forklift, Rough Terrain	0.0	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0
Front End Loader, Wheeled	2.5	2.5	2.5	0.0	3.8	2.5	0.0	0.0	0.0	0.0
Fuel Truck / Support Truck	1.3	1.3	1.3	1.3	1.3	1.3	1.3	0.0	1.3	1.3
Generator - Diesel	1.3	1.3	1.3	1.3	2.5	1.3	1.3	1.3	1.3	0.0
Grout Pump	0.0	0.0	0.0	1.3	0.0	0.0	1.3	0.0	0.0	0.0
Motor Grader	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pump truck - Concrete	0.0	1.3	0.0	0.0	5.0	2.5	2.5	0.0	0.0	1.3
Truck, Flatbed	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	0.0
Tunnel Rig	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Water Pump, Diesel	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Water Truck	1.3	1.3	0.0	0.0	1.3	1.3	1.3	0.0	0.0	1.3
Welder and Generator Set	0.0	0.0	0.0	0.0	0.0	1.3	0.0	1.3	1.3	0.0
TOTAL	16.3	12.5	11.3	10.0	22.5	17.5	8.8	5.0	6.3	3.8
Daily Vehicles⁽³⁾										
Daily Concrete Mixer Truck - 8 CY	0.0	0.0	0.0	1.3	62.5	31.3	31.3	1.3	0.0	5.0
Daily Semi Trailer Truck	50.0	18.8	3.8	0.0	50.0	25.0	0.0	0.0	0.0	0.0
Off-Site Vehicles										
Total Offsite Flatbed/Semi Trucks	0.0	1.3	0.0	2.5	11.3	192.5	10.0	13.8	10.0	3.8

(1) Rounded to nearest unit of equipment.
(2) Sum of estimated pieces of equipment times duration of construction activity. Calculated prior to rounding duration and equipment quantities. One equipment month is equal to 173 hours of operation.

(3) Number of daily vehicles on site.
(4) Pieces of equipment not equal to a whole number represent equipment not being utilized for entire duration of the activity.

(5) Rounded to the nearest month.

ESTIMATED CONSTRUCTION EQUIPMENT
EAGLE MOUNTAIN

TYPE OF EQUIPMENT	ESTIMATED AVERAGE PIECES OF EQUIPMENT FOR CONSTRUCTION ACTIVITIES ⁽¹⁾										
	INSTALL MECH. EQUIPMENT	INSTALL ELECT. EQUIPMENT	COMPLETE CONCRETE WK.	STRUCTURAL AND ARCHIT. CONST.	ELECTRICAL AND MECH. MOBE.	COMPLETE ELEC. CONSTRUCTION	EXCAVATE APPR. CHANNEL - UPPER	CONSTRUCT UPPER DAM	MOVE UNSTABLE SOIL - LOWER	LINE UPPER RESERVOIR	
	DURATION ⁽⁵⁾	6	6	9	13	3	13	10	8	13	4
On-site											
Air Compressor	1.3	1.3	0.0	1.3	0.0	1.3	1.3	2.5	0.0	0.0	
Backhoe / Front End Loader, Wheeled	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	
Backhoe, Tracked	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Compactor, Sheepsfoot, Self-Propelled	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Compactor, Vibratory, Self-Propelled	0.0	0.0	0.0	0.0	0.0	0.0	0.0	5.0	0.0	1.3	
Concrete Pump	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Crane - 40 Ton	0.0	0.0	1.3	1.3	0.0	0.0	0.0	0.0	0.0	0.0	
Crane - 70 Ton	1.3	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	0.0	
Dozer, D5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	5.0	0.0	0.0	
Dozer, D6	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	
Dozer, D8	0.0	0.0	0.0	0.0	0.0	0.0	2.5	0.0	2.5	1.3	
Drill, Tracked	0.0	0.0	0.0	1.3	0.0	0.0	2.5	0.0	0.0	0.0	
Dump Truck, End Dump, 15 Ton	0.0	0.0	0.0	0.0	0.0	0.0	0.0	6.3	0.0	0.0	
Dump Truck, Off-Highway, 34 Ton	0.0	0.0	0.0	1.3	0.0	0.0	7.5	5.0	6.3	12.5	
Excavator, 325	0.0	0.0	0.0	1.3	0.0	0.0	1.3	0.0	1.3	2.5	
Forklift, Rough Terrain	0.0	1.3	0.0	2.5	1.3	1.3	0.0	0.0	0.0	0.0	
Front End Loader, Wheeled	0.0	0.0	0.0	2.5	0.0	0.0	2.5	2.5	0.0	2.5	
Fuel Truck / Support Truck	1.3	1.3	1.3	2.5	1.3	1.3	1.3	2.5	1.3	1.3	
Generator - Diesel	1.3	1.3	1.3	2.5	1.3	2.5	0.0	0.0	0.0	0.0	
Grout Pump	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	0.0	
Motor Grader	0.0	0.0	0.0	0.0	1.3	0.0	0.0	2.5	1.3	0.0	
Pump truck - Concrete	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Truck, Flatbed	0.0	0.0	0.0	0.0	1.3	2.5	0.0	0.0	0.0	0.0	
Tunnel Rig	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Water Pump, Diesel	0.0	0.0	0.0	1.3	1.3	0.0	0.0	0.0	0.0	0.0	
Water Truck	0.0	0.0	1.3	0.0	0.0	0.0	1.3	2.5	1.3	1.3	
Welder and Generator Set	2.5	1.3	0.0	1.3	0.0	0.0	0.0	0.0	0.0	0.0	
TOTAL	7.5	6.3	6.3	21.3	10.0	8.8	20.0	33.8	13.8	22.5	
Daily Vehicles⁽³⁾											
Daily Concrete Mixer Truck - 8 CY	0.0	0.0	16.3	3.8	0.0	0.0	0.0	0.0	0.0	0.0	
Daily Semi Trailer Truck	0.0	0.0	0.0	22.5	0.0	0.0	50.0	0.0	0.0	0.0	
Off-Site Vehicles											
Total Offsite Flatbed/Semi Trucks	6.3	5.0	12.5	53.8	1.3	6.3	0.0	0.0	0.0	0.0	

(1) Rounded to nearest unit of equipment.

(2) Sum of estimated pieces of equipment times duration of construction activity. Calculated prior to rounding duration and equipment quantities. One equipment month is equal to 173 hours of operation.

(3) Number of daily vehicles on site.

(4) Pieces of equipment not equal to a whole number represent equipment not being utilized for entire duration of the activity.

(5) Rounded to the nearest month.

ESTIMATED CONSTRUCTION EQUIPMENT
EAGLE MOUNTAIN

TYPE OF EQUIPMENT	LINE LOWER RESERVOIR	CONSTRUCT I/O STRUC. - LOWER	CONSTRUCT I/O STRUC. - UPPER	SWITCHYARD EXCAVATION	SWITCHYARD FOUNDATIONS	SWITCHYARD STRUCTURES	TRANS. LINE FOUNDATIONS	TRANS. LINE STRINGING	TRANS. LINE STRUCTURES	INSTALL H2O SUPPLY AND RO S	RESERVOIR FILLING	
	DURATION ⁽⁵⁾	5	4	4	3	4	1	5	4	6	7	24
On-site												
Air Compressor	0.0	1.3	1.3	0.0	0.0	0.0	0.0	0.0	1.3	0.0	0.0	
Backhoe / Front End Loader, Wheeled	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Backhoe, Tracked	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Compactor, Sheepsfoot, Self-Propelled	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	1.3	0.0	
Compactor, Vibratory, Self-Propelled	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Concrete Pump	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Crane - 40 Ton	0.0	0.0	0.0	0.0	0.0	0.0	1.3	2.5	2.5	0.0	0.0	
Crane - 70 Ton	0.0	1.3	1.3	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	
Dozer, D5	0.0	0.0	0.0	1.3	1.3	0.0	0.0	0.0	0.0	0.0	0.0	
Dozer, D6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Dozer, D8	1.3	1.3	1.3	0.0	0.0	0.0	0.0	0.0	0.0	1.3	0.0	
Drill, Tracked	0.0	1.3	1.3	0.0	1.3	0.0	1.3	0.0	0.0	0.0	0.0	
Dump Truck, End Dump, 15 Ton	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	6.3	0.0	
Dump Truck, Off-Highway, 34 Ton	6.3	5.0	6.3	6.3	6.3	0.0	0.0	0.0	0.0	0.0	0.0	
Excavator, 325	2.5	1.3	1.3	1.3	0.0	0.0	0.0	0.0	0.0	1.3	0.0	
Forklift, Rough Terrain	0.0	0.0	0.0	0.0	0.0	1.3	0.0	1.3	1.3	0.0	0.0	
Front End Loader, Wheeled	2.5	1.3	1.3	1.3	0.0	0.0	1.3	0.0	0.0	1.3	0.0	
Fuel Truck / Support Truck	1.3	1.3	1.3	1.3	1.3	2.5	1.3	2.5	2.5	1.3	1.3	
Generator - Diesel	0.0	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	
Grout Pump	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Motor Grader	0.0	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	
Pump truck - Concrete	0.0	2.5	2.5	0.0	1.3	0.0	1.3	0.0	0.0	0.0	0.0	
Truck, Flatbed	0.0	0.0	0.0	0.0	0.0	1.3	0.0	1.3	1.3	0.0	0.0	
Tunnel Rig	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Water Pump, Diesel	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Water Truck	1.3	1.3	1.3	1.3	1.3	0.0	0.0	0.0	0.0	0.0	0.0	
Welder and Generator Set	0.0	0.0	0.0	0.0	0.0	1.3	0.0	0.0	2.5	1.3	0.0	
TOTAL	16.3	17.5	18.8	12.5	15.0	8.8	6.3	7.5	11.3	13.8	1.3	
Daily Vehicles⁽³⁾												
Daily Concrete Mixer Truck - 8 CY	0.0	31.3	31.3	0.0	2.5	0.0	8.8	0.0	0.0	0.0	0.0	
Daily Semi Trailer Truck	0.0	25.0	25.0	0.0	0.0	0.0	0.0	0.0	2.5	0.0	0.0	
Off-Site Vehicles												
Total Offsite Flatbed/Semi Trucks	0.0	11.3	0.0	0.0	1.3	12.5	30.0	0.0	200.0	260.0	0.0	

(1) Rounded to nearest unit of equipment.
(2) Sum of estimated pieces of equipment times duration of construction activity. Calculated prior to rounding duration and equipment quantities. One equipment month is equal to 173 hours of operation.

(3) Number of daily vehicles on site.
(4) Pieces of equipment not equal to a whole number represent equipment not being utilized for entire duration of the activity.

(5) Rounded to the nearest month.

ESTIMATED CONSTRUCTION EQUIPMENT
EAGLE MOUNTAIN

TYPE OF EQUIPMENT						ESTIMATED EQUIPMENT MONTHS ⁽²⁾	
	U-1 START-UP	U-2 START-UP	U-3 START-UP	U-4 START-UP	FINISH PROJECT		
DURATION ⁽⁵⁾	3	3	3	3	3		
On-site							
Air Compressor	1.3	1.3	1.3	1.3	1.3	220	
Backhoe / Front End Loader, Wheeled	0.0	0.0	0.0	0.0	0.0	9	
Backhoe, Tracked	0.0	0.0	0.0	0.0	0.0	5	
Compactor, Sheepsfoot, Self-Propelled	0.0	0.0	0.0	0.0	0.0	13	
Compactor, Vibratory, Self-Propelled	0.0	0.0	0.0	0.0	0.0	53	
Concrete Pump	0.0	0.0	0.0	0.0	0.0	23	
Crane - 40 Ton	0.0	0.0	0.0	0.0	0.0	57	
Crane - 70 Ton	0.0	0.0	0.0	0.0	0.0	81	
Dozer, D5	0.0	0.0	0.0	0.0	0.0	42	
Dozer, D6	0.0	0.0	0.0	0.0	0.0	9	
Dozer, D8	0.0	0.0	0.0	0.0	0.0	125	
Drill, Tracked	0.0	0.0	0.0	0.0	0.0	188	
Dump Truck, End Dump, 15 Ton	0.0	0.0	0.0	0.0	0.0	95	
Dump Truck, Off-Highway, 34 Ton	0.0	0.0	0.0	0.0	0.0	629	
Excavator, 325	0.0	0.0	0.0	0.0	0.0	190	
Forklift, Rough Terrain	0.0	0.0	0.0	0.0	0.0	90	
Front End Loader, Wheeled	0.0	0.0	0.0	0.0	0.0	328	
Fuel Truck / Support Truck	0.0	0.0	0.0	0.0	3.8	340	
Generator - Diesel	1.3	1.3	1.3	1.3	1.3	264	
Grout Pump	0.0	0.0	0.0	0.0	0.0	83	
Motor Grader	0.0	0.0	0.0	0.0	0.0	50	
Pump truck - Concrete	0.0	0.0	0.0	0.0	0.0	179	
Truck, Flatbed	0.0	0.0	0.0	0.0	0.0	72	
Tunnel Rig	0.0	0.0	0.0	0.0	0.0	39	
Water Pump, Diesel	0.0	0.0	0.0	0.0	0.0	83	
Water Truck	0.0	0.0	0.0	0.0	0.0	127	
Welder and Generator Set	0.0	0.0	0.0	0.0	0.0	98	
TOTAL	2.5	2.5	2.5	2.5	6.3	TOTAL	3492
Daily Vehicles⁽³⁾							
Daily Concrete Mixer Truck - 8 CY	0.0	0.0	0.0	0.0	0.0	-	
Daily Semi Trailer Truck	0.0	0.0	0.0	0.0	0.0	-	
Off-Site Vehicles							
Total Offsite Flatbed/Semi Trucks	0.0	0.0	0.0	0.0	0.0	924	

(1) Rounded to nearest unit of equipment.

(2) Sum of estimated pieces of equipment times duration of construction activity. Calculated prior to rounding duration and equipment quantities. One equipment month is equal to 173 hours of operation.

(3) Number of daily vehicles on site.

(4) Pieces of equipment not equal to a whole number represent equipment not being utilized for entire duration of the activity.

(5) Rounded to the nearest month.

Labor Costs

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	3/19/2009	By	NDM
		Checked		By	
		Approved		By	

LABOR COSTS

Crew	Hourly Wages (\$/hr)	Hourly Wages (including O &P) (\$/hr)	Source
Blaster	\$33.60	\$52.10	R.S. Means 2009, Crew B-47, Blast Foreman
Carpenters	\$39.95	\$61.95	R.S. Means 2009, Carpenters
Cement Finisher	\$38.30	\$56.05	R.S. Means 2009, Cement Finishers
Driller	\$31.60	\$49.00	R.S. Means 2009, Crew B-47, Driller
Electricians	\$47.00	\$69.95	R.S. Means 2009, Electricians
Equipment Operators	\$41.35	\$62.15	R.S. Means 2009, Equipment Operator (Medium)
Grade Setter	\$41.35	\$62.15	R.S. Means 2009, Equipment Operator (Medium)
Foreman	\$42.85	\$66.35	R.S. Means 2009, Foreman Average (Outside)
Labor Foreman	\$33.60	\$52.10	R.S. Means 2009, Labor Foreman (Outside)
Laborers	\$31.60	\$49.00	R.S. Means 2009, Common Building Laborers
Mechanics	\$42.70	\$64.20	R.S. Means 2009, Equipment Operator, Master Mechanics
Painter	\$35.20	\$52.75	R.S. Means 2009, Painters, Ordinary
Pile Driver	\$38.50	\$62.50	R.S. Means 2009, Pile Drivers
Pipe Foreman	\$49.35	\$74.05	R.S. Means 2009, Pipe Fitter
Pipe Layer	\$40.85	\$63.25	R.S. Means 2009, Skilled Worker
Plumber	\$48.75	\$73.15	R.S. Means 2009, Plumber
Rigger	\$40.85	\$63.25	R.S. Means 2009, Skilled Worker
Survey/Rodmen	\$39.75	\$60.80	R.S. Means 2009, Average of: Instrument Man, Rodmen/Chainmen
Steel Worker	\$44.70	\$79.65	R.S. Means 2009, Structural Steel Workers
Steel Worker Foreman	\$46.70	\$83.20	R.S. Means 2009, Structural Steel Foremen
Truck Drivers	\$31.95	\$49.15	R.S. Means 2009, Truck Drivers (Heavy)
Welder	\$44.70	\$79.65	R.S. Means 2009, Welders

Operations Labor Costs

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Operations	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

OPERATIONS

Crew	Shift Quantity	Number of Daily Shifts	Total Operations Crew	Annual Salaries ¹ (\$/year)	Annual Labor Costs (\$)
Mechanical Engineer	2	2	4	\$63,000	\$252,000
Electrical Engineer	2	2	4	\$63,000	\$252,000
Project Engineer	1	2	2	\$62,000	\$124,000
Project Manager	1	2	2	\$75,000	\$150,000
Construction Manager	1	2	2	\$70,000	\$140,000
Manager	1	2	2	\$54,000	\$108,000
Power Plant Operator	2	2	4	\$58,000	\$232,000
Plant Engineer	1	2	2	\$63,000	\$126,000
Mechanical Maintenance Technician	1	2	2	\$37,000	\$74,000
Scheduler	1	2	2	\$57,000	\$114,000
Field Service Engineer	1	2	2	\$53,000	\$106,000
Administration Staff	1	2	2	\$57,000	\$114,000
TOTAL =	15		30		\$1,792,000

1) Source: <http://www.simplyhired.com/a/salary/search/q-Hydro+Power> (3/19/2009)

OPERATIONS AND MAINTENANCE COSTS

The operation and maintenance costs are those associated with Project operation and upkeep. They include the cost of the direct salaries and administrative support of plant administration, operating and maintenance personnel, and of maintenance equipment and materials and repairs and spare parts.

Eagle Mountain Pumped Storage Estimated Annual Project Costs

Operating Costs Elements	Amount (\$/year)
Property Tax	\$8,390,000
Land Leases	\$2,000,000
Makeup Water and Pumping	\$2,400,000
Water Treatment	\$720,000
Property Insurance	\$4,200,000
Salaries	\$1,800,000
Home Office Administration	\$900,000
Supplies and Parts	\$2,500,000
FERC Fees	\$1,500,000
Total Annual Operating Cost	\$24,410,000

Note:

Table from Draft License Application - Exhibit D

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EAGLE MOUNTAIN PUMPED-STORAGE PROJECT --- TYPICAL EQUIPMENT AND TASK PRODUCTION RATES

TASK/EQUIPMENT	TYPICAL PRODUCTION RATES (SINGLE CREW ONLY)	
Tunnel Boring Machine	45 - 120	ft/day
Drill and Blast Excavation	200 - 400	cy/day
Benching Excavation	500	cy/day
Trench Excavation	200	lcy/hr
Prelining Shotcrete	200 - 300	sy/day
Concrete	100 - 200	cy/day
Grouting	450	cf/day
Roof & Wall Support	2000 - 2500	sf/day
Rock Anchors	400	lf/day
Misc. Steel	20	tons/day
Steel Liner	50	lf/day
Elevator Shaft	50	lf/day
Excavator	200 - 300	cy/hr
Compactor (large)	850	cy/hr
Compactor (small)	120	cy/hr
Grading	1200	cy/day
Gravel Placement	1500	cy/day
RCC Dams	1500	cy/day
Trashrack Installation	200	sf/day
Peir Foundations	4 - 10	peirs/day
Fencing Installation	300	lf/day
Transmission Line Stringing	8000	ft/day
Pipeline Installation	1000	ft/day

GEI Consultants, Inc.
080473 Eagle Mountain Pumped Storage Project
Construction Schedule Item List
1/20/2009
NDM

- 1 NOTICE TO PROCEED
- 2 CIVIL CONTRACTOR MOBILIZATION
- 3 CIVIL CONTRACTOR MOBILIZED
- 4 CONSTRUCT ACCESS ROADS
- 5 EXCAVATE POWER HOUSE ACCESS TUNNEL
- 6 COMPLETE ACCESS TUNNEL EXCAVATION
- 7 EXCAVATE TAILRACE TUNNEL
- 8 EXCAVATE LOWER PRESSURE TUNNEL
- 9 EXCAVATE UPPER PRESSURE TUNNEL
- 10 EXCAVATE PRESSURE SHAFT
- 11 EXCAVATE TOP HEADING
- 12 ROOF ANCHORAGE AND LINING
- 13 EXCAVATE REMAINDER OF CAVERN
- 14 COMPLETE POWER HOUSE EXCAVATION
- 15 EXCAVATE TRANSFORMER GALLERY
- 16 EXCAVATE TAILRACE SURGE CHAMBER
- 17 EXCAVATE CABLE TUNNEL SHAFT
- 18 LINE AND PAVE CABLE TUNNEL
- 19 LINE PENSTOCKS AND DRAFT TUBE MANIFOLD
- 20 INSTALL STEEL TUNNEL LININGS
- 21 FIRST STAGE CONCRETE
- 22 COMPLETE POWER HOUSE 1ST STAGE CONCRETE
- 23 INSTALL SPIRAL CASES AND DRAFT TUBE LINE
- 24 INSTALL PUMP TURBINES AND GENERATORS
- 25 EMBED SPIRAL CASES AND DRAFT LINERS
- 26 INSTALL MECHANICAL EQUIPMENT
- 27 INSTALL ELECTRICAL EQUIPMENT
- 28 COMPLETE CONCRETE WORK
- 29 STRUCTURAL AND ARCHITECTURAL CONSTRUCTION
- 30 COMPLETE DRAFT TUBE, SPIRAL CASE AND POWERHOUSE, 2ND STAGE CONCRETE
- 31 ELECTRICAL AND MECHANICAL MOBILIZATION
- 32 COMPLETE INSTALLATION OF PUMP-TURBINES, GENERATOR
- 33 COMPLETE ELECTRICAL CONSTRUCTION
- 34 EXCAVATE APPROACH CHANNEL - UPPER RESERVOIR
- 35 CONSTRUCT UPPER RESERVOIR DAM
- 36 MOVE UNSTABLE SOIL - LOWER RESERVOIR
- 37 LINE UPPER RESERVOIR
- 38 LINE LOWER RESERVOIR
- 39 CONSTRUCT I/O STRUCTURE - LOWER RESERVOIR
- 40 CONSTRUCT I/O STRUCTURE - UPPER RESERVOIR
- 41 SWITCHYARD EXCAVATION
- 42 SWITCHYARD FOUNDATIONS
- 43 SWITCHYARD STRUCTURES
- 44 TRANSMISSION LINE FOUNDATIONS
- 45 TRANSMISSION LINE STRINGING
- 46 TRANSMISSION LINE STRUCTURES
- 47 INSTALL WATER SUPPLY PIPELINE AND RO S
- 48 RESERVOIR FILLING
- 49 UNIT-1 START-UP
- 50 U-1 START-UP
- 51 UNIT-2 START-UP
- 52 U-2 START-UP
- 53 UNIT-3 START-UP
- 54 U-3 START-UP
- 55 UNIT-4 START-UP
- 56 U-4 START-UP
- 57 FINISH PROJECT

2 Civil Contractor Mobe

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	1
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	1
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	1
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump	
Hydroseed Sprayer, Truck Mounted	
Motor Grader	1
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	1
Tunnel Rig	
Water Pump, Diesel	1
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	1
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 4.0 Months 16.0 Weeks

NOTES:

Mobilization to include installing field offices, preparing staging area, minor road grading, temporary utility connections, security fencing, bringing equipment to site, preparation of equipment, and lighting

Crew	Quantity
Blaster	
Carpenters	2
Cement Finisher	
Driller	
Electricians	2
Equipment Operators	5
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	1
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	1
Welder	

Total Crew Size 15
 Monthly Labor Cost \$195,100

5 Power House Access Tunnel

Client:	Eagle Crest Energy	Project	080473	Page	1 of 2
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity	
On Site		
Air Compressor		
Backhoe / Front End Loader, Wheeled		
Backhoe, Tracked		
Chipper, Wood		
Compactor, Sheepsfoot, Self-Propelled		
Compactor, Vibratory, Self-Propelled		
Concrete Pump		
Crane - 40 Ton		
Crane - 70 Ton		
Dozer, D5		
Dozer, D6		
Dozer, D8		
Dozer, D10		
Drill, Tracked	2	
Dump Truck, End Dump, 15 Ton		
Dump Truck, Off-Highway, 34 Ton	4	Haul Cuttings
Dump Truck, Semi-Trailer		
Excavator, 325	1	
Forklift, Rough Terrain		
Front End Loader, Tracked		
Front End Loader, Wheeled	2	Load cuttings
Fuel Truck / Support Truck		
Generator - Diesel	1	
Grout Pump/Plant	1	
Hydroseed Sprayer, Truck Mounted		
Grader, H14		
Pile Driver		
Pump Truck - Concrete	1	
Powder Truck		
Scraper, Self-propelled, 21 CY		
Truck, Flatbed		
Tunnel Rig (TBM)	1	
Water Pump, Diesel	1	
Water Truck		
Welder and Generator Set		
Total Offsite Flatbed/Semi Trucks	9	
Daily Concrete Mixer Truck - 8 CY	13	
Daily Semi Trailer Truck	57	

Crew	Quantity
Blaster	2
Carpenters	
Cement Finisher	
Driller	2
Electricians	
Equipment Operators	5
Grade Setter	
Foreman	2
Labor Foreman	
Laborers	4
Mechanics	1
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	5
Welder	

Total Crew Size 23
 Monthly Labor Cost \$275,600

Duration: 11.6 Months 50.4 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

2.0 - CONSTRUCTION TUNNELS SCHEDULE			
2.1 To Machine Hall Roof	2,900		CY
2.2 To Transformer Hall Roof	1,700		CY
2.3 To Power Shaft Construction	8,500		CY
2.4 To Tailrace Surge Tank Construction Access	1,900		CY
Total Volume	15,000		CY
D&B Production Rate	38	FT/DAY	250 CY/DAY
Initial Duration	2.8		MONTHS
Contingency	25		%
Final Duration	3.5		MONTHS
Final Duration	15.0		WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS	30		CY/TRUCK
	500		# OF TRUCKS FOR TASK
	9		LOADS/DAY
	1.0		CYCLE TIME (HRS)
	1		REQUIRED # OF TRUCKS
SEMIS	20		CY/TRUCK
	750		# OF TRUCKS FOR TASK
	13		TRUCKS/DAY

3.0 - ACCESS TUNNEL SCHEDULE			
3.1 Main Access Tunnel (6628') to Power House			
3.1.1	Excavation (TBM)	192,500	CY
	Duration (from Tunnel Exc. Spreadsheet)	27.1	WEEKS
	Average Production Rate	1,136	CY/DAY
	Contingency	25	%
	Final Duration	7.8	MONTHS
	Final Duration	33.9	WEEKS
3.1.2	Prelining Shotcrete(w/wire-mesh)	20,600	SY
	Production Rate	200	SY/DAY
	Duration	4.8	MONTHS
	Contingency	25	%
	Final Duration	6.0	MONTHS
	Final Duration	25.8	WEEKS
	Lag	2.0	WEEKS
	Maximum Duration	27.8	WEEKS
3.1.3	Invert concrete	6,900	CY
	Production Rate	100	CY/DAY
	Duration	3.2	MONTHS
	Contingency	25	%
	Final Duration	4.0	MONTHS
	Final Duration	17.3	WEEKS
	Lag	2.0	WEEKS
	Maximum Duration	19.3	WEEKS
3.1.4	Rock anchors (15' long)	5,000	EA
	Total Bolt Length	75,000	FT
	Production Rate	800	FT/DAY
	Duration	4.3	MONTHS
	Contingency	25	%
	Final Duration	5.4	MONTHS
	Final Duration	23.4	WEEKS
	Lag	2.0	WEEKS
	Maximum Duration	25.4	WEEKS
3.2 Drainage Gallery Access Tunnel (L=80')			
3.2.1	Excavation	800	CY
	D&B Production Rate	38	FT/DAY
	Initial Duration	0.1	MONTHS
	Contingency	25	%
	Final Duration	0.2	MONTHS
	Final Duration	0.8	WEEKS
3.2.2	Invert Concrete	10	CY
	Production Rate	100	CY/DAY
	Duration	0.005	MONTHS
	Contingency	25	%
	Final Duration	0.006	MONTHS
	Final Duration	0.025	WEEKS
	Lag	0.5	WEEKS
	Maximum Duration	0.5	WEEKS
3.2.3	Prelining	200	SY
	Production Rate	200	SY/DAY
	Duration	0.0	MONTHS
	Contingency	25	%
	Final Duration	0.1	MONTHS
	Final Duration	0.3	WEEKS
	Lag	0.5	WEEKS
	Maximum Duration	0.8	WEEKS

5 Power House Access Tunnel

Client:	Eagle Crest Energy	Project:	080473	Page:	2 of 2
Subject:	Eagle Mountain Construction Schedule and Equipment	Date:	1/21/2009	By:	NDM
		Checked:		By:	
		Approved:		By:	

3.3 Tailrace Rock Trap Access Tunnel (L = 100')			100	LF
D&B Production Rate			37	FT/DAY
Initial Duration			0.1	MONTHS
Contingency			25	%
Final Duration			0.2	MONTHS
Final Duration			0.7	WEEKS
EQUIPMENT/TRUCKING				
DUMP TRUCKS				
		193954	TOTAL VOLUME, CY	
		30	CY/TRUCK	
		6,417	# OF TRUCKS FOR TASK	
		38	LOADS/DAY	
		1.0	CYCLE TIME (HRS)	
		4	REQUIRED # OF TRUCKS	
OFFSITE TRUCKS				
		168	TOTAL WEIGHT, TONS	
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;			20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete			9	# OF TRUCKS
CONCRETE TRUCKS				
		8643	TOTAL VOLUME, CY	
		8	CY/TRUCK	
		1,080	# OF TRUCKS FOR TASK	
		13	TRUCKS/DAY	
CONCRETE PUMP TRUCKS				
	(15 TRUCKS)-->	120	CY/DAY	
		1	# OF TRUCKS	
SEMIS				
		20	CY/TRUCK	
		9,698	# OF TRUCKS FOR TASK	
		57	TRUCKS/DAY	

Assumptions:

Const. Tunnel Diameter = 15', = 177sf
 D&B advancement rate = 37 ft/day, = 250cy/day
 Excavation Then Haul Offsite
 Survey Control
 Shotcrete/Prelining = 3" thick

Construction Tunnels:

Process: Drill, Blast, Excavate, Load, Haul, Dump, Load, Haul offsite.
 Equipment: Track Drill, Excavator, FE Loader, Dump Trucks, FE Loader, Semis.
 Crew: 1 Driller, 2 Blasters, 4 Equip Opr., 2 survey, 1 DT Driver

Access Tunnels:

Process: TBM bore, Excavate, Load, Haul, Dump, Load, Haul offsite; Rock Anchors; Shotcrete; Invert Concrete.
 Equipment: TBM, Excavator, FE Loader, Dump Trucks, FE Loader, 2 Track Drill, Semis; Grout Pump; Concrete

7 Excavate Tailrace Tunnel

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	5
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	
Generator - Diesel	1
Grout Pump/Plant	1
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	2
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	1
Water Pump, Diesel	1
Water Truck	
Welder and Generator Set	
Total Flatbed/Semi Trucks	5
Daily Concrete Mixer Truck - 8 CY	25
Daily Semi Trailer Truck	78

Haul Cuttings
Load cuttings

Duration: 7.7 Months 33.2 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

12.0 - TAILRACE TUNNEL SCHEDULE			
12.1 Tailrace Tunnel Excavation (TBM)			
Duration (from Tunnel Exc. Spreadsheet)		223,100	CY
Average Production Rate		23.1	WEEKS
Contingency		1,544	CY/DAY
Final Duration		25	%
Final Duration		6.7	MONTHS
Final Duration		28.9	WEEKS
12.2 Prelining Shotcrete & Support		78,700	SY
Production Rate (3-4 crews)		800	SY/DAY
Duration		4.5	MONTHS
Contingency		25	%
Final Duration		5.7	MONTHS
Final Duration		24.6	WEEKS
Lag		2.0	WEEKS
Maximum Duration		26.6	WEEKS
12.3 Plug Concrete Construction		3,400	CY
Production Rate		200	CY/DAY
Duration		0.8	MONTHS
Contingency		25	%
Final Duration		1.0	MONTHS
Final Duration		4.3	WEEKS
12.4 Plug Grout Injection		4,273	SY
Production Rate (1.5 crews)		300	SY/DAY
Duration		0.7	MONTHS
Contingency		25	%
Final Duration		0.8	MONTHS
Final Duration		3.6	WEEKS
Lag		0.5	WEEKS
Maximum Duration		4.1	WEEKS
12.5 Tailrace Rock Trap Construction		1,133	CY
D&B Production Rate		250	CY/DAY
Duration		0.21	MONTHS
Contingency		25	%
Final Duration		0.26	MONTHS
Final Duration		1.1	WEEKS
12.6 Excavate Tailrace Surge Tank (shown on different schedule task)			
EQUIPMENT/TRUCKING			
DUMP TRUCKS		224,233	TOTAL VOLUME, CY
		30	CY/TRUCK
		7,474	# OF TRUCKS FOR TASK
		46	LOADS/DAY
		1.0	CYCLE TIME (HRS)
		5	REQUIRED # OF TRUCKS
OFFSITE TRUCKS		80	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		5	# OF TRUCKS
CONCRETE TRUCKS		9958	TOTAL VOLUME, CY
		8	CY/TRUCK
		1,245	# OF TRUCKS FOR TASK
		25	TRUCKS/DAY
CONCRETE PUMP TRUCKS (15 TRUCKS)-->		120	CY/DAY
		2	# OF TRUCKS
SEMS		20	CY/TRUCK
		11,212	# OF TRUCKS FOR TASK
		78	TRUCKS/DAY

Crew	Quantity
Blaster	2
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	3
Grade Setter	
Foreman	1
Labor Foreman	1
Laborers	8
Mechanics	1
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	7
Welder	

Total Crew Size 26
Monthly Labor Cost \$298,700

Assumptions:
Excavation Then Haul Offsite
Survey Control
Shotcrete/Prelining = 3" thick
Tailrace Tunnel:
Process: TBM bore, Excavate, Load, Haul, Dump, Load, Haul offsite; Shotcrete; Plug Concrete.
Equipment: TBM, Excavator, FE Loader, Dump Trucks, FE Loader, Semis; Grout Pump; Concrete Pump Truck.
Crew: 1 TBM Operator, 2 TBM Laborers, 3 Equip Opr., 2 survey, 5 DT Drivers;
(Activities do not overlap, therefore use maximum of activities to find equipment and crew estimates)
Tailrace Rock Trap:
Process: Drill, Blast, Excavate, Load, Haul, Dump, Load, Haul offsite.
Equipment: Track Drill, Excavator, FE Loader, Dump Trucks, FE Loader, Semis.
Crew: 1 Driller, 2 Blasters, 3 Equip Opr., 2 survey, 1 DT Driver
Schedule: Excavation and Plug construction = duration, other activities + lag are less, Rock trap constructed concurrently.

8 Excavate Lower Pres. Tunnel

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	2
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	
Generator - Diesel	1
Grout Pump/Plant	1
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	2
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	1
Water Pump, Diesel	1
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	13
Daily Concrete Mixer Truck - 8 CY	25
Daily Semi Trailer Truck	61

Duration: 6.3 Months 27.3 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

8.0 - LOWER PRESSURE TUNNEL SCHEDULE			
8.1 Lower Pressure Tunnel Excavation (TBM)		52,600	CY
Duration (from Tunnel Exc. Spreadsheet)		6.9	WEEKS
Average Production Rate		1,214	CY/DAY
Contingency		25	%
Final Duration		2.0	MONTHS
Final Duration		8.7	WEEKS
8.2 Prelining Shotcrete & Support (6")		13,900	SY
Production Rate	(2 crews)	500	SY/DAY
Duration		1.3	MONTHS
Contingency		25	%
Final Duration		1.6	MONTHS
Final Duration		7.0	WEEKS
Lag		2.0	WEEKS
Maximum Duration		9.0	WEEKS
8.3 Tunnel Lining		14,300	CY
Production Rate		200	CY/DAY
Duration		3.3	MONTHS
Contingency		25	%
Final Duration		4.1	MONTHS
Final Duration		17.9	WEEKS
Lag		2.0	WEEKS
Maximum Duration		19.9	WEEKS
8.4 Miscellaneous Concrete (bends, plug, etc.)		5,900	CY
Production Rate		200	CY/DAY
Duration		1.4	MONTHS
Contingency		25	%
Final Duration		1.7	MONTHS
Final Duration		7.4	WEEKS
8.5 Contact Grouting		10,700	CF
Production Rate		450	CF/DAY
Duration		1.10	MONTHS
Contingency		25	%
Final Duration		1.37	MONTHS
Final Duration		5.9	WEEKS
Lag		1.0	WEEKS
Maximum Duration		6.9	WEEKS
8.6 Curtain Grouting		5,800	CF
Production Rate		450	CF/DAY
Duration		0.60	MONTHS
Contingency		25	%
Final Duration		0.75	MONTHS
Final Duration		3.2	WEEKS
Lag		1.0	WEEKS
Maximum Duration		4.2	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		52,600	TOTAL VOLUME, CY
		30	CY/TRUCK
		1,753	# OF TRUCKS FOR TASK
		13	LOADS/DAY
		1.0	CYCLE TIME (HRS)
		2	REQUIRED # OF TRUCKS
OFFSITE TRUCKS		249	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		13	# OF TRUCKS
CONCRETE TRUCKS		23,128	TOTAL VOLUME, CY
		8	CY/TRUCK
		2,891	# OF TRUCKS FOR TASK
		25	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)-->	120	CY/DAY
		2	# OF TRUCKS
SEMIS		20	CY/TRUCK
		2,630	# OF TRUCKS FOR TASK
		61	TRUCKS/DAY

Assumptions:

Excavation Then Haul Offsite
 Survey Control
 Shotcrete/Prelining = 3" thick

Lower Pressure Tunnel:

Process: TBM bore, Excavate, Load, Haul, Dump, Load, Haul offsite; Shotcrete; Concrete Lining, Grouting.
 Equipment: TBM, Excavator, FE Loader, Dump Trucks, FE Loader, Semis; Concrete Pump Truck; Drill, Grout
 Crew: 1 TBM Operator, 2 TBM Laborers, 3 Equip Opr., 2 survey, 2 DT Drivers;
 Schedule: Tunnel lining + Misc. Concrete = duration, other activities + lag are less, other activities constructed concurrently.

10 Excavate Pressure Shaft

Client:	Eagle Crest Energy	Project	080473	Page	1 of 2
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	1
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	2
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	1
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	2
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	1
Water Truck	
Welder and Generator Set	
Total Off-Site Flatbed/Semi Trucks	8
Daily Concrete Mixer Truck - 10 CY	25
Daily Semi Trailer Truck	24

shaft work

Benching

Larger Model

(3)

Crew	Quantity
Blaster	2
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	4
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	4
Mechanics	1
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	5
Welder	

Total Crew Size 20
 Monthly Labor Cost \$237,200

Duration: 9.4 Months 40.6 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

7.0 - POWER SHAFT SCHEDULE			
7.1 Power Shaft Excavation (D&B)		40,600	CY
Duration (from Tunnel Exc. Spreadsheet)		11.6	WEEKS
Average Production Rate		467	CY/DAY
Contingency		50	%
Final Duration		4.0	MONTHS
Final Duration		17.4	WEEKS
7.2 Shaft Prelining & Support		2,200	SF
Production Rate		100	SF/DAY
Duration		1.0	MONTHS
Contingency		25	%
Final Duration		1.3	MONTHS
Final Duration		5.5	WEEKS
Lag		2.0	WEEKS
Maximum Duration		7.5	WEEKS
7.3 Concrete Lining		11,100	CY
Production Rate		200	CY/DAY
Duration		2.6	MONTHS
Contingency		25	%
Final Duration		3.2	MONTHS
Final Duration		13.9	WEEKS
Lag		2.0	WEEKS
Maximum Duration		15.9	WEEKS
7.4 Contact Grouting		9,300	CF
Production Rate		450	CF/DAY
Duration		1.0	MONTHS
Contingency		25	%
Final Duration		1.2	MONTHS
Final Duration		5.2	WEEKS
Lag		2.0	WEEKS
Maximum Duration		7.2	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		40,600	TOTAL VOLUME, CY
		30	CY/TRUCK
		1,353	# OF TRUCKS FOR TASK
		16	LOADS/DAY
		1.0	CYCLE TIME (HRS)
		2	REQUIRED # OF TRUCKS
OFFSITE TRUCKS		133	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		7	# OF TRUCKS
CONCRETE TRUCKS		11,628	TOTAL VOLUME, CY
		8	CY/TRUCK
		1,453	# OF TRUCKS FOR TASK
		25	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)-->	120	CY/DAY
		2	# OF TRUCKS
SEMSIS		20	CY/TRUCK
		2,030	# OF TRUCKS FOR TASK
		24	TRUCKS/DAY

6.0 - SURGE TANK SCHEDULE			
6.1 Shaft Excavation (D&B)		8,900	CY
Production Rate		400	CY/DAY
Duration		1.0	MONTHS
Contingency		25	%
Final Duration		1.3	MONTHS
Final Duration		5.6	WEEKS
6.2 Benching Excavation		35,300	CY
Production Rate		500	CY/DAY
Duration		3.3	MONTHS
Contingency		25	%
Final Duration		4.1	MONTHS
Final Duration		17.7	WEEKS

10 Excavate Pressure Shaft

Client:	Eagle Crest Energy	Project	080473	Page	2 of 2
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

6.3 Concrete Works	700	CY
Production Rate	100	CY/DAY
Duration	0.3	MONTHS
Contingency	25	%
Final Duration	0.4	MONTHS
Final Duration	1.8	WEEKS
Lag	2.0	WEEKS
Maximum Duration	3.8	WEEKS
EQUIPMENT/TRUCKING		
OFFSITE TRUCKS	8	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;	20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete	1	# OF TRUCKS
CONCRETE TRUCKS	700	TOTAL VOLUME, CY
	8	CY/TRUCK
	88	# OF TRUCKS FOR TASK
	13	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)--> 120	CY/DAY
	1	# OF TRUCKS
SEMIS	20	CY/TRUCK
	2,210	# OF TRUCKS FOR TASK
	20	TRUCKS/DAY

Assumptions:

Excavation Then Haul Offsite
 Survey Control
 Shotcrete/Prelining = 3" thick

Power Shaft:

Process: Drill, Blast, Excavate, Crane Hoist, Load, Haul, Dump, Load, Haul offsite.
 Equipment: Track Drill, Excavator, Crane, FE Loader, Dump Trucks, FE Loader, Semis; Grout Pump, Concrete
 Crew: 1 Driller, 2 Blasters, 4 Equip Opr., 2 survey, 2 DT Driver;

Surge Tank:

Process: D&B: Drill, Blast, Excavate, Crane Hoist, Load, Haul offsite.
 Equipment: D&B: Track Drill, Excavator, Crane, FE Loader, Dump Trucks, FE Loader, Semis; Grout Pump,
 Crew: 1 Driller, 2 Blasters, 4 Equip Opr., 2 survey;
 Schedule: Shaft Exc. + Surge Exc. + Bench Exc. = duration, other activities + lag are less, other activities
 constructed concurrently.

11 Excavate Top Heading

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	3
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	2
Dozer, D10	
Drill, Tracked	3
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	4
Dump Truck, Semi-Trailer	
Excavator, 325	2
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	4
Fuel Truck / Support Truck	1
Generator - Diesel	2
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM) (3)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	60

Larger Model

Duration: 3.7 Months 16.1 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

13.0 MACHINE HALL SCHEDULE			
13.1-C Hall Benching Excavation (El. 18, El. 85)		64,000	CY
Production Rate	(3 crews)	1,200	CY/DAY
Duration		2.5	MONTHS
Contingency		25	%
Final Duration		3.1	MONTHS
Final Duration		13.3	WEEKS
13.1-D Roof Excavation (El. 85, El. 100)		9,900	CY
Production Rate	(2-3 crews)	900	CY/DAY
Duration		0.5	MONTHS
Contingency		25	%
Final Duration		0.6	MONTHS
Final Duration		2.8	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		73,900	TOTAL VOLUME, CY
		30	CY/TRUCK
		2,463	# OF TRUCKS FOR TASK
		40	LOADS/DAY (MAX.)
		1.0	CYCLE TIME (HRS)
		4	REQUIRED # OF TRUCKS
SEMIS		20	CY/TRUCK
		3,695	# OF TRUCKS FOR TASK
		60	TRUCKS/DAY

Assumptions:

Excavation Then Haul Offsite
Survey Control

Excavate Top Heading

Process: Drill, Blast, Excavate, Load, Haul, Dump, Load, Haul offsite.

Equipment: Track Drills, 2 Excavators, 2 Dozers, 4 FE Loaders, Dump Trucks, Semis, Water Truck, Support Truck.

Crew: 3 Drillers, 6 Blasters, 8 Equip Opr., 2 survey, 4 DT Drivers, 2 Foreman, 1 Water Truck Driver, 1 Support Driver.

Schedule: Activities are additive.

Crew	Quantity
Blafter	6
Carpenters	
Cement Finisher	
Driller	3
Electricians	
Equipment Operators	8
Grade Setter	
Foreman	2
Labor Foreman	
Laborers	1
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	5
Welder	

Total Crew Size 27
Monthly Labor Cost \$326,000

12 Roof Anchorage and Lining

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	1
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	1
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	2
Daily Concrete Mixer Truck - 8 CY	3
Daily Semi Trailer Truck	

drill anchor holes

shotcrete

Duration: 2.8 Months 12.1 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

13.0 MACHINE HALL SCHEDULE			
13.2 Roof & Walls Support (3")		96,700	SF
Production Rate	(1 crew)	2,200	SF/DAY
Duration		2.0	MONTHS
Contingency		25	%
Final Duration		2.5	MONTHS
Final Duration		11.0	WEEKS
NA Rock Bolts			
Assume Bolts Lengths are:		20.0	LF
Assume 1 bolt per:		100.0	SF
Total Length		19340.0	LF
Production Rate		400	LF/DAY
Duration		2.2	MONTHS
Contingency		25	%
Final Duration		2.8	MONTHS
Final Duration		12.1	WEEKS
EQUIPMENT/TRUCKING			
OFFSITE TRUCKS			
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;	25	TOTAL WEIGHT, TONS	
1lbs of reinforcement/s.y. of shotcrete	20	TONS/TRUCK	
	2	# OF TRUCKS	
CONCRETE TRUCKS			
	895	TOTAL VOLUME, CY	
	8	CY/TRUCK	
	112	# OF TRUCKS FOR TASK	
	3	TRUCKS/DAY	

Assumptions:

Roof and Walls Support is 3" thick shotcrete
Grout for rockbolts is included in shotcrete volume

Roof and Walls Support:

Process: Drill, Install Rock Bolts, Grout Bolts, Shotcrete Surface.
Equipment: Track Drill, Support Truck, Flatbed Truck for rock bolts.
Crew: 1 Driller, 3 Laborers, 1 Foreman, 1 Truck Driver.

Schedule: Activities are additive.

Crew	Quantity
Blaister	
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	1
Welder	

Total Crew Size 6
Monthly Labor Cost \$67,500

15 Excavate Transformer Gallery

Client:	Eagle Crest Energy	Project 080473	Page 1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date 1/21/2009	By NDM
		Checked	By
		Approved	By

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	1
Dozer, D10	
Drill, Tracked	2
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	3
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	40

Crew	Quantity
Blaster	2
Carpenters	
Cement Finisher	
Driller	2
Electricians	
Equipment Operators	5
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	1
Mechanics	1
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	4
Welder	

Total Crew Size 18
 Monthly Labor Cost \$218,800

Duration: 2.7 Months 11.8 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

15.1 TRANSFORMER HALL EXCAVATION (D&B)			
SCHEDULE			
15.1-A Transformer Hall Excavation			30,900 CY
Production Rate	(2 crews)	800	CY/DAY
Duration		1.8	MONTHS
Contingency		25	%
Final Duration		2.2	MONTHS
Final Duration		9.7	WEEKS
15.1-B Nishe Excavation			2,700 CY
Production Rate	(1crew)	400	CY/DAY
Duration		0.3	MONTHS
Contingency		25	%
Final Duration		0.4	MONTHS
Final Duration		1.7	WEEKS
15.1-C Cable Gallery Excavation			700 CY
Production Rate	(1crew)	400	CY/DAY
Duration		0.1	MONTHS
Contingency		25	%
Final Duration		0.1	MONTHS
Final Duration		0.4	WEEKS
15.1-D A/C Gallery Excavation			100 CY
Production Rate	(1crew)	400	CY/DAY
Duration		0.0	MONTHS
Contingency		25	%
Final Duration		0.0	MONTHS
Final Duration		0.1	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		34,400	TOTAL VOLUME, CY
		30	CY/TRUCK
		1,147	# OF TRUCKS FOR TASK
		27	LOADS/DAY (MAX.)
		1.0	CYCLE TIME (HRS)
		3	REQUIRED # OF TRUCKS
SEMIS		20	CY/TRUCK
		1,720	# OF TRUCKS FOR TASK
		40	TRUCKS/DAY

Assumptions:

Excavation Then Haul Offsite

Survey Control

Excavate Transformer Gallery:

Process: Drill, Blast, Excavate, Load, Haul, Dump, Load, Haul offsite.

Equipment: Track Drills, 1 Excavators, 1 Dozer, 3 FE Loaders, Dump Trucks, Semis, Water Truck, Support Truck.

Crew: 2 Drillers, 4 Blasters, 5 Equip Opr., 2 survey, 3 DT Drivers, 1 Foreman, 1 Water Truck Driver, 1 Support Driver.

Schedule: Activities are additive.

16 Exc. Tailrace Surge Chamber

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	1
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	1
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	1
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	15

Crew	Quantity
Blafter	2
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	3
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	4
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	3
Welder	

Total Crew Size 16
 Monthly Labor Cost \$188,600

Duration: 6.4 Months 27.8 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

12.6 D/S Surge Tank Construction (D&B)			
SCHEDULE			
NA Surge Tank Excavation (D&B)		19,000	CY
Production Rate	(1 crew)	300	CY/DAY
Duration	(Reduced Production - Limited Access)	2.9	MONTHS
Contingency		25	%
Final Duration		3.7	MONTHS
Final Duration		15.8	WEEKS
NA Roof & Walls Support (3")		105,000	SF
Production Rate	(1 crew)	2,200	SF/DAY
Duration		2.2	MONTHS
Contingency		25	%
Final Duration		2.8	MONTHS
Final Duration		11.9	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		19,000	TOTAL VOLUME, CY
		30	CY/TRUCK
		633	# OF TRUCKS FOR TASK
		10	LOADS/DAY (MAX.)
		1.0	CYCLE TIME (HRS)
		1	REQUIRED # OF TRUCKS
OFFSITE TRUCKS		6	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		1	# OF TRUCKS
SEMIS		20	CY/TRUCK
		950	# OF TRUCKS FOR TASK
		15	TRUCKS/DAY

Assumptions:

Excavation Then Haul Offsite
 Survey Control

Excavate Transformer Gallery:

Process: Drill, Blast, Excavate, Load, Haul, Dump, Load, Haul offsite.

Equipment: Track Drill, 1 Excavators, 2 FE Loaders, Dump Truck, Semis, Water Truck, Support Truck.
 Crew: 1 Driller, 2 Blasters, 3 Equip Opr., 2 survey, 1 DT Driver, 1 Water Truck Driver, 1 Support Driver.

Shotcrete Crew: 1 Forman, 2 Laborers, 1 CPT Driver.

Schedule: Activities are additive.

17 Excavate Cable Tunnel Shaft

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	1
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	1
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	3

Larger Model

Duration: 5.9 Months 25.4 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

15.1-E CABLE SHAFT EXCAVATION SCHEDULE			
NA Cable Shaft Excavation (D&B)			4,700 CY
Production Rate	(1 crew)		50 CY/DAY
Duration	(Low production - restricted work area)		4.3 MONTHS
Contingency			35 %
Final Duration			5.9 MONTHS
Final Duration			25.4 WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		4,700	TOTAL VOLUME, CY
		30	CY/TRUCK
		157	# OF TRUCKS FOR TASK
		2	LOADS/DAY (MAX.)
		1.0	CYCLE TIME (HRS)
		1	REQUIRED # OF TRUCKS
SEMIS		20	CY/TRUCK
		235	# OF TRUCKS FOR TASK
		3	TRUCKS/DAY

Assumptions:

Excavation Then Haul Offsite
Survey Control

Excavate Transformer Gallery:

Process: Drill, Blast, Excavate, Crane Hoist, Load, Haul, Dump, Load, Haul offsite.
Equipment: Track Drill, Excavator, Crane, FE Loader, Dump Truck, FE Loader, Semis, Support Truck.
Crew: 1 Driller, 2 Blasters, 4 Equip Opr., 2 survey, 1 DT Driver, 1 Support Driver.

Crew	Quantity
Blaster	2
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	4
Grade Setter	
Foreman	
Labor Foreman	
Laborers	1
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	1
Welder	

Total Crew Size 11
Monthly Labor Cost \$134,600

18 Line and Pave Cable Tunnel

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	1
Crane - 40 Ton	
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	1
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	1
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	2
Daily Concrete Mixer Truck - 8 CY	1
Daily Semi Trailer Truck	

Duration: 10.1 Months 43.6 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

15.0 TRANSFORMER HALL			
SCHEDULE			
15.2-E Roof & Walls Support - Cable Shaft		56,900	SF
Production Rate (1 crew)		500	SF/DAY
Duration (Low production - restricted work area)		5.3	MONTHS
Contingency		25	%
Final Duration		6.6	MONTHS
Final Duration		28.5	WEEKS
NA Rock Bolts			
Assume Bolts Lengths are:		5.5	LF
Assume 1 bolt per:		45.0	SF
Total Length		6954	LF
Production Rate		200	LF/DAY
Duration (Low production - restricted work area)		1.6	MONTHS
Contingency		25	%
Final Duration		2.0	MONTHS
Final Duration		8.7	WEEKS
NA Ladders, Platforms, Cable Installation			
Total Length		1300	LF
Production Rate		50	LF/DAY
Duration		1.2	MONTHS
Contingency		25	%
Final Duration		1.5	MONTHS
Final Duration		6.5	WEEKS
EQUIPMENT/TRUCKING			
OFFSITE TRUCKS		36	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		2	# OF TRUCKS
CONCRETE TRUCKS		527	TOTAL VOLUME, CY
		8	CY/TRUCK
		66	# OF TRUCKS FOR TASK
		1	TRUCKS/DAY

Assumptions:

Roof and Walls Support is 3" thick shotcrete

Grout for rockbolts is included in shotcrete volume

Roof and Walls Support:

Process: Drill, Install Rock Bolts, Grout Bolts, Shotcrete Surface, Install Equipment.

Equipment: Track Drill, Hoist, Support Truck, Flatbed Truck for rock bolts, Pump.

Crew: 1 Driller, 3 Laborers, 1 Foreman, 1 Truck Driver.

Schedule: Activities are additive.

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	1
Welder	

Total Crew Size 6
 Monthly Labor Cost \$67,500

19 Penstock & Draft Tube Man.

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	2
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	1
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	3
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	3
Fuel Truck / Support Truck	1
Generator - Diesel	2
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	4
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	9
Daily Concrete Mixer Truck - 8 CY	50
Daily Semi Trailer Truck	40

Crew	Quantity
Blaster	4
Carpenters	
Cement Finisher	
Driller	2
Electricians	
Equipment Operators	5
Grade Setter	
Foreman	3
Labor Foreman	3
Laborers	9
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	8
Welder	
Total Crew Size	36
Monthly Labor Cost	\$417,400

Duration: 5.2 Months 22.5 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

9.0 PENSTOCK MANIFOLD SCHEDULE			
9.1 Manifold Tunnel Excavation (D&B)			
Production Rate	(2 crews)	7,400	CY
Duration		800	CY/DAY
Contingency		0.4	MONTHS
Final Duration		25	%
Final Duration		0.5	MONTHS
Final Duration		2.3	WEEKS
9.2 Manifold Tunnel Prelining & Support (3", 75%)		2,400	SY
Production Rate	(2 crews)	500	SY/DAY
Duration		0.2	MONTHS
Contingency		25	%
Final Duration		0.3	MONTHS
Final Duration		1.2	WEEKS
9.3 Concrete Lining		1,800	CY
Production Rate	(2 crews)	400	CY/DAY
Duration		0.2	MONTHS
Contingency		25	%
Final Duration		0.3	MONTHS
Final Duration		1.1	WEEKS
9.4 Concrete Plug		10,700	CY
Production Rate	(1crew)	200	CY/DAY
Duration		2.5	MONTHS
Contingency		25	%
Final Duration		3.1	MONTHS
Final Duration		13.4	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		7,400	TOTAL VOLUME, CY
		30	CY/TRUCK
		247	# OF TRUCKS FOR TASK
		27	LOADS/DAY (MAX.)
		1.0	CYCLE TIME (HRS)
		3	REQUIRED # OF TRUCKS
OFFSITE TRUCKS		151	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		8	# OF TRUCKS
CONCRETE TRUCKS		12700	TOTAL VOLUME, CY
		8	CY/TRUCK
		1,588	# OF TRUCKS FOR TASK
		50	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)-->	120	CY/DAY
		4	# OF TRUCKS
SEMS		20	CY/TRUCK
		370	# OF TRUCKS FOR TASK
		40	TRUCKS/DAY

11.0 DRAFT TUBE MANIFOLD SCHEDULE			
11.1 Manifold Tunnel Excavation (D&B)			
Production Rate	(2 crews)	7,400	CY
Duration		800	CY/DAY
Contingency		0.4	MONTHS
Final Duration		25	%
Final Duration		0.5	MONTHS
Final Duration		2.3	WEEKS
11.2 Manifold Tunnel Prelining & Support (3", 75%)		2,400	SY
Production Rate	(2 crews)	500	SY/DAY
Duration		0.2	MONTHS
Contingency		25	%
Final Duration		0.3	MONTHS
Final Duration		1.2	WEEKS
11.3 Concrete Lining		1,600	CY
Production Rate	(2 crews)	400	CY/DAY
Duration		0.2	MONTHS
Contingency		25	%
Final Duration		0.2	MONTHS
Final Duration		1.0	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		7,400	TOTAL VOLUME, CY
		30	CY/TRUCK
		247	# OF TRUCKS FOR TASK
		27	LOADS/DAY (MAX.)
		1.0	CYCLE TIME (HRS)
		3	REQUIRED # OF TRUCKS
OFFSITE TRUCKS		20	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		1	# OF TRUCKS
CONCRETE TRUCKS		1800	TOTAL VOLUME, CY
		8	CY/TRUCK
		225	# OF TRUCKS FOR TASK
		50	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)-->	120	CY/DAY
		4	# OF TRUCKS
SEMS		20	CY/TRUCK
		370	# OF TRUCKS FOR TASK
		40	TRUCKS/DAY

Assumptions:
Excavation Then Haul Offsite
Survey Control
(Activities do not overlap, therefore use maximum of activities to find equipment and crew estimates)

21 First Stage Concrete

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	1
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	2
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	8
Daily Concrete Mixer Truck - 8 CY	25
Daily Semi Trailer Truck	

Crew	Quantity
Blaister	
Carpenters	
Cement Finisher	2
Driller	
Electricians	
Equipment Operators	1
Grade Setter	
Foreman	1
Labor Foreman	1
Laborers	9
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	2
Steel Worker Foreman	
Truck Drivers	3
Welder	

Total Crew Size 19
 Monthly Labor Cost \$225,300

Duration: 5.5 Months 23.9 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

FIRST STAGE CONCRETE - MULTIPLE ITEMS			
SCHEDULE			
13.3-B Machine Hall (El.-16,El.-12)			2,700 CY
Production Rate	(1 crew)		200 CY/DAY
Duration			0.6 MONTHS
Contingency			25 %
Final Duration			0.8 MONTHS
Final Duration			3.4 WEEKS
13.3-C Machine Hall (El.-12,El.+9)			10,100 CY
Production Rate	(1 crew)		200 CY/DAY
Duration			2.3 MONTHS
Contingency			25 %
Final Duration			2.9 MONTHS
Final Duration			12.6 WEEKS
15.2-A Roof & Wall Support Transformer Hall			44,300 SF
Production Rate	(1 crew)		2,200 SF/DAY
Duration			0.9 MONTHS
Contingency			25 %
Final Duration			1.2 MONTHS
Final Duration			5.0 WEEKS
15.2-B Roof & Wall Support Nishe Excavation			2,500 SF
Production Rate	(1 crew)		500 SF/DAY
Duration (Low production - restricted work area)			0.2 MONTHS
Contingency			25 %
Final Duration			0.3 MONTHS
Final Duration			1.3 WEEKS
15.2-C Roof & Wall Support Cable Gallery			3,200 SF
Production Rate	(1 crew)		500 SF/DAY
Duration (Low production - restricted work area)			0.30 MONTHS
Contingency			25 %
Final Duration			0.37 MONTHS
Final Duration			1.6 WEEKS
15.2-D Roof & Wall Support A/C Gallery			100 SF
Production Rate	(1 crew)		500 SF/DAY
Duration (Low production - restricted work area)			0.01 MONTHS
Contingency			25 %
Final Duration			0.01 MONTHS
Final Duration			0.1 WEEKS
EQUIPMENT/TRUCKING			
OFFSITE TRUCKS		156	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		8	# OF TRUCKS
CONCRETE TRUCKS		13,264	TOTAL VOLUME, CY
		8	CY/TRUCK
		1,658	# OF TRUCKS FOR TASK
		25	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)-->	120	CY/DAY
		2	# OF TRUCKS

Assumptions:

Process: Form, Pump, Finish.

Equipment: Concrete Trucks, Concrete Pump Trucks, 1 Water Truck, 1 Support Truck, Hoist Crane.

Crew: 1 Foreman, 1 Laborer Foreman, 8 Laborers, 2 Cement Finishers, 2 Steel Workers, 1 Water Truck Driver, 1 Support Driver, 2 CPT Drivers, 1 Crane Oper.

Schedule: Activities are additive.

23 Spiral Cases & Draft Tube

Client: Eagle Crest Energy	Project 080473	Page 1
Subject: Eagle Mountain Construction Schedule and Equipment	Date 1/21/2009	By NDM
	Checked	By
	Approved	By

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	1
Crane - 40 Ton	1
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	
Generator - Diesel	1
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	1
Total Offsite Flatbed/Semi Trucks	11
Daily Concrete Mixer Truck - 8 CY	1
Daily Semi Trailer Truck	

Duration: 8.2 Months 35.3 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

13.4 Spiral Cases & Draft Tube Liners			
SCHEDULE			
13.4-A Draft Tube Steel Liner		220	TONS
Assumed Unit Weight of Steel Liner		475	LBS/CF
Average Draft Tube Diameter		10	FT
Thickness		1.625	INCHES
Unit Weight		1.0	TONS/FT
Length		300	FT
Production Rate	(1 crew)	5	LF/DAY
Duration	(Very low production - very restricted work area)	2.8	MONTHS
Contingency		25	%
Final Duration		3.5	MONTHS
Final Duration		15.0	WEEKS
10.5 Contact Grouting		8,100	CF
Production Rate	(1 crew)	100	CF/DAY
Duration	(Very low production - very restricted work area)	3.7	MONTHS
Contingency		25	%
Final Duration		4.7	MONTHS
Final Duration		20.3	WEEKS
EQUIPMENT/TRUCKING			
CONCRETE TRUCKS		300	TOTAL VOLUME, CY
		8	CY/TRUCK
		38	# OF TRUCKS FOR TASK
		1	TRUCKS/DAY
OFFSITE TRUCKS		220	TOTAL WEIGHT, TONS
		20	TONS/TRUCK
		11	# OF TRUCKS

Assumptions:

Process: Steel Lining, Contact Grouting.
 Equipment: Crane, Concrete Pump, Welder.
 Steel Lining Crew: 1 Welders, 2 Steel Workers, 1 Equip Opr.
 Grouting Crew: 1 Foreman, 2 Laborers, 1 CPT Drivers.
 Schedule: Activities are additive.

Crew	Quantity
Blastrer	
Carpenters	
Cement Finisher	
Driller (3)	
Electricians	
Equipment Operators	1
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	2
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	2
Steel Worker Foreman	
Truck Drivers	1
Welder	1

Total Crew Size 8
 Monthly Labor Cost \$111,400

24 Pump Turbines and Generators

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	1
Total Offsite Flatbed/Semi Trucks	8
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 11.1 Months 48.0 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

14.0 TURBINES & GENERATORS			
SCHEDULE			
14.1 & .2 Install Water to Wire Package		4	EA
Production Rate		50	DAYS/EA
Duration		9.2	MONTHS
Contingency		20	%
Final Duration		11.1	MONTHS
Final Duration		48.0	WEEKS
EQUIPMENT/TRUCKING			
OFF SITE FLATBED SEMIS		0.5	UNITS/TRUCK
		8	# OF TRUCKS FOR TASK
		1	TRUCKS/DAY

Assumptions:

Equipment: Crane, Welder, Air Compressor (tools), Support Truck, Generator, Semis.
 Installation Crew: 1 Welder, 2 Electricians, 1 Equip Opr., 1 Foreman, 2 Laborers, 1 Support Truck Driver.

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	
Driller	
Electricians	2
Equipment Operators	1
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	1

Total Crew Size 8
 Monthly Labor Cost \$107,200

25 Embed Spiral Case&Draft Tube

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	1
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	3
Daily Concrete Mixer Truck - 8 CY	4
Daily Semi Trailer Truck	

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	1
Driller	
Electricians	
Equipment Operators	
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	2
Welder	

Total Crew Size 7
 Monthly Labor Cost \$79,600

Duration: 8.7 Months 37.5 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

13.0 MACHINE HALL			
SCHEDULE			
13.3-A Concrete Draft Tubes (El. -41, El. -16)		4,500	CY
Production Rate	(1 crew)	30	CY/DAY
Duration	(Very low production - very restricted work area)	6.9	MONTHS
Contingency		25	%
Final Duration		8.7	MONTHS
Final Duration		37.5	WEEKS
EQUIPMENT/TRUCKING			
OFFSITE TRUCKS			
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;	54	TOTAL WEIGHT, TONS	
1lbs of reinforcement/s.y. of shotcrete	20	TONS/TRUCK	
	3	# OF TRUCKS	
CONCRETE TRUCKS			
	4,500	TOTAL VOLUME, CY	
	8	CY/TRUCK	
	563	# OF TRUCKS FOR TASK	
	4	TRUCKS/DAY	
CONCRETE PUMP TRUCKS			
	(15 TRUCKS)-->	120	CY/DAY
		1	# OF TRUCKS

Assumptions:

Process: Form, Pump, Finish.

Equipment: Concrete Trucks, Concrete Pump Truck, 1 Water Truck, 1 Support Truck.

Crew: 1 Foreman, 2 Laborers, 1 Cement Finisher, 1 Water Truck Driver, 1 Support Driver, 1 CPT Driver.

26 Install Mech. Equip.

Client:	Eagle Crest Energy	Project 080473	Page 1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date 1/21/2009	By NDM
		Checked	By
		Approved	By

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	2
Total Offsite Flatbed/Semi Trucks	5
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration:	<u>6.0</u> Months	<u>26.0</u> Weeks
CONSTANTS:	10 HR/DAY	216.25 HRS/MONTH

INSTALL MECHANICAL EQUIPMENT SCHEDULE		
13.8 96" Dia. Spherical Valve	4	EA
Production Rate	20	DAYS/EA
Duration	3.7	MONTHS
Contingency	25	%
Final Duration	4.6	MONTHS
Final Duration	20.0	WEEKS
NA 350 Ton Bridge Crane	1.0	EA
Production Rate	24	DAYS/EA
Duration	1.1	MONTHS
Contingency	25	%
Final Duration	1.4	MONTHS
Final Duration	6.0	WEEKS
EQUIPMENT/TRUCKING		
OFFSITE FLATBED SEMIS	1.0	UNITS/TRUCK
	5	# OF TRUCKS FOR TASK
	1	TRUCKS/DAY

Assumptions:

Equipment: Crane, Welder, Air Compressor (tools), Support Truck, Generator, Semis.

Installation Crew: 2 Welders, 2 Steel Workers, 1 Equip Opr., 1 Foreman, 2 Laborers, 1 Support Truck Driver.
Schedule: Activities are additive.

Crew	Quantity
Blaister	
Carpenters	
Cement Finisher	
Driller	
Electricians	
Equipment Operators	1
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	2
Steel Worker Foreman	
Truck Drivers	
Welder	2

Total Crew Size	9
Monthly Labor Cost	\$128,600

27 Install Elec. Equip.

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	1
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	1
Total Offsite Flatbed/Semi Trucks	4
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 6.0 Months 26.0 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

INSTALL ELECTRICAL EQUIPMENT SCHEDULE			
NA Install Electrical Equipment (1300 MW)		1,300	MW
Production Rate		60	MW/WEEK
Duration		5.0	MONTHS
Contingency		20	%
Final Duration		6.0	MONTHS
Final Duration		26.0	WEEKS

Assumptions:

Equipment: Forklift, Welder, Air Compressor (tools), Support Truck, Generator.
 Installation Crew: 1 Welder, 2 Electricians, 1 Equip Opr., 1 Foreman, 2 Laborers, 1 Support Truck Driver.

Crew	Quantity
Blauster	
Carpenters	
Cement Finisher	
Driller	
Electricians	2
Equipment Operators	1
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	1

Total Crew Size 8
 Monthly Labor Cost \$107,200

28 Complete Concrete Work

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	1
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	1
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	1
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	10
Daily Concrete Mixer Truck - 8 CY	13
Daily Semi Trailer Truck	

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	2
Driller	
Electricians	
Equipment Operators	1
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	5
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	2
Steel Worker Foreman	
Truck Drivers	2
Welder	

Total Crew Size 15
 Monthly Labor Cost \$187,200

Duration: 9.3 Months 40.3 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

COMPLETE CONCRETE WORK (2ND STAGE) - MULTIPLE ITEMS			
SCHEDULE			
13.3-D Machine Hall (El.9,El.19)			1,100 CY
Production Rate	(1 crew)		100 CY/DAY
Duration	(Half Production - Detailed Finishing)		0.5 MONTHS
Contingency			25 %
Final Duration			0.6 MONTHS
Final Duration			2.8 WEEKS
13.3-E Machine Hall (El.19,El.21)			1,900 CY
Production Rate	(1 crew)		100 CY/DAY
Duration	(Half Production - Detailed Finishing)		0.9 MONTHS
Contingency			25 %
Final Duration			1.1 MONTHS
Final Duration			4.8 WEEKS
13.3-F Machine Hall Slab (El.38)			1,000 CY
Production Rate	(1 crew)		100 CY/DAY
Duration	(Half Production - Detailed Finishing)		0.5 MONTHS
Contingency			25 %
Final Duration			0.6 MONTHS
Final Duration			2.5 WEEKS
13.3-G Machine Hall Walls (El.9,El.18)			500 CY
Production Rate	(1 crew)		100 CY/DAY
Duration	(Half Production - Detailed Finishing)		0.2 MONTHS
Contingency			25 %
Final Duration			0.3 MONTHS
Final Duration			1.3 WEEKS
13.3-H Machine Hall Walls (El.18,El.85)			5,100 CY
Production Rate	(1 crew)		100 CY/DAY
Duration	(Half Production - Detailed Finishing)		2.4 MONTHS
Contingency			25 %
Final Duration			2.9 MONTHS
Final Duration			12.8 WEEKS
13.3-I Machine Hall Roof			2,600 CY
Production Rate	(1 crew)		100 CY/DAY
Duration	(Half Production - Detailed Finishing)		1.2 MONTHS
Contingency			25 %
Final Duration			1.5 MONTHS
Final Duration			6.5 WEEKS
15.3 Transformer Hall Concrete Works			3,900 CY
Production Rate	(1 crew)		100 CY/DAY
Duration	(Half Production - Detailed Finishing)		1.8 MONTHS
Contingency			25 %
Final Duration			2.3 MONTHS
Final Duration			9.8 WEEKS
EQUIPMENT/TRUCKING			
OFFSITE TRUCKS		193	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		10	# OF TRUCKS
CONCRETE TRUCKS		16,100	TOTAL VOLUME, CY
		8	CY/TRUCK
		2,013	# OF TRUCKS FOR TASK
		13	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)-->	120	CY/DAY
		1	# OF TRUCKS

Assumptions:

Process: Form, Pump, Finish.
 Equipment: Concrete Trucks, Concrete Pump Truck, 1 Water Truck, 1 Support Truck, Hoist Crane.
 Crew: 1 Foreman, 4 Laborers, 2 Cement Finishers, 2 Steel Workers, 1 Water Truck Driver, 1 Support Driver, 1 CPT Driver, 1 Crane Oper., 2 Survey
 Schedule: Activities are additive.

29 Struc. & Archit. Construct.

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	1
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	1
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	2
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	2
Generator - Diesel	2
Grout Pump/Plant	1
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	1
Water Truck	
Welder and Generator Set	1
Total Offsite Flatbed/Semi Trucks	43
Daily Concrete Mixer Truck - 8 CY	3
Daily Semi Trailer Truck	18

Crew	Quantity
Blaster	2
Carpenters	4
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	4
Grade Setter	
Foreman	2
Labor Foreman	
Laborers	5
Mechanics	1
Painter	2
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	2
Rigger	
Survey/Rodmen	2
Steel Worker	2
Steel Worker Foreman	
Truck Drivers	2
Welder	1

Total Crew Size 30
 Monthly Labor Cost \$390,100

Duration: 13.1 Months 64.5 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

STRUCTURAL & ARCHITECTURAL CONSTRUCTION SCHEDULE			
NA Structural & Architectural Construction			
Machine Hall Volume	144,000	CY	
Transformer Hall Volume	27,300	CY	
Total Struc. & Arch. Const. Volume	171,300	CY	
Production Rate	1,000	CY/DAY	
Duration	7.9	MONTHS	
Contingency	25	%	
Final Duration	9.9	MONTHS	
Final Duration	42.8	WEEKS	
13.5 Elevator Shaft Construction	1,250	LF	
Production Rate	50	LF/DAY	
Duration	1.2	MONTHS	
Contingency	25	%	
Final Duration	1.4	MONTHS	
Final Duration	6.3	WEEKS	
13.6 Miscellaneous Metal Works - Machine Hall			
Assumed Steel Weight	250	TONS	
Production Rate	20	TONS/DAY	
Duration	0.6	MONTHS	
Contingency	25	%	
Final Duration	0.7	MONTHS	
Final Duration	3.1	WEEKS	
NA Drainage Gallery Excavation - D&B	6,200	CY	
D&B Production Rate	200	CY/DAY	
Duration	1.4	MONTHS	
Contingency	25	%	
Final Duration	1.8	MONTHS	
Final Duration	7.8	WEEKS	
13.7 Drainage Gallery S&A Construction Volume	6,200	CY	
Production Rate	1,000	CY/DAY	
Duration	0.3	MONTHS	
Contingency	25	%	
Final Duration	0.4	MONTHS	
Final Duration	1.6	WEEKS	
13.6 Miscellaneous Steel - Transformer Hall			
Assumed Steel Weight	240	TONS	
Production Rate	20	TONS/DAY	
Duration	0.6	MONTHS	
Contingency	25	%	
Final Duration	0.7	MONTHS	
Final Duration	3.0	WEEKS	
EQUIPMENT/TRUCKING			
DUMP TRUCKS	6,200	TOTAL VOLUME, CY	
	30	CY/TRUCK	
	207	# OF TRUCKS FOR TASK	
	7	LOADS/DAY (MAX.)	
	1.0	CYCLE TIME (HRS)	
	1	REQUIRED # OF TRUCKS	
CONCRETE TRUCKS (Elevator Construction)	463	TOTAL VOLUME, CY	
	8	CY/TRUCK	
	58	# OF TRUCKS FOR TASK	
	3	TRUCKS/DAY	
OFFSITE FLATBED SEMIS (MISC. METAL)	490	TOTAL WEIGHT, TONS	
	20	TONS/TRUCK	
	25	# OF TRUCKS FOR TASK	
	7	TRUCKS/DAY	
OFFSITE FLATBED SEMIS (STRUCT. & ARCH. WORK) (assume 1 ton of materials per 500 CY of Volume)	355	TOTAL WEIGHT, TONS	
	20	TONS/TRUCK	
	18	# OF TRUCKS FOR TASK	
	1	TRUCKS/DAY	
SEMIS - DUMP	20	CY/TRUCK	
	310	# OF TRUCKS FOR TASK	
	10	TRUCKS/DAY	

Assumptions:
 Structural & Architectural work consists of interior walls (i.e. wood, alum., drywall, offices, restrooms, etc.)
 Excavation Then Haul Offsite
 Survey Control
Structural, Architectural, & Misc. Metal Work:
 Equipment: Crane Hoist, Air Compressor, Generator, Flatbed Semis, Fork Lifts, Support Truck.
 Crew: 1 Equip. Oper., 2 Foremans, 4 Carpenters, 4 Laborers, 2 Painters, 2 Plumbers, 1 Welder, 2 Steel Workers.
Elevator & Drainage Gallery Construction:
 Process: Drill, Blast, Excavate, Crane Hoist, Load, Haul, Dump, Load, Haul offsite; Shotcrete.
 Equipment: Track Drill, Excavator, Crane, FE Loader, Dump Truck, FE Loader, Semis; Grout Pump, Support Truck, Water Pump.
 Crew: 1 Driller, 2 Blasters, 4 Equip Opr., 2 survey, 1 DT Driver; Shotcrete/Concrete: 2 Laborers, 1 Forman, 1 Support Driver.
 Schedule: Activities are additive.

33 Complete Elec. Const.

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	1
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	2
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	2
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	5
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 13.4 Months 57.9 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

COMPLETE ELECTRICAL CONSTRUCTION SCHEDULE			
NA Complete Electrical Construction			
Machine Hall Volume	144,000	CY	
Transformer Hall Volume	27,300	CY	
Total Electrical Const. Volume	171,300	CY	
Production Rate	800	CY/DAY	
Duration	9.9	MONTHS	
Contingency	25	%	
Final Duration	12.4	MONTHS	
Final Duration	53.5	WEEKS	
13.5 Cable Shaft Electrical Construction			
Production Rate	75	LF/DAY	
Duration	0.8	MONTHS	
Contingency	25	%	
Final Duration	1.0	MONTHS	
Final Duration	4.3	WEEKS	

Assumptions:

Completing electrical work consists of wiring lighting, power outlets, controls systems, IT requirements, etc.
 Equipment: Fork Lift, Air Compressor, Generator, Flatbed Trucks, Semis, Support Truck.
 Crew: 1 Equip. Oper., 4 Electricians, 1 Foreman, 2 Laborers.

Schedule: Activities are additive.

Crew	Quantity
Blastrer	
Carpenters	
Cement Finisher	
Driller	
Electricians	4
Equipment Operators	1
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	2
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	

Total Crew Size 8
 Monthly Labor Cost \$109,600

35 Construct Upper Res Dams

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	2
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	4
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	4
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	5
Dump Truck, Off-Highway, 34 Ton	4
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	2
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	2
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	2
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Tools

Duration: 8.4 Months 36.4 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

4.0 UPPER RESERVOIR SADDLE DAMS			
SCHEDULE			
4.1 South Saddle Dam		218,400	CY
Production Rate		1,500	CY/DAY
Duration		6.7	MONTHS
Contingency		25	%
Final Duration		8.4	MONTHS
Final Duration		36.4	WEEKS
4.2 West Saddle Dam		72,100	CY
Production Rate		1,500	CY/DAY
Duration		2.2	MONTHS
Contingency		25	%
Final Duration		2.8	MONTHS
Final Duration		12.0	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS (for aggregate material, 90%)		261,450	TOTAL VOLUME, CY
(End Dump 15 Ton)		15	CY/TRUCK
		17,430	# OF TRUCKS FOR TASK
		100	LOADS/DAY (MAX.)
(From processed material stockpile onsite, to batch plant)		0.50	CYCLE TIME (HRS)
		5	REQUIRED # OF TRUCKS
CONCRETE TRUCKS (assume 10% of material)		29,050	TOTAL VOLUME, CY
		8	CY/TRUCK
		3,631	# OF TRUCKS FOR TASK
		38	TRUCKS/DAY
DUMP TRUCKS RCC MATERIAL		290,500	TOTAL VOLUME, CY
(End Dump 34 Ton)		30	CY/TRUCK
		9,683	# OF TRUCKS FOR TASK
		100	LOADS/DAY (MAX.)
(From batch plant to dam site)		0.33	CYCLE TIME (HRS)
		4	REQUIRED # OF TRUCKS

Assumptions:

South and West dams will be constructed concurrently, therefore, equipment and labor is additive for this task.
Survey Control

Upper Reservoir Dams:

Process: Haul Materials, Mix Batch, Haul to Dam Site, Place, Spread, Vibratory Compaction.
Equipment: Dump Trucks (15,34 ton), 2 FE Loaders, 4 Dozers, 2 Graders, 4 Compactors, Water Trucks, Support Trucks.
Crew: 12 Equip Opr., 4 Laborers, 4 Carpenters, 2 survey, 9 DT Drivers, 2 Foreman, 2 Water Truck Driver, 2 Support Driver, 1 Mechanics.
Schedule: Activities are additive.

Crew	Quantity
Blastrer	
Carpenters	4
Cement Finisher	
Driller	
Electricians	
Equipment Operators	12
Grade Setter	
Foreman	2
Labor Foreman	
Laborers	6
Mechanics	1
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	11
Welder	

form work

Total Crew Size 38
Monthly Labor Cost \$464,700

36 Move Unstable Soil LR

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	2
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	5
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	1
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 12.7 Months 55.1 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

MOVE UNSTABLE SOIL - LOWER RESERVOIR			
SCHEDULE			
16.1 Platform Excavation		661,000	CY
Excavator Hourly Production Rate		300	CY/HR
Assume: cycle time = 30 sec, 3.0 cy bucket, 83% eff.			
# of Excavators		1	
Production Rate		3,000	CY/DAY
Duration		10.2	MONTHS
Contingency		25	%
Final Duration		12.7	MONTHS
Final Duration		55.1	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		330,500	TOTAL VOLUME, CY
(assume 50% moved by trucks, 50% moved by equipment)			
		30	CY/TRUCK
		11,017	# OF TRUCKS FOR TASK
		100	LOADS/DAY (MAX.)
		0.50	CYCLE TIME (HRS)
		5	REQUIRED # OF TRUCKS

Assumptions:

Standard Excavation Haul & Dump Onsite

Survey Control

50% of material moved by Dozers & Loaders, other 50% loaded onto dump trucks and hauled to onsite location.

Move Unstable Soil Lower Reservoir:

Process: Excavate, Load, Haul, Dump.

Equipment: 1 Excavator, 1 Grader, 2 Dozers, 2 FE Loaders, Dump Trucks, Water Truck, Support Truck.

Crew: 6 Equip Opr., 3 Laborers, 2 survey, 5 DT Drivers, 1 Foreman, 1 Water Truck Driver, 1 Support Driver.

Crew	Quantity
Blaister	
Carpenters	
Cement Finisher	
Driller	
Electricians	
Equipment Operators	6
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	4
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	6
Welder	

Total Crew Size 19
 Monthly Labor Cost \$227,700

37 Line Upper Res.

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	1
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	1
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	10
Dump Truck, Semi-Trailer	
Excavator, 325	2
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	2
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Crew	Quantity
Blaister	
Carpenters	
Cement Finisher	
Driller	
Electricians	
Equipment Operators	6
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	11
Welder	

Total Crew Size 23
 Monthly Labor Cost \$270,300

Duration: 3.7 Months 27.4 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

LINE UPPER RESERVOIR SCHEDULE			
NA Upper Reservoir Lining (Bottom 3rd of reservoir)	385,587		SY
Lining Depth	3		FT
Total Lining Volume	385,587		CY
Excavator Hourly Production Rate	300		CY/HR
Assume: cycle time = 30 sec, 3.0 cy bucket, 83% eff.			
# of Excavators	2		
Production Rate	6,000		CY/DAY
Duration	3.0		MONTHS
Contingency	25		%
Final Duration	3.7		MONTHS
Final Duration	16.1		WEEKS
NA Compaction of Upper Reservoir Lining	385,587		SY
Compactor Hourly Production Rate	847		CY/HR
Assume: Drum Width = 84", Lift = 12", Passes = 6, V = 4mph			
# of Compactors	1		
Production Rate	8,470		CY/DAY
Duration	2.1		MONTHS
Contingency	25		%
Final Duration	2.6		MONTHS
Final Duration	11.4		WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS	385,587		TOTAL VOLUME, CY
	30		CY/TRUCK
	12,853		# OF TRUCKS FOR TASK
	200		LOADS/DAY (MAX.)
	0.50		CYCLE TIME (HRS)
	10		REQUIRED # OF TRUCKS

Assumptions:

Standard Excavation Haul & Dump Onsite
 Survey Control

Line Upper Reservoir:

Process: Excavate, Load, Haul, Dump, Compact.
 Equipment: 2 Excavators, 1 Dozer, 1 Compactor, 2 FE Loaders, Dump Trucks, Water Truck, Support Truck.
 Crew: 6 Equip Opr., 2 Laborers, 10 DT Drivers, 1 Foreman, 1 Water Truck Driver, 1 Support Driver, 2 survey.

Schedule: Activities are additive.

39 Construct IO Struc. Lower

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	1
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	4
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	1
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	2
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	9
Daily Concrete Mixer Truck - 8 CY	25
Daily Semi Trailer Truck	20

Crew	Quantity
Blaster	2
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	4
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	9
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	7
Welder	

Total Crew Size 26
 Monthly Labor Cost \$297,600

Duration: 4.1 Months 17.8 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

CONSTRUCT LOWER I/O STRUCTURE SCHEDULE			
16.3 Intake Structure Excavation		13,900	CY
Excavator Hourly Production Rate		225	CY/HR
Assume: cycle time = 40 sec, 3.0 cy bucket, 83% eff.			
# of Excavators		1	
Production Rate		2,250	CY/DAY
Duration		0.3	MONTHS
Contingency		25	%
Final Duration		0.4	MONTHS
Final Duration		1.5	WEEKS
NA Intake Structure Rock Excavation (D&B) (20%)		2,780	CY
Production Rate	(1 crew)	400	CY/DAY
Duration		0.3	MONTHS
Contingency		25	%
Final Duration		0.4	MONTHS
Final Duration		1.7	WEEKS
16.2 Access Tunnel Portal Concrete		180	CY
Production Rate	(1 crew)	200	CY/DAY
Duration		0.0	MONTHS
Contingency		25	%
Final Duration		0.1	MONTHS
Final Duration		0.2	WEEKS
16.4 Intake Structure Concrete		6,400	CY
Production Rate	(1 crew)	200	CY/DAY
Duration		1.5	MONTHS
Contingency		25	%
Final Duration		1.8	MONTHS
Final Duration		8.0	WEEKS
16.5 Trashracks, Misc. Metals		100	TONS
Assumed Unit Weight of Steel		475	LBS/CF
Area		5,040	SQ FT
Thickness		6	INCHES
Percent Openings		85	%
Unit Weight		35.6	LBS/SQ FT
Production Rate		200	SQ FT/DAY
Duration		1.2	MONTHS
Contingency		25	%
Final Duration		1.5	MONTHS
Final Duration		6.3	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		13,900	TOTAL VOLUME, CY
		30	CY/TRUCK
		463	# OF TRUCKS FOR TASK
		75	LOADS/DAY (MAX.)
		0.50	CYCLE TIME (HRS)
		4	REQUIRED # OF TRUCKS
OFFSITE TRUCKS		179	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		9	# OF TRUCKS
SEMIS		20	CY/TRUCK
		139	# OF TRUCKS FOR TASK
		20	TRUCKS/DAY
CONCRETE TRUCKS		6,580	TOTAL VOLUME, CY
		8	CY/TRUCK
		823	# OF TRUCKS FOR TASK
		25	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)-->	120	CY/DAY
		2	# OF TRUCKS

Assumptions:

Standard Excavation Haul & Dump Onsite
 Rock Excavation Haul Offsite
 Survey Control

Lower Reservoir I/O Structure:

Process: Excavate, Load, Haul, Dump; Drill, Blast, Excavate, Load, Haul offsite.

Equipment: Track Drill, 1 Excavator, 1 Dozers, 1 FE Loader, Dump Trucks, Semis, CP Trucks, Water Truck, Support Truck, Crane.

Crew: 1 Driller, 2 Blasters, 4 Equip Opr., 8 Laborers, 2 survey, 4 DT Drivers, 1 Foreman, 1 Water Truck Driver, 2 CPT Drivers, 1 Support Driver.

Schedule: Activities are additive.

40 Construct IO Struc. Upper

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	1
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	5
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	1
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	2
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	25
Daily Semi Trailer Truck	20

Crew	Quantity
Blaster	2
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	4
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	9
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	8
Welder	

Total Crew Size 27
 Monthly Labor Cost \$308,300

Duration: 3.9 Months 16.8 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

CONSTRUCT UPPER I/O STRUCTURE SCHEDULE			
4.3.1 Intake Structure Excavation		12,000	CY
Excavator Hourly Production Rate		299	CY/HR
Assume: cycle time = 30 sec, 3.0 cy bucket, 83% eff.			
# of Excavators		1	
Production Rate		2,990	CY/DAY
Duration		0.2	MONTHS
Contingency		25	%
Final Duration		0.2	MONTHS
Final Duration		1.0	WEEKS
NA Intake Structure Rock Excavation (D&B) (20%)		2,400	CY
Production Rate	(1 crew)	400	CY/DAY
Duration		0.3	MONTHS
Contingency		25	%
Final Duration		0.3	MONTHS
Final Duration		1.5	WEEKS
4.3.2 Intake Structure Concrete		6,400	CY
Production Rate	(1 crew)	200	CY/DAY
Duration		1.5	MONTHS
Contingency		25	%
Final Duration		1.8	MONTHS
Final Duration		8.0	WEEKS
16.5 Trashracks, Misc. Metals		100	TONS
Assumed Unit Weight of Steel		475	LBS/CF
Area		5,040	SQ FT
Thickness		6	INCHES
Percent Openings		85	%
Unit Weight		35.6	LBS/SQ FT
Production Rate		200	SQ FT/DAY
Duration		1.2	MONTHS
Contingency		25	%
Final Duration		1.5	MONTHS
Final Duration		6.3	WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS		12,000	TOTAL VOLUME, CY
		30	CY/TRUCK
		400	# OF TRUCKS FOR TASK
		100	LOADS/DAY (MAX.)
		0.50	CYCLE TIME (HRS)
		5	REQUIRED # OF TRUCKS
OFFSITE TRUCKS		177	TOTAL WEIGHT, TONS
Assume 2lbs/ft of rebar/rockbolts; 12ft of rebar/c.y. of conc;		20	TONS/TRUCK
1lbs of reinforcement/s.y. of shotcrete		9	# OF TRUCKS
SEMIS		20	CY/TRUCK
		120	# OF TRUCKS FOR TASK
		20	TRUCKS/DAY
CONCRETE TRUCKS		6,400	TOTAL VOLUME, CY
		8	CY/TRUCK
		800	# OF TRUCKS FOR TASK
		25	TRUCKS/DAY
CONCRETE PUMP TRUCKS	(15 TRUCKS)-->	120	CY/DAY
		2	# OF TRUCKS

Assumptions:

Standard Excavation Haul & Dump Onsite
 Rock Excavation Haul Offsite
 Survey Control

Upper Reservoir I/O Structure:

Process: Excavate, Load, Haul, Dump; Drill, Blast, Excavate, Load, Haul offsite.

Equipment: Track Drill, 1 Excavator, 1 Dozers, 1 FE Loader, Dump Trucks, Semis, CP Trucks, Water Truck, Support Truck, Crane.

Crew: 1 Driller, 2 Blasters, 4 Equip Opr., 8 Laborers, 2 survey, 5 DT Drivers, 1 Foreman, 1 Water Truck Driver, 2 CPT Drivers, 1 Support Driver.

Schedule: Activities are additive.

41 Switchyard Exc.

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	1
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	5
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	1
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	1
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 3.1 Months 13.3 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

SWITCHYARD EXCAVATION SCHEDULE			
NA Switchyard Excavation	107,860		CY
Excavation Depth	5		FT
Excavator Hourly Production Rate	299		CY/HR
Assume: cycle time = 30 sec, 3.0 cy bucket, 83% eff.			
# of Excavators	1		
Production Rate	2,988		CY/DAY
Duration	1.7		MONTHS
Contingency	25		%
Final Duration	2.1		MONTHS
Final Duration	9.0		WEEKS
NA Transfer Station Grading	20,370		CY
Production Rate	1,200		CY/DAY
Duration	0.8		MONTHS
Contingency	25		%
Final Duration	1.0		MONTHS
Final Duration	4.2		WEEKS
EQUIPMENT/TRUCKING			
DUMP TRUCKS	107,860		TOTAL VOLUME, CY
(Assume haul and dump onsite)	30		CY/TRUCK
	3,595		# OF TRUCKS FOR TASK
	100		LOADS/DAY (MAX.)
	0.50		CYCLE TIME (HRS)
	5		REQUIRED # OF TRUCKS

Assumptions:

Standard Excavation Haul & Dump Onsite

Upper Reservoir I/O Structure:

Process: Excavate, Load, Haul, Dump, Grading.

Equipment: 1 Excavator, 1 Dozers, 1 FE Loader, Dump Trucks, Water Truck, Support Truck.

Crew: 3 Equip Opr., 2 Laborers, 5 DT Drivers, 1 Foreman, 1 Water Truck Driver, 1 Support Driver.

Schedule: Activities are additive.

Crew	Quantity
Blaister	
Carpenters	
Cement Finisher	
Driller	
Electricians	
Equipment Operators	3
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	3
Welder	

Total Crew Size 10
 Monthly Labor Cost \$118,500

43 Switchyard Structures

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	1
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	1
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	2
Generator - Diesel	1
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	1
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	1
Total Offsite Flatbed/Semi Trucks	10
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 1.5 Months 6.4 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

SWITCHYARD STRUCTURES SCHEDULE			
NA Switchyard Large Structures			
Number of Structures	6	#	
Assumed Structure Height	100	FT	
Production Rate	50	FT/DAY	
Duration	0.6	MONTHS	
Contingency	25	%	
Final Duration	0.7	MONTHS	
Final Duration	3.0	WEEKS	
NA Switchyard Small Structures			
Number of Structures	6	#	
Assumed Structure Height	30	FT	
Production Rate	50	FT/DAY	
Duration	0.2	MONTHS	
Contingency	25	%	
Final Duration	0.2	MONTHS	
Final Duration	0.9	WEEKS	
15.5-C Switchyard Fencing			
Production Rate	3,200	LF	
Duration	0.5	MONTHS	
Contingency	15	%	
Final Duration	0.6	MONTHS	
Final Duration	2.5	WEEKS	

Assumptions:

Equipment: 1 Crane, 1 Flatbed Truck, 2 Support Trucks, 1 Forklift, Generator, Welder.
 Crew: 1 Crane Opr., 1 Equip. Opr., 2 Laborers, 2 Steel Workers, 1 Foreman, 2 Welders.
 Schedule: Activities are additive.

Crew	Quantity
Blaister	
Carpenters	
Cement Finisher	
Driller	
Electricians	
Equipment Operators	2
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	2
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	2
Steel Worker Foreman	
Truck Drivers	
Welder	2

Total Crew Size 9
 Monthly Labor Cost \$131,500

44 Trans. Line Foundations

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	1
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	1
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	1
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	1
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	24
Daily Concrete Mixer Truck - 8 CY	7
Daily Semi Trailer Truck	

Crew	Quantity
Blaister	
Carpenters	
Cement Finisher	
Driller	1
Electricians	
Equipment Operators	3
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	2
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	2
Steel Worker Foreman	
Truck Drivers	1
Welder	

Total Crew Size 10
 Monthly Labor Cost \$131,700

Duration: 4.6 Months 20.0 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

TRANSMISSION LINE FOUNDATIONS SCHEDULE			
NA Transmission Line Foundations - Concrete			
Line Length	10	MILES	
Assumed Structures/Mile	8	#/MILE	
Peirs Per Structure	4	#/STRUCTURE	
Total # of Peirs	320	#	
Estimated Length of Peirs	50	FT	
Peir Diameter	3	FT	
Total Volume	4,189	CY	
Production Rate	4	PEIRS/DAY	
Duration	3.7	MONTHS	
Contingency	25	%	
Final Duration	4.6	MONTHS	
Final Duration	20.0	WEEKS	
NA Transmission Line Foundations - Steel			
Total # of Peirs	320	#	
Estimated Length of Peirs	50	FT	
Peir Diameter	3	FT	
# of Bars/Sq. ft	5	#/SQ FT	
Bar Size	6	#	
Bar Weight Per Foot	1.5	LBS/FT	
Shear Reinforcement Bar Size	4	#	
Shear Reinforcement Weight Per Foot	0.67	LBS/FT	
Total Weight	475	TONS	
EQUIPMENT/TRUCKING			
CONCRETE TRUCKS	4,189	TOTAL VOLUME, CY	
	8	CY/TRUCK	
	524	# OF TRUCKS FOR TASK	
	7	TRUCKS/DAY	
CONCRETE PUMP TRUCKS	(15 TRUCKS)--> 120	CY/DAY	
	1	# OF TRUCKS	
OFFSITE FLATBED SEMIS (reinforcement)	20	TONS/TRUCK	
	24	# OF TRUCKS FOR TASK	
	1	TRUCKS/DAY	

Assumptions:

Process: Drill Peirs, Place Steel, Pour Concrete, Finish Work.
 Equipment: 1 Tracked Drill, 1 Front End Loader, 1 Crane, 1 Flatbed Truck, 1 Support Truck, 1 Conc. Pump Truck.
 Crew: 3 Equip. Opr., 2 Laborers, 2 Steel Workers, 1 Foreman, 1 CPT Driver.

45 Trans. line stringing

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	2
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	1
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	2
Generator - Diesel	
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	1
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 4.0 Months 17.2 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

TRANSMISSION LINE STRINGING SCHEDULE			
NA Transmission Line Stringing			
Transmission Line Length	10	MILES	
# of Lines	8	#	
Sag Factor	1.30		
Total Line Length	549,200	FT	
Production Rate	8,000	FT/DAY	
Duration	3.2	MONTHS	
Contingency	25	%	
Final Duration	4.0	MONTHS	
Final Duration	17.2	WEEKS	

Assumptions:

Equipment: 2 Cranes, 1 Flatbed Truck, 2 Support Truck, 1 Forklift.
Crew: 3 Equip. Opr., 3 Laborers, 1 Foreman.

Crew	Quantity
Blafter	
Carpenters	
Cement Finisher	
Driller	
Electricians	
Equipment Operators	3
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	

Total Crew Size 7
Monthly Labor Cost \$86,600

47 Inst. H2O Supply Pipe & RO S

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	1
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	1
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	5
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	1
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	1
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	1
Total Offsite Flatbed/Semi Trucks	208
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	
Driller	
Electricians	
Equipment Operators	4
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	3
Mechanics	
Painter	
Pile Driver	
Pipe Foreman	1
Pipe Layer	2
Plumber	
Rigger	
Survey/Rodmen	2
Steel Worker	
Steel Worker Foreman	
Truck Drivers	6
Welder	

Total Crew Size 19
 Monthly Labor Cost \$233,600

Duration: 6.7 Months 29.2 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

INSTALL WATER SUPPLY LINE SCHEDULE		
NA Pipeline Excavation		
Excavation Length	75,000	FT
Excavation Unit Volume	1.6	CY/FT
(assume 30 Steel pipe, 10,000 gpm, 3' Backfill)		
Excavation Total Volume	120,000	CY
Excavator Hourly Production Rate	200	LCY/HR
# of Excavators	1	
Production Rate	2,000	CY/DAY
Duration	2.8	MONTHS
Contingency	25	%
Final Duration	3.5	MONTHS
Final Duration	15.0	WEEKS
NA Pipeline Bedding Material (25% of Backfill)		
	25,500	CY
Production Rate	1,000	CY/DAY
Duration	1.2	MONTHS
Contingency	25	%
Final Duration	1.5	MONTHS
Final Duration	6.4	WEEKS
Lag from Excavation	2.0	WEEKS
Maximum Duration	8.4	WEEKS
NA Pipeline Installation		
	75,000	FT
Production Rate	1,000	FT/DAY
Duration	3.5	MONTHS
Contingency	25	%
Final Duration	4.3	MONTHS
Final Duration	18.8	WEEKS
Lag from Excavation	4.0	WEEKS
Maximum Duration	22.8	WEEKS
NA Compaction Pipeline (85% of Exc.)		
	102,000	CY
Compactor Hourly Production Rate	120	CY/HR
Assume: Drum Width = 50", Lift = 4", Passes = 6, V = 4mph		
# of Compactors	1	
Production Rate	1,204	CY/DAY
Duration	3.9	MONTHS
Contingency	25	%
Final Duration	4.9	MONTHS
Final Duration	21.2	WEEKS
Lag from Installation	4.0	WEEKS
Maximum Duration (incl. this lag + install lag)	29.2	WEEKS
EQUIPMENT/TRUCKING		
DUMP TRUCKS (bedding material onsite)	25,500	TOTAL VOLUME, CY
(Assume bedding material is 25% of backfill)	15	CY/TRUCK
	1,700	# OF TRUCKS FOR TASK
	80	LOADS/DAY (MAX.)
	0.50	CYCLE TIME (HRS)
	5	REQUIRED # OF TRUCKS
OFFSITE SEMIS (pipe material)	360	LF/TRUCK
(Assume 40' sticks, 9 per truck)	208	# OF TRUCKS FOR TASK
	3	TRUCKS/DAY

Assumptions:

Upper Reservoir I/O Structure:

Process: Excavate, Place Bedding, Install Pipe, Backfill, Compact.

Equipment: 1 Excavator, 1 Dozers, 1 FE Loader, 1 Sheepsfoot Compactor, Dump Trucks, Water Truck, Support Truck, Welder.

Crew: 4 Equip Opr., 2 Laborers, 5 DT Drivers, 1 Foreman, 1 Water Truck Driver, 1 Support Driver, 1 Pipe

Forman, 2 Pipe Layers, 2 Survey.

Schedule: Activities are additive.

48 Reservoir Filling

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	1
Generator - Diesel	
Grout Pump/Plant	
Hydroseed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 48.0 Months 207.6 Weeks

CONSTANTS: 20 HR/DAY 216.25 HRS/MONTH

RESERVOIR FILLING SCHEDULE			
NA Reservoir Filling			
Reservoirs Active Storage	17,700	AC-FT	
Upper Reservoir Inactive Storage	2,300	AC-FT	
Lower Reservoir Inactive Storage	4,200	AC-FT	
Total Storage	24,200	AC-FT	
Annual Seepage	1,628	AC-FT	
Annual Evaporation	1,763	AC-FT	
Pumping Rate	6,000	GPM	
Final Duration (From Reservoir Filling Calculations, attached)	48.0	MONTHS	
Final Duration	207.6	WEEKS	

Assumptions:

Equipment: Support Truck.
Crew: 1 Equip Opr., 1 Laborer, 1 Mechanic.

Crew	Quantity
Blauster	
Carpenters	
Cement Finisher	
Driller	
Electricians	
Equipment Operators	1
Grade Setter	
Foreman	
Labor Foreman	
Laborers	1
Mechanics	1
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	

Total Crew Size 3
Monthly Labor Cost \$38,000

49 U 1 START

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	
Generator - Diesel	1
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 3.1 Months 13.4 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

UNIT 1 START-UP

Assumptions:

Process: Start-up involves inspections and testing of all electrical and mechanical equipment prior to unit initiation.

Equipment: Air Compressor, Generator.

Crew: 3 Electricians, 3 Mechanics, 1 Foreman.

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	
Driller	
Electricians	3
Equipment Operators	
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	
Mechanics	3
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	

Total Crew Size 7
 Monthly Labor Cost \$101,500

51 U 2 START

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	
Generator - Diesel	1
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 2.8 Months 12.0 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

UNIT 2 START-UP

Assumptions:

Process: Start-up involves inspections and testing of all electrical and mechanical equipment prior to unit initiation.

Equipment: Air Compressor, Generator.

Crew: 3 Electricians, 3 Mechanics, 1 Foreman.

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	
Driller	
Electricians	3
Equipment Operators	
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	
Mechanics	3
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	

Total Crew Size 7
 Monthly Labor Cost \$101,500

53 U 3 START

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	
Generator - Diesel	1
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 2.8 Months 12.0 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

UNIT 3 START-UP

Assumptions:

Process: Start-up involves inspections and testing of all electrical and mechanical equipment prior to unit initiation.

Equipment: Air Compressor, Generator.

Crew: 3 Electricians, 3 Mechanics, 1 Foreman.

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	
Driller	
Electricians	3
Equipment Operators	
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	
Mechanics	3
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	

Total Crew Size 7
 Monthly Labor Cost \$101,500

55 U 4 START

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	
Generator - Diesel	1
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 2.8 Months 12.0 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

UNIT 4 START-UP

Assumptions:

Process: Start-up involves inspections and testing of all electrical and mechanical equipment prior to unit initiation.

Equipment: Air Compressor, Generator.

Crew: 3 Electricians, 3 Mechanics, 1 Foreman.

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	
Driller	
Electricians	3
Equipment Operators	
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	
Mechanics	3
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	
Truck Drivers	
Welder	

Total Crew Size 7
 Monthly Labor Cost \$101,500

57 FINISH PROJECT

Client:	Eagle Crest Energy	Project	080473	Page	1
Subject:	Eagle Mountain Construction Schedule and Equipment	Date	1/21/2009	By	NDM
		Checked		By	
		Approved		By	

EQUIPMENT	Quantity
On Site	
Air Compressor	1
Backhoe / Front End Loader, Wheeled	
Backhoe, Tracked	
Chipper, Wood	
Compactor, Sheepsfoot, Self-Propelled	
Compactor, Vibratory, Self-Propelled	
Concrete Pump	
Crane - 40 Ton	
Crane - 70 Ton	
Dozer, D5	
Dozer, D6	
Dozer, D8	
Dozer, D10	
Drill, Tracked	
Dump Truck, End Dump, 15 Ton	
Dump Truck, Off-Highway, 34 Ton	
Dump Truck, Semi-Trailer	
Excavator, 325	
Forklift, Rough Terrain	
Front End Loader, Tracked	
Front End Loader, Wheeled	
Fuel Truck / Support Truck	3
Generator - Diesel	1
Grout Pump/Plant	
Hydrosed Sprayer, Truck Mounted	
Grader, H14	
Pile Driver	
Pump Truck - Concrete	
Powder Truck	
Scraper, Self-propelled, 21 CY	
Truck, Flatbed	
Tunnel Rig (TBM)	
Water Pump, Diesel	
Water Truck	
Welder and Generator Set	
Total Offsite Flatbed/Semi Trucks	
Daily Concrete Mixer Truck - 8 CY	
Daily Semi Trailer Truck	

Duration: 2.8 Months 12.0 Weeks

CONSTANTS: 10 HR/DAY 216.25 HRS/MONTH

FINISH PROJECT

Assumptions:

Finish Project involves final inspections and testing of all major electrical and mechanical equipment, final tunnel and I/O structures inspections, and all other ancillary structures and equipment inspections and testing.
 Equipment: 3 Support Trucks, Air Compressor, Generator.
 Crew: 3 Electricians, 3 Mechanics, 1 Steel Worker Foreman, 2 Laborers, 1 Foreman.

Crew	Quantity
Blaster	
Carpenters	
Cement Finisher	
Driller	
Electricians	3
Equipment Operators	
Grade Setter	
Foreman	1
Labor Foreman	
Laborers	2
Mechanics	3
Painter	
Pile Driver	
Pipe Foreman	
Pipe Layer	
Plumber	
Rigger	
Survey/Rodmen	
Steel Worker	
Steel Worker Foreman	1
Truck Drivers	
Welder	

Total Crew Size 10
 Monthly Labor Cost \$140,700

TBM Advancement Rates - Lookup Table

Type A	120	ft/day
Type B	95	ft/day
Type C	45	ft/day

D&B Advancement Rates - Lookup Table

D&B Rate Reduction Factor (%) =		25
Type A	37	ft/day
Type B	32	ft/day
Type C	17	ft/day

Upper Pressure Tunnel

Begin Sta. (ft)	End Sta. (ft)	Length (ft)	Rock Type (A, B, C)	Geologic Rock Description	Excavation Method (TBM, D&B)	Advancement Rate (ft/day)	Duration (days)	Cummulative Duration (days)
0	500	500	B	Granite	TBM	95	5	5
500	1500	1000	C	Quartzite	TBM	45	22	27
1500	2500	1000	C	Schistose meta-arkose	TBM	45	22	50
2500	3000	500	C	Quartzite	TBM	45	11	61
3000	4000	1000	C	Schistose meta-arkose	TBM	45	22	83
Total = 4000 ft						Total =	83	16.7 weeks
						Contingency (%) =	25	
						Estimated Total Construction Duration =	104	20.8 weeks

Original Construction Schedule Estimate

Duration = 22.2 weeks
Length = 4000 ft
Advancement Rate = 36 ft/day

Calc. Advancement Rate = 39 ft/day

Vertical Shaft

Begin Sta. (ft)	End Sta. (ft)	Length (ft)	Rock Type (A, B, C)	Geologic Rock Description	Excavation Method (TBM, D&B)	Advancement Rate (ft/day)	Duration (days)	Cummulative Duration (days)
0	300	300	B	Granite	D&B	32	9	9
300	600	300	B	Granite	D&B	32	9	19
600	900	300	B	Granite	D&B	32	9	28
900	1200	300	C	Schistose meta-arkose	D&B	17	18	46
1200	1398	198	C	Schistose meta-arkose	D&B	17	12	58
Total = 1398 ft						Total =	58	11.6 weeks
						Contingency (%) =	50	
						Estimated Total Construction Duration =	87	17.4 weeks

Original Construction Schedule Estimate

Duration = 39.8 weeks
Length = 1398 ft
Advancement Rate = 7 ft/day

Calc. Advancement Rate = 16 ft/day

Lower Pressure Tunnel

Begin Sta. (ft)	End Sta. (ft)	Length (ft)	Rock Type (A, B, C)	Geologic Rock Description	Excavation Method (TBM, D&B)	Advancement Rate (ft/day)	Duration (days)	Cummulative Duration (days)
0	200	200	C	Granite	TBM	45	4	4
200	500	300	C	Quartz Monzonite	TBM	45	7	11
500	1000	500	C	Granite	TBM	45	11	22
1000	1200	200	C	Schistose meta-arkose	TBM	45	4	27
1200	1560	360	C	Schistose meta-arkose	TBM	45	8	35
Total = 1560 ft						Total =	35	7 weeks
						Contingency (%) =	25	
						Estimated Total Construction Duration =	43	8.7 weeks

Original Construction Schedule Estimate

Duration = 32.6 weeks
Length = 1560 ft
Advancement Rate = 10 ft/day

Calc. Advancement Rate = 36 ft/day

Penstocks & Draft Tubes

Begin Sta. (ft)	End Sta. (ft)	Length (ft)	Rock Type (A, B, C)	Geologic Rock Description	Excavation Method (TBM, D&B)	Advancement Rate (ft/day)	Duration (days)	Cummulative Duration (days)	
0	350	350	C	Granite	D&B	17	21	21	
350	850	500	C	Granite	D&B	17	30	51	
850	1200	350	C	Granite	D&B	17	21	72	
1200	1200	0	C	-	D&B	17	0	72	
1200	1200	0	C	-	D&B	17	0	72	
Total = 1200 ft							Total = 72	14.4 weeks	
							Contingency (%) = 50		
							Estimated Total Construction Duration = 108	21.6 weeks	

Original Construction Schedule Estimate

Duration = 22.6 weeks
Length = 1200 ft
Advancement Rate = 11 ft/day

Calc. Advancement Rate = 11 ft/day

Tailrace Tunnel

Begin Sta. (ft)	End Sta. (ft)	Length (ft)	Rock Type (A, B, C)	Geologic Rock Description	Excavation Method (TBM, D&B)	Advancement Rate (ft/day)	Duration (days)	Cummulative Duration (days)	
0	600	600	B	Granite	TBM	95	6	6	
600	2500	1900	C	Quartz Monzonite	TBM	45	42	49	
2500	4000	1500	B	Granite	TBM	95	16	64	
4000	5000	1000	B	Schistose meta-arkose	TBM	95	11	75	
5000	6835	1835	C	Schistose meta-arkose	TBM	45	41	116	
Total = 6835 ft							Total = 116	23.2 weeks	
							Contingency (%) = 25		
							Estimated Total Construction Duration = 145	29 weeks	

Original Construction Schedule Estimate

Duration = 31.2 weeks
Length = 6835 ft
Advancement Rate = 44 ft/day

Calc. Advancement Rate = 47 ft/day

Access Tunnel

Begin Sta. (ft)	End Sta. (ft)	Length (ft)	Rock Type (A, B, C)	Geologic Rock Description	Excavation Method (TBM, D&B)	Advancement Rate (ft/day)	Duration (days)	Cummulative Duration (days)	
0	500	500	B	Granite	TBM	95	5	5	
500	2000	1500	C	Quartz Monzonite	TBM	45	33	39	
2000	4000	2000	C	Granite	TBM	45	44	83	
4000	4500	500	B	Schistose meta-arkose	TBM	95	5	88	
4500	6625	2125	C	Schistose meta-arkose	TBM	45	47	136	
Total = 6625 ft							Total = 136	27.2 weeks	
							Contingency (%) = 25		
							Estimated Total Construction Duration = 169	33.9 weeks	

Original Construction Schedule Estimate

Duration = 48.6 weeks
Length = 6625 ft
Advancement Rate = 27 ft/day

Calc. Advancement Rate = 39 ft/day

Cable Shaft

Begin Sta. (ft)	End Sta. (ft)	Length (ft)	Rock Type (A, B, C)	Geologic Rock Description	Excavation Method (TBM, D&B)	Advancement Rate (ft/day)	Duration (days)	Cummulative Duration (days)	
0	500	500	B	Granite	D&B	32	16	16	
500	1000	500	B	Quartz Monzonite	D&B	32	16	31	
1000	1500	500	B	Granite	D&B	32	16	47	
1500	2010	510	C	Schistose meta-arkose	D&B	17	30	77	
2010	2010	0	C	-	D&B	17	0	77	
Total = 2010 ft							Total = 77	15.5 weeks	
							Contingency (%) = 50		
							Estimated Total Construction Duration = 116	23.3 weeks	

Original Construction Schedule Estimate

Duration = 26 weeks
Length = 2010 ft
Advancement Rate = 15 ft/day

Calc. Advancement Rate = 17 ft/day

GEI Consultants, Inc.
080473 Eagle Mountain Pumped Storage Project
Tunnel Boring Maching Advancement Rates
1/20/2009
NDM

Assumptions:

Work days/week: 5
Work Hours/Day: 20

Average Advancment Rate	120	ft/day	Equation
Std. Dev. (rounded) =	50	ft/day	
Type A (std. TBM Exc.) =	120	ft/day	Average Value
Type B (CIP Liner Req'd) =	95	ft/day	Average Value - (1/2) Std. Dev.
Type C (Diff. Exc w/ Conc. Liner) =	45	ft/day	Average Value - (1.5) Std. Dev.

Diameter (ft)	Rock Type	Advancement Rate	Units	Advance ment Rate (ft/day)	Source
16	A - Std. TBM Exc.	225	m/week	148	Hatch Mott MacDonald Tunnel Estimating Database spreadsheet, Appendix D of VLHC in Northern Illinois, Fermi National Accelerator Labs.
16	B - CIP Liner	195	m/week	128	
16	C - Difficult Exc. Conc Liner	102	m/week	67	
NA	NA	16	m/day	52	http://www-project.slac.stanford.edu/lc/local/documentation/pdf/TBM-
NA	Limestone	8.8	ft/hr	176	Peter J. Tarkoy, Predicting TBM Penetration Rates in Selected Rock Types, Figure 3, Plot of group averages, 1973.
	Shale & Siltstone	9.5	ft/hr	190	
	Sandstone	11.2	ft/hr	224	
	Orthoquartzite	5.2	ft/hr	104	
	Quartzite	3.6	ft/hr	72	
NA	Schist	3.5	ft/hr	70	
					Projects Involving Robbins Equipment reported by TunnelBuilder.com,
11.5	Sandstone	55.0	m/day	180	Bolivia, Misicuni
16.2	Hardrock	28.8	m/day	94	China, Shanxi
13.3	NA	39.1	m/day	128	Ecuador, Manabi
32.8	Hardrock	30.0	m/day	98	New Zealand, Manapouri
18.7	NA	38.0	m/day	125	Peru, Chinango
18.2	Limestone	57.2	m/day	188	United States, Illinois
10.4	Sandstone, shale	58.1	m/day	191	United States, Colorado, Plateau Creek
11	Sandstones	50	ft/day	50	Jacobs Associates. Beatriz Reservoir Intake Tunnel, Tunnel Feasibility
NA	Quartzite	20	m/day	66	EM 1110-2-2901, May 30, 1997, Low values used of Drilling Rate Index range given in Table C-10.
NA	Basalt	30	m/day	98	
NA	Gneiss	30	m/day	98	
NA	Mica Gneiss/Coarse Granite	30	m/day	98	
NA	Schist/Phyllite	35	m/day	115	
NA	Med/Fine Granite	30	m/day	98	
NA	Limestone	50	m/day	164	
NA	Shale	55	m/day	180	
NA	Sandstone	45	m/day	148	
NA	Siltstone	60	m/day	197	

**PROJECT FEATURES
& COSTS**

Item	Description	Unit	Quantity	Unit Cost	Cost
1	CONSTRUCTION AND ACCESS ROADS				
	1.1 Construction Road to Saddle Dams*	LF	13,800	\$95	1,306,800
	1.2 Road from South Dam to Intake Platform*	LF	1,800	\$95	170,500
	1.3 Road from intake platform down to Channel	LF	2,000	\$95	189,400
	1.4 Road from South Dam to Power Tunnel Portal Const.	LF	10,100	\$95	956,400
	1.5 Extension to Cable Elevator Shafts & Surge Tank	LF	4,400	\$95	416,700
	1.5 Access road to Lower Inlet Platform	LF	4,000	\$95	378,800
	1.6 Inlet Platform Down to Channel	LF	3,000	\$95	284,100
	* Existing unpaved mining road				
					3,702,700
2	CONSTRUCTION TUNNELS				
	2.1 To Machine Hall Roof	CY	2,900	\$208	603,200
	2.2 To Transformer Hall Roof	CY	1,700	\$208	353,600
	2.3 To Power Shaft Construction	CY	8,500	\$208	1,768,000
	2.4 To Tailrace Surge Tank Construction Access	CY	1,900	\$208	395,200
					3,120,000
3	ACCESS TUNNELS				
	3.1 Main Access Tunnel (6628')				
	3.1.1 Excavation	CY	192,500	\$208	40,040,000
	3.1.2 Prelining Shotcrete(w/wire-mesh)	SY	20,600	\$109	2,245,400
	3.1.3 Invert concrete	CY	6,900	\$500	3,450,000
	3.1.4 Rock anchors (15' long)	EA	5,000	\$300	1,500,000
	3.2 Drainage Gallery Access Tunnel (L=80')				
	3.2.1 Excavation	CY	800	\$208	166,400
	3.2.2 Invert Concrete	CY	10	\$500	5,000
	3.2.3 Prelining	SY	200	\$72	14,400
	3.3 Tailrace Rock Trap Access Tunnel (L = 100')	LF	100	\$780	78,000
					47,499,200
4	UPPER RESERVOIR				
	4.1 South Saddle Dam	CY	218,400	\$100	21,840,000
	4.2 West Saddle dam	CY	72,100	\$100	7,210,000
	4.3 Upper Reservoir Intake Structure				
	4.3.1 Excavation	CY	12,000	\$25	300,000
	4.3.2 Concrete	CY	6,400	\$878	5,616,000
	4.3.3 Trashracks, Gares, misc. Metals	Tons	100	\$10,000	1,000,000
					35,966,000
5	UPPER PRESSURE TUNNEL (3963')				
	5.1 Tunnel Excavation - TBM	CY	133,300	\$156	20,794,800
	5.2 Tunnel Prelining & Support (3')	CY	35,300	\$109	3,847,700
	5.3 Tunnel Lining	CY	36,300	\$1,080	39,204,000
	5.4 Miscellaneous Concrete (bent, plug etc)	CY	5,400	\$1,080	5,832,000
	5.5 Contact Grouting	CF	27,200	\$42	1,142,400
					69,514,800
6	SURGE TANK				
	6.1 Shaft Excavation - D/B	CY	8,900	\$208	1,851,200
	6.2 Benching Excavation	CY	35,300	\$150	5,295,000
	6.3 Concrete Works	CY	700	\$878	614,300
					7,760,500
7	POWER SHAFT (1348')				
	7.1 Power Shaft Excavation (1208') - D/B	CY	40,600	\$208	8,444,800
	7.2 Shaft Prelining & support	SF	2,200	\$72	158,400
	7.3 Concrete Lining	CY	11,100	\$1,080	11,988,000
	7.4 Contact Grouting	CF	9,300	\$42	390,600
					20,981,800
8	LOWER PRESSURE TUNNEL (1563')				
	8.1 Tunnel Excavation - TBM	CY	52,600	\$156	8,205,600
	8.2 Tunnel Prelining & Support (6')	SY	13,900	\$109	1,515,100
	8.3 Tunnel Lining	CY	14,300	\$1,080	15,444,000
	8.4 Miscellaneous Concrete (bent, plug etc)	CY	5,900	\$1,080	6,372,000
	8.5 Contact Grouting	CF	10,700	\$42	449,400
	8.6 Curtain Grouting	CF	5,800	\$42	243,600
					32,229,700
9	PENSTOCK MANIFOLD (350')				
	9.1 Manifold Tunnel Excavation - D/B	CY	7,400	\$208	1,539,200
	9.2 Manifold Tunnel Prelining & Support (3', 75%)	SY	2,400	\$72	172,800
	9.3 Concrete Lining	CY	1,800	\$1,080	1,944,000
	9.4 Concrete Plug	CY	10,700	\$1,080	11,556,000
					15,212,000
10	PENSTOCKS (500')				
	10.1 Penstock Tunnel Excavation - D/B	CY	18,900	\$208	3,931,200
	10.2 Penstock Tunnel Prelining & Support (3', 30%)	SY	3,800	\$72	273,600
	10.3 Steel liner installation	Tons	3,000	\$12,000	36,000,000
	10.4 Concrete Filling around Liner	CY	5,200	\$1,080	5,616,000
	10.5 Contact Grouting	LF	2,000	\$59	118,000
	10.6 Curtain Grouting	LS	1	\$92,000	92,000
					46,030,800
11	DRAFT TUBE MANIFOLD (350')				
	11.1 Manifold Tunnel Excavation - D/B	CY	7,400	\$208	1,539,200
	11.2 Manifold Tunnel Prelining & Support (3', 75%)	SY	2,400	\$72	172,800
	11.3 Concrete Lining	CY	1,600	\$1,080	1,728,000
	11.4 Tube Fingers Excavation (Total L=620')	CY	6,500	\$208	1,352,000
	11.5 Tube Fingers Prelining	SY	4,100	\$72	295,200
	11.6 Tube Fingers Concrete	CY	1,200	\$1,080	1,296,000
					6,383,200
12	TAILRACE TUNNEL (6635')				
	12.1 Tailrace Tunnel Excavation - TBM	CY	223,100	\$156	34,803,600
	12.2 Tailrace Tunnel Prelining & Support (3', 100%)	SY	78,700	\$109	8,578,300
	12.3 Plug Concrete Construction	CY	3,400	\$1,080	3,672,000
	12.4 Plug -Radial Grout Injection	EA	1	\$2,000	2,000
	12.5 Rock Trap Construction	LS	1	\$950,000	950,000
	12.6 D/S Surge Tank Construction	LS	1	\$6,000,000	6,000,000
					54,095,900

**PROJECT FEATURES
& COSTS**

Item	Description	Unit	Quantity	Unit Cost	Cost
13	MACHINE HALL				
	13.1 Excavation Draft Tubes(El.-16,El.-36)	CY	4,600	\$208	956,800
	Benching excavation (El.-16,18)	CY	22,700	\$156	3,541,200
	Hall Benching excavation (El.18,El.85)	CY	64,000	\$156	9,984,000
	Roof excavation (El.85- 100)	CY	9,900	\$208	2,059,200
	13.2 Roof &Walls Support (W/3' shotcrete)	SF	96,700	\$42	4,082,700
	13.3 Concrete				
	Draft Tubes El.-41- EL.-16	CY	4,500	\$1,000	4,500,000
	Machine Hall El.-16- El.-12	CY	2,700	\$800	2,160,000
	Machine Hall El.-12- El.-9	CY	10,100	\$1,000	10,100,000
	Machine Hall El.9- El. 19	CY	1,100	\$1,000	1,100,000
	Machine Hall El.18- El.21	CY	1,900	\$800	1,520,000
	Machine Hall slab El. 38	CY	1,000	\$1,000	1,000,000
	Machine Hall Walls El. 9- El.18	CY	500	\$1,000	500,000
	Machine Hall Walls El.18- El.85	CY	5,100	\$1,000	5,100,000
	Machine Hall Roof	CY	2,600	\$1,000	2,600,000
	13.4 Draft Tube Liner	Tons	220	\$12,000	2,640,000
	Draft Tube Contact Grouting	LS	1	\$340,000	340,000
	13.5 Elevator Shaft Construction	LS	1	\$1,194,647	1,194,600
	13.6 Miscellaneous Metal works	LS	1	\$500,000	500,000
	13.7 Drainage Gallery Construction	LS	1	\$852,013	852,000
	13.8 96" Dia. Spherical Valve	EA	4	\$360,000	1,440,000
	14 TURBINES/GENERATORS				
	14.1 Water to Wire Package	EA	4	\$60,000,000	240,000,000
	14.2 Installation	EA	4	\$15,000,000	60,000,000
	15 TRANSFORMER HALL				
	15.1 Excavation				
	Transformer Hall Excavation	CY	30,800	\$156	4,820,400
	Niche Excavation	CY	2,700	\$208	561,600
	Cable Gallery Excavation	CY	700	\$208	145,600
	A/C Gallery Excavation	CY	100	\$208	20,800
	Cable Shaft Excavation	CY	4,700	\$156	733,200
	15.2 Roof & Wall Support				
	Transformer Hall	SF	44,300	\$35	1,566,500
	Niche	SF	2,500	\$12	30,400
	Cable Gallery	SF	3,200	\$12	38,900
	A/C Gallery	SF	100	\$12	1,200
	Cable Shaft	SF	56,900	\$12	691,200
	15.3 Concrete works	CY	3,900	\$1,000	3,900,000
	15.4 Miscellaneous Steel	LS	1	\$472,764	472,800
	15.5 Transfer Station				
	Grading	CY	820	\$10	8,200
	Gravel Base	CY	410	\$40	16,400
	Fence	LS	1	\$20,000	20,000
	Towers	Tons	7	\$15,000	105,000
	Footings	LS	1	\$18,000	18,000
	O/H Transmission Lines, (Two pili. each 0.9 mile long)	Mile	1.8	\$300,000	540,000
	16 LOWER RESERVOIR				
	16.1 Platform Excavation	CY	661,000	\$25	16,525,000
	16.2 Access tunnel portal concrete	CY	180	\$500	90,000
	16.3 Intake structure excavation	CY	13,900	\$40	556,000
	16.4 Intake structure concrete	CY	6,400	\$800	5,120,000
	16.5 Trashracks, Gares, misc. Metals	Tons	100	\$10,000	1,000,000
	17 Unlisted Items (10% of all other items)	LS	1	\$73,564,800	73,564,800
	Total				809,213,100
	Base Construction Subtotal (BCS)				\$809,213,100
	Mobilization @ 5% of BCS				\$40,460,700
	Construction Contingencies (15% of BCS+Mob.)				\$127,451,100
	Direct Construction Subtotal (DCS)				\$977,124,900
	Design Engineering (4% of DCS)				\$39,085,000
	Permitting (.5% of DCS)				\$4,885,600
	Legal and Administrative Costs (.3% of DCS)				\$2,931,400
	Construction Administration and Engineering (5% of DCS)				\$48,856,200
	Opinion of Probable Construction Costs (OPCC) 2008				\$1,072,880,000

56,170,500

300,000,000

13,690,200

23,291,000

73,564,800

RESERVOIR FILLING CALCULATIONS

Purpose: Estimate the time required to fill the Eagle Mountain Pumped Storage Project Reservoirs to full operating capacity.

Procedure: Calculate inflow, losses, and final reservoir levels based on a monthly time step.

- Calculation Steps:**
1. Determine volume of groundwater pumped from wells to Lower Reservoir (varies by month).
 2. Determine Lower Reservoir storage and water surface elevation after inflow from groundwater wells.
 3. Subtract seepage and evaporation losses from Lower Reservoir.
 4. If Lower Reservoir level is above 25% active capacity, pump available water up to the Upper Reservoir.
 5. Determine the Upper Reservoir storage and water surface elevation after inflow from Lower Reservoir.
 6. Subtract seepage and evaporation losses from Upper Reservoir.
 7. Repeat steps 1 through 6 until Upper Reservoir is at full capacity.

See attached calculation table and required inputs.

- Attached Charts:**
1. Eagle Mountain Pumped Storage Project Lower Reservoir Filling:
This graph shows the Lower Reservoir storage and water surface elevation just before pumping to the Upper Reservoir and the storage and water surface elevation after pumping to the Upper Reservoir, for each monthly time step.
 2. Eagle Mountain Pumped Storage Project Upper Reservoir Filling:
This graph shows the Upper Reservoir storage and water surface elevation just before pumping from the Lower Reservoir and the storage and water surface elevation after pumping From the Lower Reservoir, for each monthly time step.
 3. Eagle Mountain Pumped Storage Project Groundwater Supply and Lower Reservoir Pumping:
This graph shows the volume of water pumped from the groundwater supply wells to Lower Reservoir, and the water pumped from the Lower Reservoir to the Upper Reservoir, for each monthly time step.

GEI Consultants, Inc.
 080473 Eagle Mountain Pumped Storage Project
 Reservoir Filling
 4/7/2009
 NDM

INPUT DATA


First Filling Month: March
 Pumping Duration Oct-May, t1: 24 hrs
 Pumping Duration Jun-Sept, t2: 12 hrs
 Pumping Rate, Q: 6,000 gpm
 Pumping Rate, Q: 13.37 cfs
 Pumping Rate, Q1: 9679 AF/yr
 Pumping Rate, Q2: 4839 AF/yr
 Evaporation Rate: 7.5 ft/yr

SEEPAGE DATA


LR Seepage at Max. El.: 2765 AF/yr
 LR Seepage at Min. El.: 863 AF/yr
 Begin LR Seepage Pumpback Month: 12
 UR Seepage at Max. El.: 1913 AF/yr
 UR Seepage at Min. El.: 456 AF/yr
 Begin UR Seepage Pumpback Month: 24

Month Count	Month	Water Supply Pipeline Discharge (ac-ft)	Lower Reservoir										Upper Reservoir												
			Starting Elevation (ft)	Starting Storage (ac-ft)	After Filling Storage (ac-ft)	After Filling Elevation (ft)	Evaporation (ac-ft)	Seepage (ac-ft)	Intermediate Storage Volume (ac-ft)	Intermediate Water Surface Elevation (ft)	Percent of Total Capacity (%)	Final Storage Volume (ac-ft)	Final Water Surface Elevation (ft)	Available Pumping Volume to UR (ac-ft)	UR Starting Elevation (ft)	Starting Storage (ac-ft)	Ending Storage (ac-ft)	Volume Pumped (ac-ft)	Ending Elevation (ft)	Evaporation (ac-ft)	Seepage (ac-ft)	Final Storage Volume (ac-ft)	Final Water Surface Elevation (ft)	Percent of Total Capacity (%)	
1	March	807	740.0	0	807	822.6	7	32	768	820.2	3.5%	768	820.2	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
2	April	807	820.2	768	1575	863.3	12	48	1515	860.6	6.9%	1515	860.6	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
3	May	807	860.6	1515	2322	892.0	15	59	2247	890.2	10.3%	2247	890.2	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
4	June	403	890.2	2247	2651	898.7	30	62	2559	896.9	11.7%	2559	896.9	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
5	July	403	896.9	2559	2963	904.7	32	64	2867	902.4	13.1%	2867	902.9	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
6	August	403	902.9	2867	3270	910.2	34	66	3170	908.4	14.5%	3170	908.4	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
7	September	403	908.4	3170	3573	915.4	36	68	3469	913.7	15.8%	3469	913.7	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
8	October	807	913.7	3469	4276	926.7	38	74	4164	925.0	19.0%	4164	925.0	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
9	November	807	925.0	4164	4971	937.0	42	83	4846	935.2	22.1%	4846	935.2	0	2234	0	0.0	0.0	2234.0	0.0	0.0	0.0	0.0	2234.0	0.0%
10	December	807	935.2	4846	5652	946.5	44	92	5516	944.6	25.2%	5469	944.0	47	2234	0	47.4	47.4	2259.0	0.6	8.7	38.1	2257.9	0.2%	
11	January	807	944.0	5469	6275	954.7	47	100	6128	952.8	28.0%	5469	944.0	660	2258	38	697.8	659.8	2297.9	10.0	22.3	665.5	2296.6	3.3%	
12	February	807	944.0	5469	6275	954.7	47	100	6128	952.8	28.0%	5469	944.0	660	2297	666	1325.3	659.8	2319.2	17.5	29.7	1278.0	2317.9	6.4%	
13	March	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2318	1278	2037.4	759.3	2336.9	24.6	35.9	1976.9	2335.5	9.9%	
14	April	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2336	1977	2736.2	759.3	2350.9	30.0	44.7	2661.6	2349.6	13.3%	
15	May	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2350	2662	3420.9	759.3	2361.3	39.5	53.6	3327.8	2360.0	16.6%	
16	June	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2360	3328	3685.0	357.2	2364.8	45.8	56.6	3582.6	2363.5	17.9%	
17	July	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2363	3583	3939.8	357.2	2368.1	47.2	59.4	3833.2	2366.7	19.2%	
18	August	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2367	3833	4190.4	357.2	2371.1	50.1	62.0	4078.3	2369.8	20.4%	
19	September	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2370	4078	4435.5	357.2	2374.0	51.5	64.5	4319.5	2372.6	21.6%	
20	October	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2373	4319	5078.8	759.3	2381.1	55.7	70.6	4952.6	2379.7	24.8%	
21	November	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2380	4953	5711.9	759.3	2387.4	61.4	75.9	5574.5	2386.1	27.9%	
22	December	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2386	5575	6333.8	759.3	2393.1	65.3	80.8	6187.7	2391.8	30.9%	
23	January	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2392	6188	6947.0	759.3	2398.3	72.9	85.2	6788.8	2397.0	33.9%	
24	February	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2397	6789	7548.2	759.3	2403.0	76.5	89.3	7382.3	2401.7	36.9%	
25	March	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2402	7382	8141.6	759.3	2407.6	80.3	0.0	8061.3	2407.0	40.3%	
26	April	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2407	8061	8820.6	759.3	2412.7	82.5	0.0	8738.1	2412.1	43.7%	
27	May	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2412	8738	9497.4	759.3	2417.6	85.6	0.0	9411.8	2417.0	47.1%	
28	June	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2417	9412	9769.1	357.2	2419.5	87.5	0.0	9681.5	2418.9	48.4%	
29	July	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2419	9682	10038.8	357.2	2421.4	88.5	0.0	9950.3	2420.8	49.8%	
30	August	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2421	9950	10307.5	357.2	2423.3	89.7	0.0	10217.8	2422.7	51.1%	
31	September	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2423	10218	10575.1	357.2	2427.4	90.8	0.0	10484.3	2425.6	52.4%	
32	October	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2426	10484	11243.6	759.3	2432.2	94.9	0.0	11150.7	2431.6	55.8%	
33	November	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2432	11151	11910.0	759.3	2439.2	96.1	0.0	11814.0	2438.6	59.1%	
34	December	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2439	11814	12573.3	759.3	2443.3	99.3	0.0	12474.0	2442.7	62.4%	
35	January	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2443	12474	13233.3	759.3	2447.4	101.6	0.0	13131.7	2446.7	65.7%	
36	February	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2447	13132	13891.0	759.3	2451.3	104.7	0.0	13786.4	2450.6	68.9%	
37	March	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2451	13786	14545.7	759.3	2455.0	107.7	0.0	14438.0	2454.4	72.2%	
38	April	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2454	14438	15197.3	759.3	2458.8	109.4	0.0	15087.9	2458.1	75.4%	
39	May	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2458	15088	15847.2	759.3	2462.4	110.9	0.0	15736.4	2461.8	78.7%	
40	June	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2462	15736	16093.6	357.2	2463.8	111.7	0.0	15981.9	2463.2	79.9%	
41	July	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2463	15982	16339.2	357.2	2465.1	112.4	0.0	16226.8	2464.5	81.1%	
42	August	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2465	16227	16584.0	357.2	2466.5	112.4	0.0	16471.7	2465.9	82.4%	
43	September	403	944.0	5469	5872	949.4	46	0	5826	948.8	26.6%	5469	944.0	357	2466	16472	16828.9	357.2	2467.9	113.0	0.0	16715.9	2467.2	83.6%	
44	October	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2467	16716	17475.2	759.3	2471.4	113.7	0.0	17361.5	2470.8	86.8%	
45	November	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2471	17361	18120.8	759.3	2474.9	115.1	0.0	18005.7	2474.3	90.0%	
46	December	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2474	18006	18765.0	759.3	2478.3	116.5	0.0	18648.6	2477.7	93.2%	
47	January	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2478	18649	19407.9	759.3	2481.7	117.1	0.0	19290.8	2481.1	96.5%	
48	February	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	5469	944.0	759	2481	19291	20000.0	759.3	2484.9	118.5	0.0	19881.5	2484.2	99.4%	
49	March	807	944.0	5469	6275	954.7	47	0	6228	954.0	28.4%	6228	954.0	759	2484	19881	20000.0	118.5	2484.9	119.2	0.0	19880.8	2484.2	99.4%	
50	April	807	954.0	6228	7035	964.1	50	0	6985	963.5	31.9%	6985	963.5	1516	2484	19881	20000.0	119.2	2484.9	119.2	0.0	19880.8	2484.2	99.4%	
51	May																								


Eagle Mountain Pumped Storage Project Lower Reservoir Filling



Eagle Mountain Pumped Storage Project Upper Reservoir Filling



Eagle Mountain Pumped Storage Project Groundwater Supply and Lower Reservoir Pumping



Eagle Mountain Pumped Storage Project – Landfill Compatibility

Prepared by: Richard Westmore, P.E., GEI Consultants, Inc. and Ginger Gillin, GEI Consultants, Inc.

April 8, 2009, revised November 24, 2009 and August 13, 2012

The Eagle Mountain Pumped Storage Project will be constructed at the site of the Eagle Mountain Mine, which is no longer operational as an iron mine. Certain features of the pumped storage project will be located on lands that have also been designated for construction of a municipal landfill operation. This memorandum addresses the potential conflicts between the landfill project and the pumped storage project, and provides an assessment of the compatibility of the two projects and how potential conflicts are proposed to be addressed.

Figure 1 presents the pumped storage facilities as they were depicted in the Draft License Application (DLA) dated June 22, 2008. Based on that presentation and comments on the DLA offered by Kaiser Eagle Mountain LLC and Mine Reclamation LLC (the landfill proponents collectively called “Kaiser”) and the Los Angeles County Sanitation District No. 2, FERC requested Eagle Crest Energy Company (ECE) to include in its Final License Application (FLA) documentation to support the conclusion that the landfill project and the pumped storage project are compatible (i.e., neither project would interfere with the construction or operation of the other) as stated in the FLA (see FERC letter dated September 15, 2008).

Comments on the DLA provided by Kaiser in a letter dated September 12, 2008, identify a number of perceived conflicts between the pumped storage project and proposed landfill operations and ancillary facilities of the landfill as follows:

- *Pumped storage facilities would hinder or prohibit development of the truck marshalling yard and portions of the rail yards.*
- *The above-ground transmission line from the underground powerhouse to the Eagle Mountain switchyard would reduce Phase 3 landfill disposal capacity.*
- *The pumped storage project tunnels are aligned below the landfill Phases 2, 3 and 4 and could affect landfill liner integrity.*
- *The use of fine tailings from the mine for lining of the proposed reservoirs to control seepage may conflict with use of these fine tailings for the landfill.*
- *The DLA did not indicate how interference and compatibility issues will be addressed and does not credit the advanced design level (estimated to be 70% complete) for the landfill project relative to re-securing approvals if the landfill designs are changed to accommodate the pumped storage project.*

- *Implementation of the landfill project is part of the overall plan for reclamation of the Eagle Mountain mine site. Implementation of the pumped storage project would not be consistent with the plan of reclamation.*

Based upon the analysis undertaken in response to these comments, design of the pumped storage project has been adjusted to avoid or better manage potential conflicts. This memorandum documents these design changes and presents the supporting analysis to demonstrate compatibility of the two projects. This technical memorandum was initially prepared using landfill design drawings dated December 1993. The 2011 update of this TM was prepared using a landfill design drawing dated October 27, 1997.

Conflicts at Truck Marshalling and Rail Yard

The truck marshalling and rail yard facilities for the landfill are located on the east end of the mine site, as shown on Figures 2 and 4. In the DLA, ECE had indicated that construction staging and lay-down areas required for pumped storage project construction would be located close to the truck marshalling and rail yard. These areas have been relocated to a parcel southwest of the lower reservoir and outside of the proposed landfill, as shown on Figure 2.

Transmission from Powerhouse to Eagle Mountain Switchyard

The DLA showed the low-voltage cable connection from the powerhouse to the Eagle Mountain switchyard as an above-ground line. The transmission lines connecting the transfer station and the switchyard were originally placed above ground through the Phase 3 portion of the landfill project. This layout (from the DLA) is shown in Figure 1. The line would have extended from the top through a vertical cable shaft, above ground to the switchyard. ECE now intends to route the low-voltage cables from the underground powerhouse through the underground powerhouse access tunnel (Figure 2). The transmission cables would only be located above ground from the access tunnel portal near the lower reservoir, along the north rim of the reservoir and adjacent to the proposed water pipeline from the reverse osmosis treatment plant to the lower reservoir. The water treatment facilities have also been relocated from the location shown in the DLA to address concerns raised by the Metropolitan Water District (MWD) of Southern California.

The proposed FLA pumped storage layout, shown on Figure 2 (with proposed finished landfill contours), aligns transmission lines within the access tunnel where they will be protected from moisture, down to near the lower reservoir inlet structure. Here, the lines will run up through a shaft to the ground surface and then continue on to the Eagle Mountain switchyard as overhead transmission lines. Cables will run from each of the four 500/18 kV, 135 MVA transformers through the access tunnel and then above ground on towers to the switchyard. The total length of each cable will be approximately 10,000 feet and each will be rated as indicated for the transformers. The cable runs in the tunnel will be approximately 6,000 feet long and above ground the length will be approximately 4,000 feet. A profile view of this alignment is shown in Figure 3, FLA Layout – Cross Section.

Pumped Storage Tunnel Located Beneath the Landfill

The pumped storage facilities are located primarily underground at depths ranging from 100 to 1,500 feet below the existing ground surface and the proposed bottom liner for the landfill. This relationship is shown on Figure 3, which presents cross-sections showing the relationship between the tunnels and the landfill.

For project planning and to assure conservative estimates of project cost, we have assumed that the water conveyance tunnels for the Pumped Storage Project will be concrete-lined throughout, except for the steel-lined penstock and draft-tube tunnels. Depending on actual

rock conditions and hydraulic requirements determined during final design and construction, it may be feasible to only line the tunnels at certain locations where seepage potentials are high. Much of the deeper portions of the pumped storage project will be located above the current water table, which is at El. 700 throughout most of the project area.

Kaiser's concerns with the water conveyance tunnels relate to the potential for seepage from the tunnels to impact the landfill liner system. The lower pressure tunnel and tailrace tunnel will be located generally 1,000 – 1,500 ft below ground, far beneath the landfill liner. Maximum operating pressure within the main conveyance tunnel will be approximately 700 psi. Final tunnel design will need to carefully consider water pressures acting on the tunnels in both directions when the tunnels are fully pressurized for hydroelectric operations and when they are dewatered for inspection. The final designs for the tunnels and associated tunnel linings will assure that no potential will exist for water from the project to cause uplift loads on the landfill liner system.

Concerns were expressed by LA Sanitation regarding possible buildup of methane gas in the water conveyance tunnels. This is not expected to be an issue due to the continuous "flushing" operations of the tunnel that will not allow for methane gas buildup. Security concerns were also brought up by LA Sanitation. All of the hydroelectric facilities will be below ground, with the exception of the overhead transmission line southwest of the lower reservoir to the Eagle Mountain switchyard. Access to shafts, access tunnels and pressure tunnels will be secured. Above ground facilities will follow the same security requirements as the landfill project for their construction activities and operations.

Potential for Reservoir Seepage to Impact the Landfill

Concerns have been expressed that seepage from the upper reservoir and from the water conveyance tunnels could potentially impact the landfill. Studies by GeoSyntec (1996) indicate that the natural groundwater flow is initially to the south from the area of the central pit. Those studies also indicated that because of fractures in the bedrock, seepage will occur, particularly if the reservoir is not treated to control the rate of seepage. Therefore, the proposed pumped-storage operations may artificially raise groundwater levels in this local area. In the case of consistently high reservoir levels and efficient interconnectivity of bedrock fractures to the south, there is potential that this groundwater could exit on the hillside south of the upper reservoir, rather than staying beneath the existing ground surface and the landfill. With the landfill proposed to be constructed south (down-gradient) of the upper reservoir, this groundwater could potentially encounter the lining of the landfill.

The potential and timing for groundwater to migrate to the southern slope is dependent on the local hydraulic conductivity of the rock and project operations. The fact that the reservoir will be filled and drained on a weekly basis will have a dampening effect on the rate of seepage, however, assuming a hydraulic conductivity of 650 feet per year as suggested by GeoSyntec's work, it appears that seepage could intersect the southern slope under long-term steady-state assumptions.

The following engineering investigation will be undertaken to determine the actual potential for seepage and to control its rate from the upper reservoir:

- The upper reservoir (east pit) will be thoroughly investigated during final design of the pumped-storage project to identify a program for seepage control. This investigation will include geologic mapping to identify the locations and extent of faults, cracks, fractures, and discontinuities in the rock formations and subsurface explorations to characterize the hydraulic conductivity of the rock formations. The mapping will identify locations that will

tend to be the areas where seepage into the bedrock will be most pronounced. A seepage model will then be developed to characterize the flow patterns and potential seepage rates through the bedrock with the upper reservoir at its maximum normal pool (El. 2,485).

Based on the above studies, a seepage control and recovery program will be developed. This program will include:

- Curtain grouting beneath the footprints of the two upper reservoir dams. (Foundation grouting typically is performed for dam safety reasons as a means of uplift control). Grouting and/or shotcrete treatment of the surface features identified in the reservoir as likely locations for seepage to concentrate.
- Installation of monitoring wells and piezometers so that seepage amounts and flow patterns can be understood and addressed as necessary over the long term. (Seepage monitoring wells and recovery wells are described in the technical memorandum on seepage modeling.)
- Installation of seepage recovery well(s) both up-gradient and down-gradient of the landfill prism to maintain groundwater levels below the landfill liner. Seepage recovery wells will be installed at the time of project construction so they will be fully functional if and when seepage from the reservoirs is detected. Phase 1 of the landfill is most proximal to the seepage from the Upper Reservoir. Since the Pumped Storage Project will be constructed before the landfill, the seepage monitoring and recovery wells will be in place before Phase 1 of the landfill is constructed, insuring that the landfill is protected.
- Other measures, such as use of impervious blanketing on portions of the reservoir bottom and sides, may also be used depending on results of detailed studies during final engineering design.

The water surface elevation in the Lower Reservoir will range from elevation 925 and 1,092 feet msl. The landfill is proposed to be constructed in four phases. Phases 1 through 3 will be constructed at elevations above the lower reservoir's maximum water surface elevation and therefore cannot be affected by the seepage from the lower reservoir. Phase 4 is located to the north of the lower reservoir and its foundation finish grade at its lowest point is about 1,040 feet msl (about 800 feet from the reservoir), below the maximum reservoir water surface. This portion of the landfill is being built at least in part over the older alluvium exposed in the eastern portion of the Lower Reservoir, however the area is currently covered by tailing piles so the exact extent of the alluvium is unknown.

The groundwater model covered this area and can approximate the change in the groundwater level beneath this portion of the landfill. Groundwater levels directly beneath the reservoir, if not controlled by seepage recovery wells, would be expected to rise a maximum of 8 feet. Existing monitoring well MW-1 is the closest monitoring well in the alluvium to Phase 4. The groundwater elevation in well MW-1 was 706 feet msl in 1992. The water surface elevation with uncontrolled recharge mounding, projects to be about 714 feet elevation, far below the landfill foundation. With seepage control wells, as shown on Figure 16, groundwater levels are expected to change by about one to four feet.

Use of Fine Tailings for Reservoir Seepage Control

The fine tailings remaining from mine operations may be a good source of lower permeability material for lining the reservoir bottoms to help control seepage. Kaiser intends to use a fairly large quantity of these fine tailings for the landfill. Should a potential shortage develop,

reservoir bottom lining for seepage will be accomplished using the portion of the fine tailings that is not needed by the landfill, coupled with imported materials, materials processed on-site that provide sufficiently low permeability, or combinations of all three. During final design, ECE's consultants will work with Kaiser to understand materials availability and to tailor reservoir design to achieve goals without adversely impacting the landfill.

Resolution of Project Compatibility Issues

ECE is committed to successfully resolving all issues of compatibility between the two projects. ECE has attempted to address capability issues with the assumption that the landfill project will be constructed as configured on the most recent set of drawings we have obtained (dated December 1993) with no adjustments to accommodate the pumped storage project.

Based on an overlay of the two projects (Figure 2) and with changes to the pumped storage facility locations described above (DLA to FLA), it appears that the proposed landfill and proposed pumped storage project have insignificant potential conflicts. During final design of the pumped storage project, ECE is committed to meet with Kaiser to review design and construction issues and resolve concerns over conflicts, with the current 70% level design documentation for the landfill serving as the "baseline".

We believe that the existing and proposed roads within the landfill can be utilized by both projects if construction were to occur simultaneously, although simultaneous construction of both projects is unlikely. This will require close coordination and communications between all parties. The landfill haul roads along the perimeter of the project area could be used to move equipment for pumped storage construction and as construction access roads. The existing internal access road running through the northern portion of landfill Phases 2 and 3 may be used to access the pumped storage surge tank and shaft until the north perimeter maintenance road is completed.

The staging, storage, and office/administrative areas for the pumped storage project construction are proposed to be located to the southwest of the lower reservoir, in close proximity to the landfill project's proposed administration buildings. South of this area is the proposed desalination works. The proposed water treatment plant and brine disposal ponds will be accessed using existing roads, and crossing over the Eagle Mountain railroad track system will not be required.

Kaiser's concern with the impacts of the use of rock resources (more specifically within the area of section 36, T14E, R3N) does not appear to be a conflict between the two projects. This area along with other rock pile areas, will not limit access, construction or maintenance for either project. There are no proposed pumped storage project facilities planned to be located on or near this area.

Landfill Use of the East Pit

Landfill Phases 1 through 4 will extend over a period of 85 years, under Kaiser's current projections. In order to operate the landfill for more than 85 years, Phase 5 would be required. The lower reservoir for the pumped storage project (using the East Pit) overlaps with Phase 5. However, the Eagle Mountain landfill was approved by Riverside County for a 50-year operation, and Phase 5 is not a part of the County-approved landfill project. Therefore, there is no conflict between the landfill and the pumped storage project over the use of the East Pit unless and until Phase 5 of the landfill is approved.

The operating license for the pumped storage project from FERC is also proposed to be for a period of 50 years, at which point the project will either be relicensed or retired. Therefore, it is

fair to leave the decision of the best use of the east pit to a future generation if relicensing is proposed and a conflict with future landfill operations is encountered.

Landfill Timing Compatibility Issues

The timing of construction of the landfill project is not known at this time. Under present conditions, construction of the pumped storage project is very likely to be completed before the start of the landfill project and construction of facilities required to support landfill operations.

If all approvals for the landfill were resolved in 2012, then construction of support facilities for the landfill could begin when designs were finalized, and commercial landfill operations could theoretically begin as early as 2016. However, we believe this is an unlikely scenario based upon the recent Ninth Circuit Court decision remanding the legal dispute for further review, review of current and projected demand for landfill capacity in southern California, the bankruptcy filing of Mine Reclamation, LLC, and the recent opening of the Mesquite Regional Landfill. Therefore, as discussed in greater depth below, it is highly unlikely that the landfill project and the pumped storage project construction periods will overlap.

One component of the landfill proposal is an exchange of lands between Kaiser and the Bureau of Land Management (“BLM”). Approval of the landfill is contingent upon Kaiser being the fee owner of the property (See Development Agreement No. 64 Section 2.2; California Integrated Waste Management Board resolution 1999-624 (revised); and California Integrated Waste Management Board, Board Meeting Summary December 14-15, 1999). Therefore, until the land exchange is effectuated, the landfill is not a formally approved operation.

On September 25, 1997, BLM issued a Record of Decision approving the land exchange between itself and Kaiser, which was appealed to the Interior Board of Land Appeals (“IBLA”). On September 20, 1999 the IBLA issued an order denying the appeal and affirming the land exchange. This decision was subsequently appealed to the District Court who decided that “*The subject land exchange and grants of rights of way and reversionary interest are set aside and the Defendants are enjoined from engaging in any action that would change the character and use of the exchanged properties...*” until they complied with the changes requested by the decision. *Donna Charpiet et al., v. United States Dept. of Interior et al.*, ED CV99-0454 RT (Mcx) (Sept. 20, 2005); *Nat’l Parks and Conservation Assoc., v. Bureau of Land Mgmt, et al.*, ED CV 00-0041 RT (Mcx) (Sept. 20, 2005).

This case was appealed to the Ninth Circuit Court of Appeals, and oral argument was heard on December 6, 2007. A decision on the case was published November 10, 2009, and the case was remanded for further proceedings consistent with the Ninth Circuit opinion. The U.S. Supreme Court declined to hear Kaiser’s appeal of the Ninth Circuit decision. According to Kaiser’s Quarterly Report to the Securities and Exchange Commission (dated May 2011), “the adverse federal litigation jeopardizes the viability of the current Landfill project. In addition such decision may adversely impact the agreement to sell the Landfill Project to the [Los Angeles County Sanitation] District, including termination of the agreement.”

According to the Quarterly Report, “If the land exchange litigation is not ultimately favorably resolved and/or the Company cannot otherwise cure various alleged title and other closing issues in a timely fashion, then the [Los Angeles Sanitation] District’s purchase of the Landfill Project would not be completed and the Company might have to abandon the Eagle Mountain Landfill Project and its investment in MRC. The adverse federal litigation materially increases the possibility of such a scenario.”

The Quarterly Report additionally states that, "With regard to the Landfill Project, we are evaluating the time and money necessary to pursue a fix through the BLM. This fix process would ultimately include the federal courts reviewing the adequacy of the fix. A fix through BLM and the likely court review would take several years once the fix is formally initiated. Due to the results of the federal litigation and if there is not a successful fix through the BLM, it is a possible [sic] that there ultimately may not be a viable landfill project."

On October 31, 2011 Mine Reclamation LLC, filed a voluntary petition for relief under Chapter 11 of the United States Bankruptcy Code in the United States Bankruptcy Court for Central District of California, Riverside Division, bankruptcy case number 6:11-bk-43596 . According to Form 8-K filed by Kaiser Ventures with the Security and Exchange Commission, dated October 31, 2011, Mine Reclamation will continue to operate its business as a "debtor in possession" under the jurisdiction of the Bankruptcy Court and in accordance with the applicable provisions of the Bankruptcy Code, Rules and orders of the Bankruptcy Court. Kaiser Ventures LLC owns approximately 84.247% of Mine Reclamation. In a press release issued on October 31, 2011, Mine Reclamation stated that "the future of the [Eagle Mountain] site and its potential for job creation and funding for Riverside County and the future for Kaiser's retired steel workers are all more uncertain than ever."

Therefore, while it is not possible to predict the length of time needed for future proceedings, it is clear that several years will be needed to resolve the landfill litigation. In the event that the land exchange is confirmed and all the necessary landfill approvals are issued, construction of the landfill could commence. A timeline for the start of construction is unknown, but is unlikely to occur before 2015 under the most optimistic scenario. Based on the experience of the Mesquite Regional Landfill, construction could take three years before the landfill would be ready to accept waste. Therefore, landfill operations are unlikely to commence prior to 2018.

However, the construction and operation of the Eagle Mountain Landfill may be further delayed due to a lack of demand for additional landfill capacity in southern California at this time. The Mesquite Regional Landfill (MRL) opened for business in 2009. The MRL will provide capacity for approximately 600 million tons of solid waste and 100 years of operation at a maximum of 20,000 tons per day. In 2009, when the MRL became operational, the Los Angeles County Sanitation District's projections show there will be between 10,000 and 16,000 tons per day of excess landfill capacity in Los Angeles County. Although this means there is no immediate need to export trash to the MRL, the Sanitation Districts are proposing to conduct a 300 tons per day operation at the MRL. The projections continue to show excess landfill capacity in Los Angeles County until late 2013, when the Puente Hills Landfill will be closed permanently. According to the projections, there may still be some excess capacity at other landfills in 2013. However, there could be an overall shortfall of 4,500 tons per day in 2013 (Sanitation Districts of Los Angeles County, <http://www.mrlf.org/index.php?pid=101>, accessed February 18, 2009).

If the entire 4,500 tons per day shortfall from Los Angeles County is transported to the MRL facility, there would still be capacity for an additional 15,500 tons per day from other sources at the MRL facility. Therefore, there is enough capacity at the MRL facility to serve southern California's waste disposal needs for decades to come. For these reasons, construction of the landfill is unlikely to commence in the foreseeable future. On this basis, we conclude that the Pumped Storage Project is likely to be built and operational prior to initiation of landfill construction at Eagle Mountain.

Post Construction Operations

During normal operations after construction, the pumped storage project will require a relatively small work force for routine operations and maintenance. Daily traffic patterns would likely be as follows:

- Day and night shift small truck traffic on Kaiser Road into and out of the underground powerhouse access tunnel portal at the lower reservoir.
- Day shift traffic on Kaiser Road into and out of the water treatment facility area.
- Once or twice per day daytime small truck traffic on the lower reservoir perimeter road to inspect the inlet/outlet structure
- Once or twice per day daytime small truck traffic on the access road along the landfill to the upper reservoir and the surge shaft location for inspection of the upper reservoir dams inlet/outlet structure, and the surge control facilities.

During major maintenance activities (once per year and possibly less frequently), larger trucks and construction-type equipment will be traveling on the same project area roads as indicated above. These activities, although relatively infrequent, can be readily coordinated in advance with Kaiser so that landfill operations are not impacted.

As part of the design coordination process between ECE and Kaiser, planning for large and small vehicle traffic and road design should be addressed. Operation of the landfill will be large vehicle and equipment intensive and there will be times when large vehicles and equipment must be mobilized. Roads will be wide enough to accommodate simultaneous road use for both projects. Signage and safety management measures will be designed to address both projects.

January 2011 update: Response to Additional Comments from Kaiser and Others in Review of the July 2010 Draft Environmental Impact Report.

In June 2010, the Draft Environmental Impact Report (DEIR) on the Eagle Mountain Pumped Storage Project was issued by the State Water Board under the California Environmental Quality Act (CEQA) process. In a letter dated October 7, 2010, Kaiser provided additional comments on the Project related to the potentials for conflicts between the Project and the Landfill. ECE's position on these conflicts and proposals to address potential conflicts are summarized below:

Kaiser concern: The proposed construction road to the shaft crosses Phases 2 and 3 of the Landfill.

Response: The existing access road will be used to access the pumped storage surge tank and shaft. However, in the event that the landfill is constructed, a north perimeter access road will be constructed by the landfill for landfill access. The proposed Project will then utilize the north perimeter maintenance road for access to the surge tank and shaft to avoid impacts to the landfill Phases 2 and 3.

Kaiser concern: The Project's upper reservoir outlet channel may conflict with Phase 1 of the Landfill.

Response: The existing natural drainage downstream of the existing Central Pit will accept any flood spills or other releases from the upper reservoir. ECE has assumed that this drainage would not be within the "footprint" of the proposed Landfill. At the present time, with the scale and level of design detail available for both projects, it is not possible to clearly

identify conflicts that may potentially exist. As designs for both projects progress, it will be very important to determine the westerly extent of the Phase 1 Landfill toe and to see whether or not it will extend into the existing drainage, which will be improved to handle the very infrequent outflows from the upper reservoir. If the Landfill toe will extend into this drainage channel, it will be necessary to adjust the channel alignment and to assure that the Landfill toe is protected against erosion.

Kaiser concern: It appears that the upper reservoir dam toe extends into Phase 1 of the Landfill.

Response: The selected upper reservoir south dam axis is tentatively located to minimize the amount of material required to construct the dam, based on available topographic mapping. The dam axis can be adjusted during final project planning and design to avoid any potential for conflict. This adjustment would generally be to the north (upstream) of the currently proposed dam axis a distance of 150 to 200 feet. The “footprint” of the upper reservoir area would not be increased.

Kaiser concern: The transmission line from access tunnel portal to the switchyard is above ground and extends through a portion of Landfill Phase 4.

Response: The current alignment of the transmission line from the access tunnel portal to the switchyard can be modified to avoid Phase 4 of the Landfill, with little impact on the Project. This revised alignment will be developed during final project planning and design, and discussed with Kaiser to be sure of compatibility.

Kaiser concern: Certain proposed Project facilities could interfere with the planned Landfill rail yard and RO/Admin facilities for the Project.

Response: ECE developed Figure 4 using the most-current landfill design drawings which are publically available (dated October 1997). Based on this project layout, ECE understands that the railyard and operations center would be located on the east side of the Landfill. However, other, older drawings from the proposed Specific Plan show the railyard to be located south of the East Pit for the early years of landfill development. The ideal location for the proposed Project switchyard and RO facilities and structures is the one currently shown on the Project drawings. Therefore, it appears that further discussions between ECE and landfill interests will be required as final planning and design of both projects proceeds.

August 2012 update: Response to Additional Comments from Kaiser on Draft Water Quality Certification

Kaiser concern: All five phases of the landfill were covered in the Landfill EIR/EIS and received the necessary approvals from Riverside County.

Response: On January 14, 2000, the Local Solid Waste Management Enforcement Agency for Riverside County issued a Solid Waste Facility Permit 33-AA-0228 for the Eagle Mountain Landfill. The California Integrated Water Management Board concurred with the issuance of Solid Waste Facility Permit No. 33-AA-0228 (Resolution 1999-624 Revised). The Solid Waste Facility Permit issued to the Eagle Mountain Landfill specifies a “permitted area” of 4,654 acres, a “disposal area” of 1,864 acres, and a design capacity for Phases 1 – 4 of 559,963,680 cubic yards. These specifications match the area and capacity of landfill Phases 1 – 4, but do not include landfill Phase 5. Therefore, Landfill Phase 5 is not included in the Solid Waste Facility permit.

The Waste Discharge Requirements (WDR) Order 99-061 issued by the Colorado River Regional Water Quality Control Board states that development of the landfill will, “Begin with Phase 1 and end with Phase 4.” The WDR further states that, “The 1,868 acre landfill will be

constructed in four contiguous phases, containing 13 sequences... The approximate total airspace of the site is 660 million cubic yards, which will provide waste capacity of about 561 million cubic yards during the 84 year life of projected landfill life." The WDR specifies the construction sequencing of the landfill (starting with Phase 1 and ending with Phase 4) and requires the written approval of the Executive Director for significant deviations in sequencing. Attachment 8 of the WDR is the Landfill Phasing Plan which shows only Phases 1 – 4 of the landfill. No provision is made in the WDR for construction of Phase 5 of the landfill.


The Report of Disposal Site Information (RDSI) prepared by GeoSyntec in August 1999 and filed with the Regional Water Quality Control Board states that "The proposed landfill operation addressed in this RDSI occurs in four large contiguous phases. A future fill area designated as Phase 5 and evaluated in the EIR/EIS is also indicated in the RDSI for conceptual purposes. The permitting for Phase 5 future fill area will be accomplished at a later date under a separate document from this RDSI... Total estimated capacity of the landfill area (Phases 1 – 4) is approximately 560,700,000 cubic yards which will accommodate the disposal of 462,500,000 cubic yards of waste." The projected life of Phases 1 - 4 is 84 years. No later permitting was accomplished for Phase 5 of the landfill.

The Development Agreement No. 64 between Riverside County and Mine Reclamation Corporation specifies the term of the agreement, "The County has further approved the term of this Agreement for the period beginning on the Effective Date and continuing until November 30, 2088, and the parties have agreed to stage the term. Specifically, the parties have agreed to initial term of fifty (50) years from the Effective Date, although there will be additional landfill capacity available at the expiration of the initial term of this Agreement...**in no event shall the term of this agreement be extended under this Section 2.3.1 beyond November 30, 2088.**" (emphasis added). As described above, the projected life of Phases 1 - 4 is 84 years. Therefore, even if the landfill were to begin operation this year, which is not possible for the reasons described above, the Development Agreement will expire prior to the completion of Phase 4.

Therefore, we conclude that Phase 5 of the Eagle Mountain Landfill is not a component of the project as approved by Riverside County and the Regional Water Quality Control Board, and there is not sufficient time remaining in the Development Agreement to allow for construction of any phases beyond Phase 4.

Conclusion

Based on GEI's review of the landfill design, as currently documented, we are of the opinion that both the proposed pumped storage project and the proposed landfill project (Phases 1 – 4) can be constructed and operated without significant conflicts. As final design on both projects progresses, potential conflicts that relate to road use and traffic management will be assessed and planned for.



NOTES:
 1. PLAN BASED ON MAP PREPARED BY
 C.M. ENGINEERING ASSOCIATES,
 SAN BERNARDINO, CA.

P:\080470 Eagle Mountain Landfill Compatibility\APRIL 2009 DLA Layout.dwg Apr 2009

THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF GEI CONSULTANTS, INC. AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF GEI CONSULTANTS, INC.

NO.	DATE	ISSUE/REVISION	DES	DRN	CHK	APP




EAGLE CREST ENERGY COMPANY
 GEI PROJECT 080473

EAGLE MOUNTAIN PUMPED STORAGE PROJECT

**LANDFILL COMPATIBILITY PLAN
 DLA LAYOUT**

FIGURE NO.
1
 SHEET NO.
 1 of 3



NOTES:
 1. PLAN BASED ON MAP PREPARED BY C.M. ENGINEERING ASSOCIATES, SAN BERNARDINO, CA.

P:\080470 Eagle\080472 Landfill\080472.dwg Apr 2009

THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF GEI CONSULTANTS, INC. AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF GEI CONSULTANTS, INC.

NO.	DATE	ISSUE/REVISION	DES	DRN	CHK	APP





EAGLE CREST ENERGY COMPANY
 GEI PROJECT 080473

EAGLE MOUNTAIN PUMPED STORAGE PROJECT

**LANDFILL COMPATIBILITY PLAN
 FLA LAYOUT**

FIGURE NO.
2
 SHEET NO.
 2 of 3



CROSS SECTION ALONG WATER CONDUITS

NOTES:

- 1. UNDEFINED LANDFILL CONTOURS WERE ASSUMED TO FOLLOW DEFINED CONTOURS AND TO COME INTO ALIGNMENT WITH THE EXISING GROUND SURFACE.

NOTES:

- 1. PLAN BASED ON MAP PREPARED BY C.M. ENGINEERING ASSOCIATES, SAN BERNARDINO, CA.



THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF GEI CONSULTANTS, INC. AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF GEI CONSULTANTS, INC.

NO.	DATE	ISSUE/REVISION	DES	DRN	CHK	APP



EAGLE CREST ENERGY COMPANY


GEI PROJECT 080473

EAGLE MOUNTAIN PUMPED STORAGE PROJECT

LANDFILL COMPATIBILITY FLA LAYOUT - CROSS SECTION

FIGURE NO. **3**
SHEET NO. 3 of 3

Z:\Projects\080472_Eagle\Mfn_fromDenver\Figure_C_forLF_2.mxd SET
15-Jun-2011



Pumped Storage Project Facilities	Landfill Facilities
○ Mitigation Monitoring Network Well	■ Building
--- Water Supply Line	■ Reservoir
▬▬▬ Transmission Route	● Water Tank
▭ Project Boundary	▭ Landfill Project Boundary



Source: Landfill Features from Eagle Mountain Landfill and Recycling Center Site, Report of Disposal Site Information, Site Development Plan, Prepared for Mine Reclamation Corporation by C-M Engineering Associates, Drawing 2 of 43, Feb 1994, updated 10/27/97.

Eagle Crest Energy Company
Eastern Riverside County, California



OVERLAY OF LANDFILL PROJECT (1997 UPDATE) AND PUMPED STORAGE PROJECT (DEIS)
June 2011
Figure 4, Sheet 4 of 4